

# PIC16F627A/628A/648A Data Sheet

Flash-Based 8-Bit CMOS Microcontrollers with nanoWatt Technology

#### Note the following details of the code protection feature on Microchip devices:

- Microchip products meet the specification contained in their particular Microchip Data Sheet.
- Microchip believes that its family of products is one of the most secure families of its kind on the market today, when used in the intended manner and under normal conditions.
- There are dishonest and possibly illegal methods used to breach the code protection feature. All of these methods, to our knowledge, require using the Microchip products in a manner outside the operating specifications contained in Microchip's Data Sheets. Most likely, the person doing so is engaged in theft of intellectual property.
- · Microchip is willing to work with the customer who is concerned about the integrity of their code.
- Neither Microchip nor any other semiconductor manufacturer can guarantee the security of their code. Code protection does not mean that we are guaranteeing the product as "unbreakable."

Code protection is constantly evolving. We at Microchip are committed to continuously improving the code protection features of our products. Attempts to break Microchip's code protection feature may be a violation of the Digital Millennium Copyright Act. If such acts allow unauthorized access to your software or other copyrighted work, you may have a right to sue for relief under that Act.

Information contained in this publication regarding device applications and the like is intended through suggestion only and may be superseded by updates. It is your responsibility to ensure that your application meets with your specifications. No representation or warranty is given and no liability is assumed by Microchip Technology Incorporated with respect to the accuracy or use of such information, or infringement of patents or other intellectual property rights arising from such use or otherwise. Use of Microchip's products as critical components in life support systems is not authorized except with express written approval by Microchip. No licenses are conveyed, implicitly or otherwise, under any intellectual property rights.

#### **Trademarks**

The Microchip name and logo, the Microchip logo, Accuron, dsPIC, KEELOQ, MPLAB, PIC, PICmicro, PICSTART, PRO MATE, PowerSmart and rfPIC are registered trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

AmpLab, FilterLab, microID, MXDEV, MXLAB, PICMASTER, SEEVAL, SmartShunt and The Embedded Control Solutions Company are registered trademarks of Microchip Technology Incorporated in the U.S.A.

Application Maestro, dsPICDEM, dsPICDEM.net, dsPICworks, ECAN, ECONOMONITOR, FanSense, FlexROM, fuzzyLAB, In-Circuit Serial Programming, ICSP, ICEPIC, Migratable Memory, MPASM, MPLIB, MPLINK, MPSIM, PICkit, PICDEM, PICDEM.net, PICtail, PowerCal, PowerInfo, PowerMate, PowerTool, rfLAB, Select Mode, SmartSensor, SmartTel and Total Endurance are trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

Serialized Quick Turn Programming (SQTP) is a service mark of Microchip Technology Incorporated in the U.S.A.

All other trademarks mentioned herein are property of their respective companies.

© 2004, Microchip Technology Incorporated, Printed in the U.S.A., All Rights Reserved.

Printed on recycled paper.

QUALITY MANAGEMENT SYSTEM

CERTIFIED BY DNV

ISO/TS 16949:2002 ===

Microchip received ISO/TS-16949:2002 quality system certification for its worldwide headquarters, design and wafer fabrication facilities in Chandler and Tempe, Arizona and Mountain View, California in October 2003. The Company's quality system processes and procedures are for its PICmicro® 8-bit MCUs, KEELoo® code hopping devices, Serial EEPROMs, microperipherals, nonvolatile memory and analog products. In addition, Microchip's quality system for the design and manufacture of development systems is ISO 9001:2000 certified.



# 18-pin Flash-Based 8-Bit CMOS Microcontrollers with nanoWatt Technology

- · Operating speeds from DC 20 MHz
- · Interrupt capability
- 8-level deep hardware stack
- · Direct, Indirect and Relative Addressing modes
- · 35 single word instructions
  - All instructions single cycle except branches

#### **Special Microcontroller Features:**

- Internal and external oscillator options
  - Precision Internal 4 MHz oscillator factory calibrated to ±1%
  - Low Power Internal 37 kHz oscillator
  - External Oscillator support for crystals and resonators.
- · Power saving Sleep mode
- Programmable weak pull-ups on PORTB
- Multiplexed Master Clear/Input-pin
- Watchdog Timer with independent oscillator for reliable operation
- · Low voltage programming
- In-Circuit Serial Programming<sup>™</sup> (via two pins)
- Programmable code protection
- · Brown-out Reset
- Power-on Reset
- Power-up Timer and Oscillator Start-up Timer
- Wide operating voltage range. (2.0 5.5V)
- · Industrial and extended temperature range
- High Endurance Flash/EEPROM Cell
  - 100,000 write Flash endurance
  - 1.000.000 write EEPROM endurance
  - 100 year data retention


- · Standby Current:
  - 100 nA @ 2.0V, typical
- Operating Current:
  - 12 μA @ 32 kHz, 2.0V, typical
  - 120 μA @ 1 MHz, 2.0V, typical
- · Watchdog Timer Current
  - 1 μA @ 2.0V, typical
- Timer1 oscillator current:
  - 1.2 μA @ 32 kHz, 2.0V, typical
- · Dual Speed Internal Oscillator:
  - Run-time selectable between 4 MHz and 37 kHz
  - 4 μs wake-up from Sleep, 3.0V, typical

#### **Peripheral Features:**

- 16 I/O pins with individual direction control
- · High current sink/source for direct LED drive
- · Analog comparator module with:
  - Two analog comparators
  - Programmable on-chip voltage reference (VREF) module
  - Selectable internal or external reference
  - Comparator outputs are externally accessible
- Timer0: 8-bit timer/counter with 8-bit programmable prescaler
- Timer1: 16-bit timer/counter with external crystal/ clock capability
- Timer2: 8-bit timer/counter with 8-bit period register, prescaler and postscaler
- · Capture, Compare, PWM module
  - 16-bit Capture/Compare
  - 10-bit PWM
- Addressable Universal Synchronous/Asynchronous Receiver/Transmitter USART/SCI

Device	Program Memory	Data N	lemory	1/0	ССР	USART	Comparators	Timers	
Device	Flash (words)	SRAM (bytes)	EEPROM (bytes)	1/0	(PWM)	USAKI	Comparators	8/16-bit	
PIC16F627A	1024	224	128	16	1	Υ	2	2/1	
PIC16F628A	2048	224	128	16	1	Υ	2	2/1	
PIC16F648A	4096	256	256	16	1	Υ	2	2/1	

#### **Pin Diagrams**



#### **Table of Contents**

1.0	General Description	5
2.0	PIC16F627A/628A/648A Device Varieties	7
3.0	Architectural Overview	9
4.0	Memory Organization	
5.0	VO Ports	
6.0	Timer0 Module	. 45
7.0	Timer1 Module	. 48
8.0	Timer2 Module	
9.0	Capture/Compare/PWM (CCP) Module	. 55
10.0	Comparator Module	. 61
11.0	Voltage Reference Module	. 67
12.0	Universal Synchronous Asynchronous Receiver Transmitter (USART) Module	. 69
13.0	Data EEPROM Memory	. 89
	Special Features of the CPU	
15.0	Instruction Set Summary	111
	Development Support	
17.0	Electrical Specifications	131
	DC and AC Characteristics Graphs and Tables	
19.0	Packaging Information	149

#### TO OUR VALUED CUSTOMERS

It is our intention to provide our valued customers with the best documentation possible to ensure successful use of your Microchip products. To this end, we will continue to improve our publications to better suit your needs. Our publications will be refined and enhanced as new volumes and updates are introduced.

If you have any questions or comments regarding this publication, please contact the Marketing Communications Department via E-mail at **docerrors@mail.microchip.com** or fax the **Reader Response Form** in the back of this data sheet to (480) 792-4150. We welcome your feedback.

#### **Most Current Data Sheet**

To obtain the most up-to-date version of this data sheet, please register at our Worldwide Web site at:

http://www.microchip.com

You can determine the version of a data sheet by examining its literature number found on the bottom outside corner of any page. The last character of the literature number is the version number, (e.g., DS30000A is version A of document DS30000).

#### Errata

An errata sheet, describing minor operational differences from the data sheet and recommended workarounds, may exist for current devices. As device/documentation issues become known to us, we will publish an errata sheet. The errata will specify the revision of silicon and revision of document to which it applies.

To determine if an errata sheet exists for a particular device, please check with one of the following:

- Microchip's Worldwide Web site; http://www.microchip.com
- Your local Microchip sales office (see last page)
- The Microchip Corporate Literature Center; U.S. FAX: (480) 792-7277

When contacting a sales office or the literature center, please specify which device, revision of silicon and data sheet (include literature number) you are using.

#### **Customer Notification System**

Register on our web site at www.microchip.com/cn to receive the most current information on all of our products.

NOTES:

#### 1.0 GENERAL DESCRIPTION

The PIC16F627A/628A/648A are 18-Pin Flash-based members of the versatile PIC16CXX family of low cost, high performance, CMOS, fully-static, 8-bit microcontrollers.

All PICmicro<sup>®</sup> microcontrollers employ an advanced RISC architecture. The PIC16F627A/628A/648A have enhanced core features, eight-level deep stack, and multiple internal and external interrupt sources. The separate instruction and data buses of the Harvard architecture allow a 14-bit wide instruction word with the separate 8-bit wide data. The two-stage instruction pipeline allows all instructions to execute in a single-cycle, except for program branches (which require two cycles). A total of 35 instructions (reduced instruction set) are available, complemented by a large register set.

PIC16F627A/628A/648A microcontrollers typically achieve a 2:1 code compression and a 4:1 speed improvement over other 8-bit microcontrollers in their class.

PIC16F627A/628A/648A devices have integrated features to reduce external components, thus reducing system cost, enhancing system reliability and reducing power consumption.

The PIC16F627A/628A/648A has 8 oscillator configurations. The single-pin RC oscillator provides a low cost solution. The LP oscillator minimizes power consumption, XT is a standard crystal, and INTOSC is a self-contained precision two-speed internal oscillator. The

HS is for High-Speed crystals. The EC mode is for an external clock source.

The Sleep (Power-down) mode offers power savings. Users can wake-up the chip from Sleep through several external interrupts, internal interrupts and Resets.

A highly reliable Watchdog Timer with its own on-chip RC oscillator provides protection against software lock-up.

Table 1-1 shows the features of the PIC16F627A/628A/648A mid-range microcontroller families.

A simplified block diagram of the PIC16F627A/628A/648A is shown in Figure 3-1.

The PIC16F627A/628A/648A series fits in applications ranging from battery chargers to low power remote sensors. The Flash technology makes customizing application programs (detection levels, pulse generation, timers, etc.) extremely fast and convenient. The small footprint packages makes this microcontroller series ideal for all applications with space limitations. Low cost, low power, high performance, ease of use and I/O flexibility make the PIC16F627A/628A/648A very versatile.

#### 1.1 Development Support

The PIC16F627A/628A/648A family is supported by a full-featured macro assembler, a software simulator, an in-circuit emulator, a low cost in-circuit debugger, a low cost development programmer and a full-featured programmer. A Third Party "C" compiler support tool is also available.

TABLE 1-1: PIC16F627A/628A/648A FAMILY OF DEVICES

		PIC16F627A	PIC16F628A	PIC16F648A	PIC16LF627A	PIC16LF628A	PIC16LF648A
Clock	Maximum Frequency of Operation (MHz)	20	20	20	4	4	4
	Flash Program Memory (words)	1024	2048	4096	1024	2048	4096
Memory	RAM Data Memory (bytes)	224	224	256	224	224	256
	EEPROM Data Memory (bytes)	128	128	256	128	128	256
	Timer module(s)	TMR0, TMR1, TMR2					
	Comparator(s)	2	2	2	2	2	2
Peripherals	Capture/Compare/ PWM modules	1	1	1	1	1	1
	Serial Communications	USART	USART	USART	USART	USART	USART
	Internal Voltage Reference	Yes	Yes	Yes	Yes	Yes	Yes
	Interrupt Sources	10	10	10	10	10	10
	I/O Pins	16	16	16	16	16	16
Features	Voltage Range (Volts)	3.0-5.5	3.0-5.5	3.0-5.5	2.0-5.5	2.0-5.5	2.0-5.5
	Brown-out Reset	Yes	Yes	Yes	Yes	Yes	Yes
	Packages	18-pin DIP, SOIC, 20-pin SSOP, 28-pin QFN					

All PICmicro® Family devices have Power-on Reset, selectable Watchdog Timer, selectable Code Protect and high I/O current capability. All PIC16F627A/628A/648A Family devices use serial programming with clock pin RB6 and data pin RB7.

NOTES:

# 2.0 PIC16F627A/628A/648A DEVICE VARIETIES

A variety of frequency ranges and packaging options are available. Depending on application and production requirements, the proper device option can be selected using the information in the PIC16F627A/628A/648A Product Identification System, at the end of this data sheet. When placing orders, please use this page of the data sheet to specify the correct part number.

#### 2.1 Flash Devices

Flash devices can be erased and re-programmed electrically. This allows the same device to be used for prototype development, pilot programs and production.

A further advantage of the electrically erasable Flash is that it can be erased and reprogrammed in-circuit, or by device programmers, such as Microchip's PICSTART® Plus, or PRO MATE® II programmers.

# 2.2 Quick-Turnaround-Production (QTP) Devices

Microchip offers a QTP Programming Service for factory production orders. This service is made available for users who chose not to program a medium to high quantity of units and whose code patterns have stabilized. The devices are standard Flash devices but with all program locations and configuration options already programmed by the factory. Certain code and prototype verification procedures apply before production shipments are available. Please contact your Microchip Technology sales office for more details.

#### 2.3 Serialized Quick-Turnaround-Production (SQTP<sup>SM</sup>) Devices

Microchip offers a unique programming service where a few user-defined locations in each device are programmed with different serial numbers. The serial numbers may be random, pseudo-random or sequential.

Serial programming allows each device to have a unique number, which can serve as an entry-code, password or ID number.

© 2004 Microchip Technology Inc.

Preliminary

DS40044B-page 7

NOTES:

#### 3.0 ARCHITECTURAL OVERVIEW

The high performance of the PIC16F627A/628A/648A family can be attributed to a number of architectural features commonly found in RISC microprocessors. To begin with, the PIC16F627A/628A/648A uses a Harvard architecture, in which program and data are accessed from separate memories using separate busses. This improves bandwidth over traditional Von Neumann architecture where program and data are fetched from the same memory. Separating program and data memory further allows instructions to be sized differently than 8-bit wide data word. Instruction opcodes are 14-bits wide making it possible to have all single word instructions. A 14-bit wide program memory access bus fetches a 14-bit instruction in a single cycle. A two-stage pipeline overlaps fetch and execution of instructions. Consequently, all instructions (35) execute in a single-cycle (200 ns @ 20 MHz) except for program branches.

Table 3-1 lists device memory sizes (Flash, Data and EEPROM).

TABLE 3-1: DEVICE MEMORY LIST

	Memory								
Device	Flash Program	RAM Data	EEPROM Data						
PIC16F627A	1024 x 14	224 x 8	128 x 8						
PIC16F628A	2048 x 14	224 x 8	128 x 8						
PIC16F648A	4096 x 14	256 x 8	256 x 8						
PIC16LF627A	1024 x 14	224 x 8	128 x 8						
PIC16LF628A	2048 x 14	224 x 8	128 x 8						
PIC16LF648A	4096 x 14	256 x 8	256 x 8						

The PIC16F627A/628A/648A can directly or indirectly address its register files or data memory. All Special Function Registers (SFR), including the program counter, are mapped in the data memory. The PIC16F627A/628A/648A have an orthogonal (symmetrical) instruction set that makes it possible to carry out any operation, on any register, using any Addressing mode. This symmetrical nature and lack of 'special optimal situations' make programming with the PIC16F627A/628A/648A simple yet efficient. In addition, the learning curve is reduced significantly.

The PIC16F627A/628A/648A devices contain an 8-bit ALU and working register. The ALU is a general purpose arithmetic unit. It performs arithmetic and Boolean functions between data in the working register and any register file.

The ALU is 8-bit wide and capable of addition, subtraction, shift and logical operations. Unless otherwise mentioned, arithmetic operations are two's complement in nature. In two-operand instructions, typically one operand is the working register (W register). The other operand is a file register or an immediate constant. In single operand instructions, the operand is either the W register or a file register.

The W register is an 8-bit working register used for ALU operations. It is not an addressable register.

Depending on the instruction executed, the ALU may affect the values of the Carry (C), Digit Carry (DC), and Zero (Z) bits in the Status Register. The C and DC bits operate as a Borrow and Digit Borrow out bit, respectively, bit in subtraction. See the SUBLW and SUBWF instructions for examples.

A simplified block diagram is shown in Figure 3-1, and a description of the device pins in Table 3-2.

Two types of data memory are provided on the PIC16F627A/628A/648A devices. Nonvolatile EEPROM data memory is provided for long term storage of data such as calibration values, look up table data, and any other data which may require periodic updating in the field. These data are not lost when power is removed. The other data memory provided is regular RAM data memory. Regular RAM data memory is provided for temporary storage of data during normal operation. Data are lost when power is removed.

FIGURE 3-1: BLOCK DIAGRAM




TABLE 3-2: PIC16F627A/628A/648A PINOUT DESCRIPTION

Name	Function	Input Type	Output Type	Description		
RA0/AN0	RA0	ST	CMOS	Bidirectional I/O port		
	AN0	AN	_	Analog comparator input		
RA1/AN1	RA1	ST	CMOS	Bidirectional I/O port		
	AN1	AN	_	Analog comparator input		
RA2/AN2/VREF	RA2	ST	CMOS	Bidirectional I/O port		
	AN2	AN	_	Analog comparator input		
	VREF	_	AN	VREF output		
RA3/AN3/CMP1	RA3	ST	CMOS	Bidirectional I/O port		
	AN3	AN	_	Analog comparator input		
	CMP1	_	CMOS	Comparator 1 output		
RA4/T0CKI/CMP2	RA4	ST	OD	Bidirectional I/O port		
	T0CKI	ST	_	Timer0 clock input		
	CMP2	_	OD	Comparator 2 output		
RA5/MCLR/VPP	RA5	ST	_	Input port		
	MCLR	ST	_	Master clear. When configured as MCLR, this pin is an active low Reset to the device. Voltage on MCLR/VPP must not exceed VDD during normal device operation.		
	VPP	_	_	Programming voltage input.		
RA6/OSC2/CLKOUT	RA6	ST	CMOS	Bidirectional I/O port		
	OSC2	_	XTAL	Oscillator crystal output. Connects to crystal or resonator in Crystal Oscillator mode.		
	CLKOUT	_	CMOS	In RC/INTOSC mode, OSC2 pin can output CLKOUT, which has 1/4 the frequency of OSC1		
RA7/OSC1/CLKIN	RA7	ST	CMOS	Bidirectional I/O port		
	OSC1	XTAL	_	Oscillator crystal input		
	CLKIN	ST	_	External clock source input. RC biasing pin.		
RB0/INT	RB0	TTL	CMOS	Bidirectional I/O port. Can be software programmed for internal weak pull-up.		
	INT	ST	_	External interrupt.		
RB1/RX/DT	RB1	TTL	CMOS	Bidirectional I/O port. Can be software programmed for internal weak pull-up.		
	RX	ST	_	USART receive pin		
	DT	ST	CMOS	Synchronous data I/O.		
RB2/TX/CK	RB2	TTL	CMOS	Bidirectional I/O port. Can be software programmed for internal weak pull-up.		
	TX	_	CMOS	USART transmit pin		
	CK	ST	CMOS	Synchronous clock I/O.		
RB3/CCP1	RB3	TTL	CMOS	Bidirectional I/O port. Can be software programmed for internal weak pull-up.		
	CCP1	ST	CMOS	Capture/Compare/PWM I/O		

**Legend:** O = Output CMOS = CMOS Output P = Power

— = Not used I = Input ST = Schmitt Trigger Input

TTL = TTL Input OD = Open Drain Output AN = Analog

TABLE 3-2: PIC16F627A/628A/648A PINOUT DESCRIPTION

Name	Function	Input Type	Output Type	Description
RB4/PGM	RB4	TTL	CMOS	Bidirectional I/O port. Interrupt-on-pin change. Can be software programmed for internal weak pull-up.
	PGM	ST	_	Low voltage programming input pin. When low voltage programming is enabled, the interrupt-on-pin change and weak pull-up resistor are disabled.
RB5	RB5	TTL	CMOS	Bidirectional I/O port. Interrupt-on-pin change. Can be software programmed for internal weak pull-up.
RB6/T1OSO/T1CKI/PGC	RB6	TTL	CMOS	Bidirectional I/O port. Interrupt-on-pin change. Can be software programmed for internal weak pull-up.
	T1OSO	_	XTAL	Timer1 oscillator output.
	T1CKI	ST	_	Timer1 clock input.
	PGC	ST	_	ICSP Programming Clock.
RB7/T1OSI/PGD	RB7	TTL	CMOS	Bidirectional I/O port. Interrupt-on-pin change. Can be software programmed for internal weak pull-up.
	T1OSI	XTAL	_	Timer1 oscillator input.
	PGD	ST	CMOS	ICSP Data I/O
Vss	Vss	Power	_	Ground reference for logic and I/O pins
VDD	VDD	Power		Positive supply for logic and I/O pins

**Legend:** O = Output CMOS = CMOS Output P = Power

— = Not used I = Input ST = Schmitt Trigger Input

TTL = TTL Input OD = Open Drain Output AN = Analog

# 3.1 Clocking Scheme/Instruction Cycle

The clock input (OSC1/CLKIN/RA7 pin) is internally divided by four to generate four non-overlapping quadrature clocks namely Q1, Q2, Q3 and Q4. Internally, the program counter (PC) is incremented every Q1, the instruction is fetched from the program memory and latched into the instruction register in Q4. The instruction is decoded and executed during the following Q1 through Q4. The clocks and instruction execution flow is shown in Figure 3-2.


#### 3.2 Instruction Flow/Pipelining

An instruction cycle consists of four Q cycles (Q1, Q2, Q3 and Q4). The instruction fetch and execute are pipelined such that fetch takes one instruction cycle while decode and execute takes another instruction cycle. However, due to the pipelining, each instruction effectively executes in one cycle. If an instruction causes the program counter to change (e.g., GOTO) then two cycles are required to complete the instruction (Example 3-1).


A fetch cycle begins with the program counter (PC) incrementing in Q1.

In the execution cycle, the fetched instruction is latched into the Instruction Register (IR) in cycle Q1. This instruction is then decoded and executed during the Q2, Q3, and Q4 cycles. Data memory is read during Q2 (operand read) and written during Q4 (destination write).

FIGURE 3-2: CLOCK/INSTRUCTION CYCLE



#### **EXAMPLE 3-1: INSTRUCTION PIPELINE FLOW**



All instructions are single cycle, except for any program branches. These take two cycles since the fetch instruction is "flushed" from the pipeline while the new instruction is being fetched and then executed.

© 2004 Microchip Technology Inc. Preliminary DS40044B-page 13


NOTES:

#### 4.0 MEMORY ORGANIZATION

#### 4.1 Program Memory Organization

The PIC16F627A/628A/648A has a 13-bit program counter capable of addressing an 8K x 14 program memory space. Only the first 1K x 14 (0000h - 03FFh) for the PIC16F627A, 2K x 14 (0000h - 07FFh) for the PIC16F628A and 4K x 14 (0000h - 0FFFh) for the PIC16F648A are physically implemented. Accessing a location above these boundaries will cause a wraparound within the first 1K x 14 space (PIC16F627A), 2K x 14 space (PIC16F628A) or 4K x 14 space (PIC16F648A). The Reset vector is at 0000h and the interrupt vector is at 0004h (Figure 4-1).

FIGURE 4-1: PROGRAM MEMORY MAP AND STACK



#### 4.2 Data Memory Organization

The data memory (Figure 4-2 and Figure 4-3) is partitioned into four banks, which contain the General Purpose Registers (GPR's) and the Special Function Registers (SFR). The SFR's are located in the first 32 locations of each Bank. There are General Purpose Registers implemented as static RAM in each Bank. Table 4-1 lists the General Purpose Register available in each of the four banks.

TABLE 4-1: GENERAL PURPOSE STATIC RAM REGISTERS

	PIC16F627A/628A	PIC16F648A
Bank0	20-7Fh	20-7Fh
Bank1	A0h-FF	A0h-FF
Bank2	120h-14Fh, 170h-17Fh	120h-17Fh
Bank3	1F0h-1FFh	1F0h-1FFh

Addresses F0h-FFh, 170h-17Fh and 1F0h-1FFh are implemented as common RAM and mapped back to addresses 70h-7Fh.

Table 4-2 lists how to access the four banks of registers via the Status Register bits RP1 and RP0.

TABLE 4-2: ACCESS TO BANKS OF REGISTERS

	RP1	RP0
Bank0	0	0
Bank1	0	1
Bank2	1	0
Bank3	1	1

### 4.2.1 GENERAL PURPOSE REGISTER FILE

The register file is organized as 224 x 8 in the PIC16F627A/628A and 256 x 8 in the PIC16F648A. Each is accessed either directly or indirectly through the File Select Register (FSR), See Section 4.4 "Indirect Addressing, INDF and FSR Registers".

© 2004 Microchip Technology Inc. Preliminary DS40044B-page 15

FIGURE 4-2: DATA MEMORY MAP OF THE PIC16F627A AND PIC16F628A File Address Indirect addr. (1) Indirect addr.(1) Indirect addr.(1) Indirect addr.(1) 100h 00h 80h 180h 101h OPTION TMR0 01h OPTION TMR0 81h 181h PCL 02h PCL 102h **PCL** 182h **PCL** 82h **STATUS STATUS** 103h 03h **STATUS** 83h **STATUS** 183h **FSR** 04h **FSR** 104h **FSR** 184h **FSR** 84h 105h **PORTA** 05h **TRISA** 85h 185h **PORTB** TRISB 06h 106h **PORTB TRISB** 86h 186h 07h 107h 187h 87h 108h 08h 188h 88h 109h 09h 89h 189h **PCLATH PCLATH** 10Ah 0Ah **PCLATH** 18Ah **PCLATH** 8Ah INTCON 0Bh INTCON 10Bh INTCON 18Bh INTCON 8Bh PIR1 0Ch PIE1 8Ch 10Ch 18Ch 10Dh 0Dh 8Dh 18Dh TMR1L 0Eh 10Eh **PCON** 18Eh 8Eh 10Fh TMR1H 0Fh 18Fh 8Fh T1CON 10h 90h TMR2 11h 91h T2CON 12h PR2 92h 13h 93h 14h 94h CCPR1L 15h 95h CCPR1H 16h 96h CCP1CON 17h 97h 18h **RCSTA** 98h **TXSTA** 19h **TXREG SPBRG** 99h EEDATA **RCREG** 1Ah 9Ah 1Bh **EEADR** 9Bh EECON1 1Ch 9Ch EECON2<sup>(1)</sup> 1Dh 9Dh 1Eh 9Eh 1Fh **VRCON** 9Fh **CMCON** 11Fh General 120h 20h A0h Purpose General General Register 48 Bytes Purpose Purpose 14Fh Register Register 150h 80 Bytes 80 Bytes 1EFh 6Fh **EFh** 16Fh 1F0h 70h F0h 170h accesses accesses accesses 16 Bytes 70h-7Fh 70h-7Fh 70h - 7Fh 1FFh 17Fh 7Fh **FFh** Bank 0 Bank 1 Bank 2 Bank 3 Unimplemented data memory locations, read as '0'. Note 1: Not a physical register.

FIGURE 4-3: DATA MEMORY MAP OF THE PIC16F648A

Indirect addr. (1)	00h	Indirect addr.(1)	80h	Indirect addr.(1)	100h	Indirect addr.(1)	180
TMR0	01h	OPTION	81h	TMR0	101h	OPTION	18
PCL	02h	PCL	82h	PCL	102h	PCL	18:
STATUS	03h	STATUS	83h	STATUS	103h	STATUS	18:
FSR	04h	FSR	84h	FSR	104h	FSR	18
PORTA	05h	TRISA	85h		105h		18
PORTB	06h	TRISB	86h	PORTB	106h	TRISB	18
	07h		87h		107h		18
	08h		88h		108h		18
	09h		89h		109h		189
PCLATH	0Ah	PCLATH	8Ah	PCLATH	10Ah	PCLATH	18
INTCON	0Bh	INTCON	8Bh	INTCON	10Bh	INTCON	18
PIR1	0Ch	PIE1	8Ch		10Ch		18
	0Dh		8Dh		10Dh		181
TMR1L	0Eh	PCON	8Eh		10Eh		181
TMR1H	0Fh	. 3311	8Fh		10Fh		181
T1CON	10h		90h				
TMR2	11h		91h				
T2CON	12h	PR2	92h				
	13h	111/2	93h				
	14h		94h				
CCPR1L	15h		95h				
CCPR1H	16h		96h				
CCP1CON	17h		97h				
RCSTA	18h	TXSTA	98h				
TXREG	19h	SPBRG	99h				
RCREG	1Ah	EEDATA	9Ah				
KCKEG	1Bh	EEADR	9Bh				
	1Ch	EECON1	9Ch				
	1Dh	EECON2 <sup>(1)</sup>	9Dh				
	1Eh	2200112	9Eh				
CMCON	1Fh	VRCON	9Fh		11 Th		
CIVICOIN	20h	VICON	İ		11Fh 120h		
0	2011	Camanal	A0h	General	12011		
General Purpose		General Purpose		Purpose			
Register		Register		Register			
80 Bytes		80 Bytes		80 Bytes			
00 2)100							1E
	6Fh 70h		EFh F0h		16Fh 170h		1 1E
16 Bytes	7011	accesses	FUII	accesses	17011	accesses	
<b>,</b>		70h-7Fh		70h-7Fh		70h - 7Fh	
Donk O	7Fh	Donk 4	FFh	Pont 2	17Fh	Ponk 2	J 1F
Bank 0		Bank 1		Bank 2		Bank 3	

#### 4.2.2 SPECIAL FUNCTION REGISTERS

The SFRs are registers used by the CPU and Peripheral functions for controlling the desired operation of the device (Table 4-3). These registers are static RAM.

The special registers can be classified into two sets (core and peripheral). The SFRs associated with the "core" functions are described in this section. Those related to the operation of the peripheral features are described in the section of that peripheral feature.

TABLE 4-3: SPECIAL REGISTERS SUMMARY BANKO

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR Reset <sup>(1)</sup>	Details on Page
Bank 0											
00h	INDF	Addressir	ng this location	al register)	xxxx xxxx	28					
01h	TMR0	Timer0 m	odule's Regis	<u> </u>	xxxx xxxx	45					
02h	PCL	Program	Counter's (Po	0000 0000	28						
03h	STATUS	IRP	RP1	0001 1xxx	22						
04h	FSR	Indirect d	ata memory a	address poin	ter				•	xxxx xxxx	28
05h	PORTA	RA7	RA6	RA5	RA4	RA3	RA2	RA1	RA0	xxxx 0000	31
06h	PORTB	RB7	RB6	RB5	RB4	RB3	RB2	RB1	RB0	xxxx xxxx	36
07h	_	Unimplen	nented							_	_
08h	_	Unimplen	nented							_	_
09h	_	Unimplen	nented							_	_
0Ah	PCLATH	_	1	ĺ	Write buffer	for upper 5 b	oits of progra	am counter		0 0000	28
0Bh	INTCON	GIE	PEIE	TOIE	INTE	RBIE	TOIF	INTF	RBIF	0000 000x	24
0Ch	PIR1	EEIF	CMIF	RCIF	TXIF	_	CCP1IF	TMR2IF	TMR1IF	0000 -000	26
0Dh	_	Unimplen	nented							_	_
0Eh	TMR1L	Holding re	egister for the	e Least Signi	ficant Byte o	f the 16-bit TI	MR1			xxxx xxxx	48
0Fh	TMR1H	Holding re	egister for the	Most Signif	icant Byte of	the 16-bit TM	/IR1			xxxx xxxx	48
10h	T1CON	_	_	T1CKPS1	T1CKPS0	T10SCEN	T1SYNC	TMR1CS	TMR10N	00 0000	48
11h	TMR2	TMR2 mo	odule's registe	er						0000 0000	52
12h	T2CON	_	TOUTPS3	TOUTPS2	TOUTPS1	TOUTPS0	TMR2ON	T2CKPS1	T2CKPS0	-000 0000	52
13h	_	Unimplen	nented							_	_
14h	_	Unimplen								_	_
15h	CCPR1L	Capture/0	Compare/PW	M register (L	.SB)					xxxx xxxx	55
16h	CCPR1H	Capture/0	Compare/PW	M register (N	MSB)					xxxx xxxx	55
17h	CCP1CON	_	_	CCP1X	CCP1Y	CCP1M3	CCP1M2	CCP1M1	CCP1M0	00 0000	55
18h	RCSTA	SPEN	RX9	SREN	CREN	ADEN	FERR	OERR	RX9D	0000 000x	69
19h	TXREG	USART T	ransmit data	register						0000 0000	76
1Ah	RCREG	USART F	Receive data i	register						0000 0000	79
1Bh		Unimplen	nented							_	_
1Ch	_	Unimplen	nented							_	_
1Dh	_	Unimplen	nented							_	_
1Eh	_	Unimplen	nented							_	_
1Fh	CMCON	C2OUT	C1OUT	C2INV	C1INV	CIS	CM2	CM1	CM0	0000 0000	61

**Legend:** — = Unimplemented locations read as '0', u = unchanged, x = unknown, q = value depends on condition, shaded = unimplemented

Note 1: For the Initialization Condition for Registers Tables, refer to Table 14-6 and Table 14-7.

TABLE 4-4: SPECIAL FUNCTION REGISTERS SUMMARY BANK1

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR Reset <sup>(1)</sup>	Details on Page
Bank 1											
80h	INDF	Addressing register)	this location	uses conter	nts of FSR to	address da	ata memory	(not a physic	al	xxxx xxxx	28
81h	OPTION	RBPU	INTEDG	T0CS	T0SE	PSA	PS2	PS1	PS0	1111 1111	23
82h	PCL	Program C	ounter's (PC)	Least Signi	ficant Byte		•	•	•	0000 0000	28
83h	STATUS	IRP	RP1	RP0	TO	PD	Z	DC	С	0001 1xxx	22
84h	FSR	Indirect da	ta memory ad	dress pointe	er	I	ı			xxxx xxxx	28
85h	TRISA	TRISA7	TRISA6	TRISA5	TRISA4	TRISA3	TRISA2	TRISA1	TRISA0	1111 1111	31
86h	TRISB	TRISB7	TRISB6	TRISB5	TRISB4	TRISB3	TRISB2	TRISB1	TRISB0	1111 1111	36
87h	_	Unimpleme	ented			,				_	_
88h	_	Unimpleme	ented							_	_
89h	_	Unimpleme	ented							_	_
8Ah	PCLATH	_	_	_	Write buffe	r for upper t	5 bits of prog	ram counter		0 0000	28
8Bh	INTCON	GIE	PEIE	T0IE	INTE	RBIE	TOIF	INTF	RBIF	0000 000x	24
8Ch	PIE1	EEIE	CMIE	RCIE	TXIE	_	CCP1IE	TMR2IE	TMR1IE	0000 -000	25
8Dh	_	Unimpleme	ented							_	-
8Eh	PCON	_	_	_	_	OSCF	_	POR	BOR	1-0x	27
8Fh	_	Unimpleme	ented		•	•	•	•	•	_	_
90h	_	Unimpleme	ented							_	_
91h	_	Unimpleme	ented							_	_
92h	PR2	Timer2 Pe	riod Register							1111 1111	52
93h	_	Unimpleme	ented							_	1
94h	_	Unimpleme	ented							_	_
95h	_	Unimpleme	ented							_	_
96h	_	Unimpleme	ented							_	_
97h	_	Unimpleme	ented							_	_
98h	TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000 -010	71
99h	SPBRG	Baud Rate	Generator Re	egister						0000 0000	71
9Ah	EEDATA	EEPROM	data register							xxxx xxxx	89
9Bh	EEADR	EEPROM	address regist	ter						xxxx xxxx	90
9Ch	EECON1	_	_	_	_	WRERR	WREN	WR	RD	x000	90
9Dh	EECON2	EEPROM	control registe	r 2 (not a pl	nysical regis	ter)					90
9Eh	_	Unimpleme	ented							_	_
9Fh	VRCON	VREN	VROE	VRR	_	VR3	VR2	VR1	VR0	000- 0000	67

**Legend:** — = Unimplemented locations read as '0', u = unchanged, x = unknown, q = value depends on condition, shaded = unimplemented

Note 1: For the Initialization Condition for Registers Tables, refer to Table 14-6 and Table 14-7.

© 2004 Microchip Technology Inc. Preliminary DS40044B-page 19

TABLE 4-5: SPECIAL FUNCTION REGISTERS SUMMARY BANK2

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR Reset <sup>(1)</sup>	Details on Page
Bank 2											
100h	INDF	Addressing	this location	cal register)	xxxx xxxx	28					
101h	TMR0	Timer0 mo	dule's Registe		xxxx xxxx	45					
102h	PCL	Program C	Counter's (PC)	Least Signi	ficant Byte					0000 0000	28
103h	STATUS	IRP	RP1	RP0	TO	PD	Z	DC	С	0001 1xxx	22
104h	FSR	Indirect da	ta memory ac	dress pointe	er		ı		_	xxxx xxxx	28
105h	_	Unimpleme	ented	•						_	_
106h	PORTB	RB7	RB6	RB5	RB4	RB3	RB2	RB1	RB0	xxxx xxxx	36
107h	_	Unimpleme	ented							_	_
108h		Unimpleme	ented							_	_
109h	_	Unimpleme	ented							_	_
10Ah	PCLATH	_	_	_	Write	buffer for u	pper 5 bits o	f program c	ounter	0 0000	28
10Bh	INTCON	GIE	PEIE	T0IE	INTE	RBIE	TOIF	INTF	RBIF	0000 000x	24
10Ch	I	Unimpleme	ented							_	_
10Dh	_	Unimpleme	ented							_	_
10Eh	_	Unimpleme	ented							_	_
10Fh	_	Unimpleme	ented							_	_
110h	_	Unimpleme	ented							_	_
111h	_	Unimpleme	ented							_	_
112h	_	Unimpleme	ented							_	_
113h	_	Unimpleme	ented								_
114h	_	Unimpleme	ented							_	_
115h	_	Unimpleme								_	_
116h	_	Unimpleme								_	_
117h	_	Unimpleme								_	_
118h	_	Unimpleme								_	_
119h	_	Unimpleme								_	_
11Ah	_	Unimpleme									_
11Bh	_	Unimpleme								_	_
11Ch	_	Unimpleme									_
11Dh	_	Unimpleme								_	_
11Eh	_	Unimpleme									
11Fh	_	Unimpleme	ented							_	_

**Legend:** — = Unimplemented locations read as '0', u = unchanged, x = unknown, q = value depends on condition, shaded = unimplemented.

Note 1: For the Initialization Condition for Registers Tables, refer to Table 14-6 and Table 14-7.

TABLE 4-6: SPECIAL FUNCTION REGISTERS SUMMARY BANK3

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR Reset <sup>(1)</sup>	Details on Page
Bank 3											
180h	INDF	Addressing	dressing this location uses contents of FSR to address data memory (not a physical registe							xxxx xxxx	28
181h	OPTION	RBPU	PU INTEDG TOCS TOSE PSA PS2 PS1 PS0							1111 1111	23
182h	PCL	Program C	gram Counter's (PC) Least Significant Byte							0000 0000	28
183h	STATUS	IRP	RP1	RP0	TO	PD	Z	DC	С	0001 1xxx	22
184h	FSR	Indirect da	ta memory ad	dress point	er					xxxx xxxx	28
185h	_	Unimpleme	ented							_	_
186h	TRISB	TRISB7	TRISB6	TRISB5	TRISB4	TRISB3	TRISB2	TRISB1	TRISB0	1111 1111	36
187h	_	Unimpleme	ented		•	•	•	•	•	_	_
188h	_	Unimpleme	ented							_	_
189h	ı	Unimpleme	implemented							_	_
18Ah	PCLATH	_	_	_	Write buffe	er for upper	5 bits of pro	gram counte	r	0 0000	28
18Bh	INTCON	GIE	PEIE	T0IE	INTE	RBIE	T0IF	INTF	RBIF	0000 000x	24
18Ch	_	Unimpleme	ented							_	_
18Dh	_	Unimpleme	nimplemented							_	_
18Eh	_	Unimpleme	ented							_	_
18Fh	_	Unimpleme	ented							_	_
190h	_	Unimpleme	ented							_	_
191h	_	Unimpleme	ented							_	_
192h	_	Unimpleme	ented							_	_
193h	_	Unimpleme	ented							_	_
194h	_	Unimpleme	ented							_	_
195h	_	Unimpleme	ented							_	_
196h	_	Unimpleme	ented							_	_
197h	_	Unimpleme	ented							_	_
198h	_	Unimpleme	ented							_	_
199h	_	Unimpleme	ented							_	_
19Ah		Unimpleme								_	_
19Bh		Unimpleme								_	_
19Ch		Unimpleme								_	_
19Dh		Unimpleme								_	_
19Eh		Unimpleme								_	_
19Fh	_	Unimpleme	ented							_	_

**Legend:** — = Unimplemented locations read as '0', u = unchanged, x = unknown, q = value depends on condition, shaded = unimplemented

Note 1: For the Initialization Condition for Registers Tables, refer to Table 14-6 and Table 14-7.

© 2004 Microchip Technology Inc. Preliminary DS40044B-page 21

#### 4.2.2.1 Status Register

The Status Register, shown in Register 4-1, contains the arithmetic status of the ALU; the Reset status and the bank select bits for data memory (SRAM).

The Status Register can be the destination for any instruction, like any other register. If the Status Register is the destination for an instruction that affects the Z, DC or C bits, then the write to these three bits is disabled. These bits are set or cleared according to the device logic. Furthermore, the  $\overline{\text{TO}}$  and  $\overline{\text{PD}}$  bits are nonwritable. Therefore, the result of an instruction with the Status Register as destination may be different than intended.

For example, CLRF STATUS will clear the upper-three bits and set the Z bit. This leaves the Status Register as "000uu1uu" (where u = unchanged).

It is recommended, therefore, that only BCF, BSF, SWAPF and MOVWF instructions are used to alter the StatusRegister because these instructions do not affect any Status bit. For other instructions, not affecting any Status bits, see the "Instruction Set Summary".

Note 1: The C and DC bits operate as a Borrow and Digit Borrow out bit, respectively, in subtraction. See the SUBLW and SUBWF instructions for examples.

#### REGISTER 4-1: STATUS REGISTER (ADDRESS: 03h, 83h, 103h, 183h)

R/W-0	R/W-0	R/W-0	R-1	R-1	R/W-x	R/W-x	R/W-x
IRP	RP1	RP0	TO	PD	Z	DC	С
hit 7							hit 0

bit 7 IRP: Register Bank Select bit (used for indirect addressing)

1 = Bank 2, 3 (100h - 1FFh)

0 = Bank 0, 1 (00h - FFh)

bit 6-5 RP1:RP0: Register Bank Select bits (used for direct addressing)

00 = Bank 0 (00h - 7Fh)

01 = Bank 1 (80h - FFh)

10 = Bank 2 (100h - 17Fh)

11 = Bank 3 (180h - 1FFh)

bit 4 **TO**: Time out bit

1 = After power-up, CLRWDT instruction, or SLEEP instruction

0 = A WDT time out occurred

bit 3 **PD**: Power-down bit

1 = After power-up or by the CLRWDT instruction

0 = By execution of the SLEEP instruction

bit 2 Z: Zero bit

1 = The result of an arithmetic or logic operation is zero

0 = The result of an arithmetic or logic operation is not zero

bit 1 DC: Digit carry/borrow bit (ADDWF, ADDLW, SUBLW, SUBWF instructions) (for borrow the polarity is reversed)

1 = A carry-out from the 4th low order bit of the result occurred

0 = No carry-out from the 4th low order bit of the result

bit 0 C: Carry/borrow bit (ADDWF, ADDLW, SUBLW, SUBWF instructions)

1 = A carry-out from the Most Significant bit of the result occurred

0 = No carry-out from the Most Significant bit of the result occurred

**Note:** For borrow, the polarity is reversed. A subtraction is executed by adding the two's complement of the second operand. For rotate (RRF, RLF) instructions, this bit is loaded with either the high or low order bit of the source register.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	l bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

#### 4.2.2.2 OPTION Register

The OPTION register is a readable and writable register, which contains various control bits to configure the TMR0/WDT prescaler, the external RB0/INT interrupt, TMR0 and the weak pull-ups on PORTB.

Note: To achieve a 1:1 prescaler assignment for TMR0, assign the prescaler to the WDT (PSA = 1). See Section 6.3.1 "Switching Prescaler Assignment".

#### REGISTER 4-2: OPTION REGISTER (ADDRESS: 81h, 181h)

R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
RBPU	INTEDG	T0CS	T0SE	PSA	PS2	PS1	PS0
bit 7							bit 0

bit 7 RBPU: PORTB Pull-up Enable bit

1 = PORTB pull-ups are disabled

0 = PORTB pull-ups are enabled by individual port latch values

bit 6 INTEDG: Interrupt Edge Select bit

1 = Interrupt on rising edge of RB0/INT pin

0 = Interrupt on falling edge of RB0/INT pin

bit 5 TOCS: TMR0 Clock Source Select bit

1 = Transition on RA4/T0CKI pin

0 = Internal instruction cycle clock (CLKOUT)

bit 4 T0SE: TMR0 Source Edge Select bit

1 = Increment on high-to-low transition on RA4/T0CKI pin

0 = Increment on low-to-high transition on RA4/T0CKI pin

bit 3 **PSA**: Prescaler Assignment bit

1 = Prescaler is assigned to the WDT

0 = Prescaler is assigned to the Timer0 module

bit 2-0 **PS2:PS0**: Prescaler Rate Select bits

Bit Value	TMR0 Rate	WDT Rate
000	1:2	1:1
001	1:4	1:2
010	1:8	1:4
011	1:16	1:8
100	1:32	1 : 16
101	1:64	1:32
110	1 : 128	1:64
111	1 : 256	1 : 128

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'	
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared $x = Bit$ is unknown	

#### 4.2.2.3 INTCON Register

The INTCON register is a readable and writable register, which contains the various enable and flag bits for all interrupt sources except the comparator module. See Section 4.2.2.4 "PIE1 Register" and Section 4.2.2.5 "PIR1 Register" for a description of the comparator enable and flag bits.

Interrupt flag bits get set when an interrupt condition occurs regardless of the state of its corresponding enable bit or the global enable bit, GIE (INTCON<7>).

#### REGISTER 4-3: INTCON REGISTER (ADDRESS: 0Bh, 8Bh, 10Bh, 18Bh)

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-x
GIE	PEIE	T0IE	INTE	RBIE	T0IF	INTF	RBIF
bit 7							bit 0

Note:

bit 7 **GIE:** Global Interrupt Enable bit

1 = Enables all un-masked interrupts

0 = Disables all interrupts

bit 6 **PEIE**: Peripheral Interrupt Enable bit

1 = Enables all un-masked peripheral interrupts

0 = Disables all peripheral interrupts

bit 5 **T0IE**: TMR0 Overflow Interrupt Enable bit

1 = Enables the TMR0 interrupt 0 = Disables the TMR0 interrupt

bit 4 INTE: RB0/INT External Interrupt Enable bit

1 = Enables the RB0/INT external interrupt

0 = Disables the RB0/INT external interrupt

bit 3 RBIE: RB Port Change Interrupt Enable bit

1 = Enables the RB port change interrupt

0 =Disables the RB port change interrupt

bit 2 **T0IF**: TMR0 Overflow Interrupt Flag bit

1 = TMR0 register has overflowed (must be cleared in software)

0 = TMR0 register did not overflow

bit 1 INTF: RB0/INT External Interrupt Flag bit

1 = The RB0/INT external interrupt occurred (must be cleared in software)

0 = The RB0/INT external interrupt did not occur

bit 0 RBIF: RB Port Change Interrupt Flag bit

1 = When at least one of the RB7:RB4 pins changed state (must be cleared in software)

0 = None of the RB7:RB4 pins have changed state

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

#### 4.2.2.4 PIE1 Register

This register contains interrupt enable bits.

#### REGISTER 4-4: PIE1 REGISTER (ADDRESS: 8Ch)

R/W-0	R/W-0	R/W-0	R/W-0	U-0	R/W-0	R/W-0	R/W-0
EEIE	CMIE	RCIE	TXIE	_	CCP1IE	TMR2IE	TMR1IE
bit 7							bit 0

bit 7 **EEIE:** EE Write Complete Interrupt Enable Bit 1 = Enables the EE write complete interrupt 0 = Disables the EE write complete interrupt bit 6 **CMIE**: Comparator Interrupt Enable bit 1 = Enables the comparator interrupt 0 = Disables the comparator interrupt bit 5 RCIE: USART Receive Interrupt Enable bit 1 = Enables the USART receive interrupt 0 = Disables the USART receive interrupt bit 4 TXIE: USART Transmit Interrupt Enable bit 1 = Enables the USART transmit interrupt 0 = Disables the USART transmit interrupt bit 3 Unimplemented: Read as '0' **CCP1IE**: CCP1 Interrupt Enable bit bit 2 1 = Enables the CCP1 interrupt 0 = Disables the CCP1 interrupt bit 1 TMR2IE: TMR2 to PR2 Match Interrupt Enable bit 1 = Enables the TMR2 to PR2 match interrupt 0 = Disables the TMR2 to PR2 match interrupt bit 0 TMR1IE: TMR1 Overflow Interrupt Enable bit 1 = Enables the TMR1 overflow interrupt 0 = Disables the TMR1 overflow interrupt

	_		_	١.
ea	e	n	О	П

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### 4.2.2.5 PIR1 Register

This register contains interrupt flag bits.

Note: Interrupt flag bits get set when an interrupt condition occurs regardless of the state of its corresponding enable bit or the global enable bit, GIE (INTCON<7>). User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.

#### REGISTER 4-5: PIR1 REGISTER (ADDRESS: 0Ch)

R/W-0	R/W-0	R-0	R-0	U-0	R/W-0	R/W-0	R/W-0
EEIF	CMIF	RCIF	TXIF	_	CCP1IF	TMR2IF	TMR1IF

bit 7 bit 0

bit 7 **EEIF:** EEPROM Write Operation Interrupt Flag bit

1 = The write operation completed (must be cleared in software)
 0 = The write operation has not completed or has not been started

bit 6 CMIF: Comparator Interrupt Flag bit

1 = Comparator output has changed

0 = Comparator output has not changed

bit 5 RCIF: USART Receive Interrupt Flag bit

1 = The USART receive buffer is full

0 = The USART receive buffer is empty

bit 4 TXIF: USART Transmit Interrupt Flag bit

1 = The USART transmit buffer is empty

0 = The USART transmit buffer is full

bit 3 **Unimplemented**: Read as '0'

bit 2 **CCP1IF**: CCP1 Interrupt Flag bit

#### Capture Mode

1 = A TMR1 register capture occurred (must be cleared in software)

0 = No TMR1 register capture occurred

#### Compare Mode

1 = A TMR1 register compare match occurred (must be cleared in software)

0 = No TMR1 register compare match occurred

#### **PWM Mode**

Unused in this mode

bit 1 TMR2IF: TMR2 to PR2 Match Interrupt Flag bit

1 = TMR2 to PR2 match occurred (must be cleared in software)

0 = No TMR2 to PR2 match occurred

bit 0 **TMR1IF**: TMR1 Overflow Interrupt Flag bit

1 = TMR1 register overflowed (must be cleared in software)

0 = TMR1 register did not overflow

#### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### 4.2.2.6 PCON Register

The PCON register contains flag bits to differentiate between a Power-on Reset, an external MCLR Reset, WDT Reset or a Brown-out Reset.

Note: BOR is unknown on Power-on Reset. It must then be set by the user and checked on subsequent Resets to see if BOR is cleared, indicating a brown-out has occurred. The BOR Status bit is a "don't care" and is not necessarily predictable if the brown-out circuit is disabled (by clearing the BOREN bit in the Configuration word).

#### REGISTER 4-6: PCON REGISTER (ADDRESS: 8Eh)

U-0	U-0	U-0	U-0	R/W-1	U-0	R/W-0	R/W-x
_	_	_	_	OSCF	_	POR	BOR
bit 7							bit 0

bit 7-4 Unimplemented: Read as '0'

bit 3 OSCF: INTOSC oscillator frequency

1 = 4 MHz typical 0 = 37 kHz typical

bit 2 **Unimplemented:** Read as '0'

bit 1 POR: Power-on Reset Status bit

1 = No Power-on Reset occurred

0 = A Power-on Reset occurred (must be set in software after a Power-on Reset occurs)

bit 0 BOR: Brown-out Reset Status bit

1 = No Brown-out Reset occurred

0 = A Brown-out Reset occurred (must be set in software after a Brown-out Reset occurs)

#### Legend:


R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### 4.3 PCL and PCLATH

The program counter (PC) is 13-bits wide. The low byte comes from the PCL register, which is a readable and writable register. The high byte (PC<12:8>) is not directly readable or writable and comes from PCLATH. On any Reset, the PC is cleared. Figure 4-4 shows the two situations for loading the PC. The upper example in Figure 4-4 shows how the PC is loaded on a write to PCL (PCLATH<4:0>  $\rightarrow$  PCH). The lower example in Figure 4-4 shows how the PC is loaded during a CALL or GOTO instruction (PCLATH<4:3>  $\rightarrow$  PCH).

FIGURE 4-4: LOADING OF PC IN DIFFERENT SITUATIONS



#### 4.3.1 COMPUTED GOTO

A computed GOTO is accomplished by adding an offset to the program counter (ADDWF PCL). When doing a table read using a computed GOTO method, care should be exercised if the table location crosses a PCL memory boundary (each 256-byte block). Refer to the application note "Implementing a Table Read" (AN556).

#### 4.3.2 STACK

The PIC16F627A/628A/648A family has an 8-level deep x 13-bit wide hardware stack (Figure 4-1). The stack space is not part of either program or data space and the stack pointer is not readable or writable. The PC is PUSHed onto the stack when a CALL instruction is executed or an interrupt causes a branch. The stack is POPed in the event of a RETURN, RETLW or a RETFIE instruction execution. PCLATH is not affected by a PUSH or POP operation.

The stack operates as a circular buffer. This means that after the stack has been PUSHed eight times, the ninth push overwrites the value that was stored from the first push. The tenth push overwrites the second push (and so on).

Note 1: There are no Status bits to indicate stack overflow or stack underflow conditions.

2: There are no instructions/mnemonics called PUSH or POP. These are actions that occur from the execution of the CALL, RETURN, RETLW and RETFIE instructions, or the vectoring to an interrupt address.

## 4.4 Indirect Addressing, INDF and FSR Registers

The INDF register is not a physical register. Addressing the INDF register will cause indirect addressing.

Indirect addressing is possible by using the INDF register. Any instruction using the INDF register actually accesses data pointed to by the file select register (FSR). Reading INDF itself indirectly will produce 00h. Writing to the INDF register indirectly results in a no-operation (although Status bits may be affected). An effective 9-bit address is obtained by concatenating the 8-bit FSR register and the IRP bit (STATUS<7>), as shown in Figure 4-5.

A simple program to clear RAM location 20h-2Fh using indirect addressing is shown in Example 4-1.

#### **EXAMPLE 4-1:** Indirect Addressing

	MOVLW	0x20	;initialize pointer
	MOVWF	FSR	;to RAM
NEXT	CLRF	INDF	clear INDF register;
	INCF	FSR	;inc pointer
	BTFSS	FSR,4	;all done?
	GOTO	NEXT	;no clear next
			;yes continue
L			




FIGURE 4-5: DIRECT/INDIRECT ADDRESSING PIC16F627A/628A/648A

© 2004 Microchip Technology Inc. Preliminary DS40044B-page 29

NOTES:

#### **5.0 I/O PORTS**

The PIC16F627A/628A/648A have two ports, PORTA and PORTB. Some pins for these I/O ports are multiplexed with alternate functions for the peripheral features on the device. In general, when a peripheral is enabled, that pin may not be used as a general purpose I/O pin.

#### 5.1 IPORTA and TRISA Registers

PORTA is an 8-bit wide latch. RA4 is a Schmitt Trigger input and an open drain output. Port RA4 is multiplexed with the T0CKI clock input. RA5<sup>(1)</sup> is a Schmitt Trigger input only and has no output drivers. All other RA port pins have Schmitt Trigger input levels and full CMOS output drivers. All pins have data direction bits (TRIS registers) which can configure these pins as input or output.

A '1' in the TRISA register puts the corresponding output driver in a High-impedance mode. A '0' in the TRISA register puts the contents of the output latch on the selected pin(s).

Reading the PORTA register reads the status of the pins whereas writing to it will write to the port latch. All write operations are read-modify-write operations. So a write to a port implies that the port pins are first read, then this value is modified and written to the port data latch.

The PORTA pins are multiplexed with comparator and voltage reference functions. The operation of these pins are selected by control bits in the CMCON (comparator control register) register and the VRCON (voltage reference control register) register. When selected as a comparator input, these pins will read as '0's.

**Note 1:** RA5 shares function with VPP. When VPP voltage levels are applied to RA5, the device will enter Programming mode.

- 2: On Reset, the TRISA register is set to all inputs. The digital inputs (RA<3:0>) are disabled and the comparator inputs are forced to ground to reduce current consumption.
- **3:** TRISA<6:7> is overridden by oscillator configuration. When PORTA<6:7> is overridden, the data reads '0' and the TRISA<6:7> bits are ignored.

TRISA controls the direction of the RA pins, even when they are being used as comparator inputs. The user must make sure to keep the pins configured as inputs when using them as comparator inputs.

The RA2 pin will also function as the output for the voltage reference. When in this mode, the VREF pin is a very high-impedance output. The user must configure TRISA<2> bit as an input and use high-impedance loads.

In one of the Comparator modes defined by the CMCON register, pins RA3 and RA4 become outputs of the comparators. The TRISA<4:3> bits must be cleared to enable outputs to use this function.

**EXAMPLE 5-1:** Initializing PORTA

CLRF	PORTA	;Initialize PORTA by
CLRF	PORTA	/IIIICIAIIZE PORTA Dy
		;setting
		output data latches;
MOVLW	$0 \times 07$	Turn comparators off and
MOVWF	CMCON	enable pins for I/0
		;functions
BCF	STATUS,	RP1
BSF	STATUS,	RP0;Select Bank1
MOVLW	0x1F	;Value used to initialize
		data direction;
MOVWF	TRISA	;Set RA<4:0> as inputs
		;TRISA<5> always
		;read as `1'.
		;TRISA<7:6>
		depend on oscillator;
		;mode

### FIGURE 5-1: BLOCK DIAGRAM OF RA0/AN0:RA1/AN1 PINS





FIGURE 5-2: BLOCK DIAGRAM OF RA2/VREF PIN



#### FIGURE 5-3: BLOCK DIAGRAM OF THE RA3/AN3 PIN




FIGURE 5-4: BLOCK DIAGRAM OF RA4/T0CKI PIN




FIGURE 5-5: BLOCK DIAGRAM OF THE RA5/MCLR/VPP PIN




FIGURE 5-6: BLOCK DIAGRAM OF RA6/OSC2/CLKOUT PIN




FIGURE 5-7: BLOCK DIAGRAM OF RA7/OSC1/CLKIN PIN




TABLE 5-1: PORTA FUNCTIONS

Name	Function	Input Type	Output Type	Description
RA0/AN0	RA0	ST	CMOS	Bidirectional I/O port
	AN0	AN	_	Analog comparator input
RA1/AN1	RA1	ST	CMOS	Bidirectional I/O port
	AN1	AN	_	Analog comparator input
RA2/AN2/VREF	RA2	ST	CMOS	Bidirectional I/O port
	AN2	AN	1	Analog comparator input
	VREF	_	AN	VREF output
RA3/AN3/CMP1	RA3	ST	CMOS	Bidirectional I/O port
	AN3	AN	_	Analog comparator input
	CMP1	_	CMOS	Comparator 1 output
RA4/T0CKI/CMP2	RA4	ST	OD	Bidirectional I/O port. Output is open drain type.
	T0CKI	ST	_	External clock input for TMR0 or comparator output
	CMP2	_	OD	Comparator 2 output
RA5/MCLR/VPP	RA5	ST		Input port
	MCLR	ST		Master clear. When configured as MCLR, this pin is an active low Reset to the device. Voltage on MCLR/VPP must not exceed VDD during normal device operation.
	VPP	HV		Programming voltage input.
RA6/OSC2/CLKOUT	RA6	ST	CMOS	Bidirectional I/O port
	OSC2	_	XTAL	Oscillator crystal output. Connects to crystal resonator in Crystal Oscillator mode.
	CLKOUT	_	CMOS	In RC or INTOSC mode. OSC2 pin can output CLKOUT, which has 1/4 the frequency of OSC1
RA7/OSC1/CLKIN	RA7	ST	CMOS	Bidirectional I/O port
	OSC1	XTAL	_	Oscillator crystal input. Connects to crystal resonator in Crystal Oscillator mode.
	CLKIN	ST		External clock source input. RC biasing pin.

**Legend:** O = Output CMOS = CMOS Output P = Power

— = Not used I = Input ST = Schmitt Trigger Input

TTL = TTL Input OD = Open Drain Output AN = Analog

TABLE 5-2: SUMMARY OF REGISTERS ASSOCIATED WITH PORTA<sup>(1)</sup>

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR	Value on All Other Resets
05h	PORTA	RA7	RA6	RA5 <sup>(2)</sup>	RA4	RA3	RA2	RA1	RA0	xxxx 0000	qqqu 0000
85h	TRISA	TRISA7	TRISA6	TRISA5	TRISA4	TRISA3	TRISA2	TRISA1	TRISA0	1111 1111	1111 1111
1Fh	CMCON	C2OUT	C1OUT	C2INV	C1INV	CIS	CM2	CM1	CM0	0000 0000	0000 0000
9Fh	VRCON	VREN	VROE	VRR	_	VR3	VR2	VR1	VR0	000- 0000	000- 0000

**Legend:** — = Unimplemented locations read as '0', u = unchanged, x = unknown, q = value depends on condition, shaded = unimplemented

Note 1: Shaded bits are not used by PORTA.

2: MCLRE Configuration Bit sets RA5 functionality.

### 5.2 PORTB and TRISB Registers

PORTB is an 8-bit wide bidirectional port. The corresponding data direction register is TRISB. A '1' in the TRISB register puts the corresponding output driver in a High-impedance mode. A '0' in the TRISB register puts the contents of the output latch on the selected pin(s).

PORTB is multiplexed with the external interrupt, USART, CCP module and the TMR1 clock input/output. The standard port functions and the alternate port functions are shown in Table 5-3. Alternate port functions may override TRIS setting when enabled.

Reading PORTB register reads the status of the pins, whereas writing to it will write to the port latch. All write operations are read-modify-write operations. So a write to a port implies that the port pins are first read, then this value is modified and written to the port data latch.

Each of the PORTB pins has a weak internal pull-up ( $\approx$ 200  $\mu$ A typical). A single control bit can turn on all the pull-ups. This is done by clearing the  $\overline{RBPU}$  (OPTION<7>) bit. The weak pull-up is automatically turned off when the port pin is configured as an output. The pull-ups are disabled on Power-on Reset.

Four of PORTB's pins, RB<7:4>, have an interrupt-on-change feature. Only pins configured as inputs can cause this interrupt to occur (i.e., any RB<7:4> pin configured as an output is excluded from the interrupt-on-change comparison). The input pins (of RB7:RB4) are compared with the old value latched on the last read of PORTB. The "mismatch" outputs of RB7:RB4 are OR'ed together to generate the RBIF interrupt (flag latched in INTCON<0>).

This interrupt can wake the device from Sleep. The user, in the interrupt service routine, can clear the interrupt in the following manner:

- a) Any read or write of PORTB. This will end the mismatch condition.
- b) Clear flag bit RBIF.

A mismatch condition will continue to set flag bit RBIF. Reading PORTB will end the mismatch condition and allow flag bit RBIF to be cleared. This interrupt on mismatch feature, together with software configurable pull-ups on these four pins allow easy interface to a key pad and make it possible for wake-up on key-depression. (See AN552)

**Note:** If a change on the I/O pin should occur when a read operation is being executed (start of the Q2 cycle), then the RBIF interrupt flag may not get set.

The interrupt-on-change feature is recommended for wake-up on key depression operation and operations where PORTB is only used for the interrupt-on-change feature. Polling of PORTB is not recommended while using the interrupt-on-change feature.

FIGURE 5-8: BLOCK DIAGRAM OF RB0/INT PIN




FIGURE 5-9: BLOCK DIAGRAM OF RB1/RX/DT PIN




FIGURE 5-10: BLOCK DIAGRAM OF RB2/TX/CK PIN





FIGURE 5-11: BLOCK DIAGRAM OF RB3/CCP1 PIN



**FIGURE 5-12: BLOCK DIAGRAM OF RB4/PGM PIN** Vdd RBPU weak pull-up Data Bus D Q VDD — WR PORTB ∙ck <del>\</del>∟<u>a</u> Data Latch RB4/PGM D Q WR TRISB ck**₹**\_Q TRIS Latch RD TRISB LVP (Configuration Bit) **RD PORTB** PGM input Schmitt input Trigger buffer Q D Q1 EN Set RBIF Q D From other RB<7:4> pins Q3 EN<

Note:

The low voltage programming disables the interrupt-on-change and the weak pull-ups on RB4.

RBPU ed P weak VDD pull-up Data Bus D Q WR PORTB Data Latch D Q WR TRISB CK \\_Q TRIS Latch TTL input buffer RD TRISB Q D RD PORTB – Q1 EN< Set RBIF Q

D

ΕN

- Q3

**FIGURE 5-13: BLOCK DIAGRAM OF RB5 PIN** 

From other RB<7:4> pins




FIGURE 5-14: BLOCK DIAGRAM OF RB6/T10S0/T1CKI PIN




FIGURE 5-15: BLOCK DIAGRAM OF THE RB7/T10SI PIN

TABLE 5-3: PORTB FUNCTIONS

Name	Function	Input Type	Output Type	Description
RB0/INT	RB0	TTL	CMOS	Bidirectional I/O port. Can be software programmed for internal weak pull-up.
	INT	ST	_	External interrupt.
RB1/RX/DT	RB1	TTL	CMOS	Bidirectional I/O port. Can be software programmed for internal weak pull-up.
	RX	ST	_	USART Receive Pin
	DT	ST	CMOS	Synchronous data I/O
RB2/TX/CK	RB2	TTL	CMOS	Bidirectional I/O port
	TX	_	CMOS	USART Transmit Pin
	CK	ST	CMOS	Synchronous Clock I/O. Can be software programmed for internal weak pull-up.
RB3/CCP1	RB3	TTL	CMOS	Bidirectional I/O port. Can be software programmed for internal weak pull-up.
	CCP1	ST	CMOS	Capture/Compare/PWM/I/O
RB4/PGM	RB4	TTL	CMOS	Bidirectional I/O port. Interrupt-on-pin change. Can be software programmed for internal weak pull-up.
	PGM	ST	_	Low voltage programming input pin. When low voltage programming is enabled, the interrupt-on-pin change and weak pull-up resistor are disabled.
RB5	RB5	TTL	CMOS	Bidirectional I/O port. Interrupt-on-pin change. Can be software programmed for internal weak pull-up.
RB6/T1OSO/T1CKI/ PGC	RB6	TTL	CMOS	Bidirectional I/O port. Interrupt-on-pin change. Can be software programmed for internal weak pull-up.
	T1OSO	_	XTAL	Timer1 Oscillator Output
	T1CKI	ST	_	Timer1 Clock Input
	PGC	ST		ICSP Programming Clock
RB7/T1OSI/PGD	RB7	TTL	CMOS	Bidirectional I/O port. Interrupt-on-pin change. Can be software programmed for internal weak pull-up.
	T1OSI	XTAL		Timer1 Oscillator Input
	PGD	ST	CMOS	ICSP Data I/O

**Legend:** O = Output CMOS = CMOS Output P = Power

— = Not used I = Input ST = Schmitt Trigger Input

TTL = TTL Input OD = Open Drain Output AN = Analog

### TABLE 5-4: SUMMARY OF REGISTERS ASSOCIATED WITH PORTB<sup>(1)</sup>

IADEL	ADEL 0 4. COMMINANT OF REGIOTERO ACCOUNTED WITH TORTH												
Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR	Value on All Other Resets		
06h, 106h	PORTB	RB7	RB6	RB5	RB4 <sup>(2)</sup>	RB3	RB2	RB1	RB0	xxxx xxxx	uuuu uuuu		
86h, 186h	TRISB	TRISB7	TRISB6	TRISB5	TRISB4	TRISB3	TRISB2	TRISB1	TRISB0	1111 1111	1111 1111		
81h, 181h	OPTION	RBPU	INTEDG	T0CS	T0SE	PSA	PS2	PS1	PS0	1111 1111	1111 1111		

**Legend:** u = unchanged, x = unknown

Note 1: Shaded bits are not used by PORTB.

2: LVP Configuration Bit sets RB4 functionality.

### 5.3 I/O Programming Considerations

### 5.3.1 BIDIRECTIONAL I/O PORTS

Any instruction that writes, operates internally as a read followed by a write operation. The BCF and BSF instructions, for example, read the register into the CPU, execute the bit operation and write the result back to the register. Caution must be used when these instructions are applied to a port with both inputs and outputs defined. For example, a BSF operation on bit5 of PORTB will cause all eight bits of PORTB to be read into the CPU. Then the BSF operation takes place on bit5 and PORTB is written to the output latches. If another bit of PORTB is used as a bidirectional I/O pin (e.g., bit 0) and is defined as an input at this time, the input signal present on the pin itself would be read into the CPU and rewritten to the data latch of this particular pin, overwriting the previous content. As long as the pin stays in the Input mode, no problem occurs. However, if bit 0 is switched into Output mode later on, the content of the data latch may now be unknown.

Reading a port register reads the values of the port pins. Writing to the port register writes the value to the port latch. When using read-modify-write instructions (ex. BCF, BSF, etc.) on a port, the value of the port pins is read, the desired operation is done to this value, and this value is then written to the port latch.

Example 5-2 shows the effect of two sequential read-modify-write instructions (ex.,  ${\tt BCF}\,,~{\tt BSF},$  etc.) on an I/O port

A pin actively outputting a Low or High should not be driven from external devices at the same time in order to change the level on this pin ("wired-or", "wired-and"). The resulting high output currents may damage the chip.


## EXAMPLE 5-2: READ-MODIFY-WRITE INSTRUCTIONS ON AN I/O PORT

```
;Initial PORT settings:PORTB<7:4> Inputs
                       PORTB<3:0> Outputs
;PORTB<7:6> have external pull-up and are
;not connected to other circuitry
                       PORT latchPORT Pins
   BCF STATUS, RP0
   BCF PORTB, 7
                       ;01pp pppp 11pp pppp
   BSF STATUS, RPO
   BCF TRISB, 7
                       ;10pp pppp 11pp pppp
                       ;10pp pppp 10pp pppp
   BCF TRISB, 6
; Note that the user may have expected the
;pin values to be 00pp pppp. The 2nd BCF
; caused RB7 to be latched as the pin value
; (High).
```

## 5.3.2 SUCCESSIVE OPERATIONS ON I/O PORTS

The actual write to an I/O port happens at the end of an instruction cycle, whereas for reading, the data must be valid at the beginning of the instruction cycle (Figure 5-16). Therefore, care must be exercised if a write followed by a read operation is carried out on the same I/O port. The sequence of instructions should be such to allow the pin voltage to stabilize (load dependent) before the next instruction, which causes that file to be read into the CPU, is executed. Otherwise, the previous state of that pin may be read into the CPU rather than the new state. When in doubt, it is better to separate these instructions with a NOP or another instruction not accessing this I/O port.

### FIGURE 5-16: SUCCESSIVE I/O OPERATION



Note

- 1: This example shows write to PORTB followed by a read from PORTB.
- 2: Data setup time = (0.25 TcY TPD) where TcY = instruction cycle and TPD = propagation delay of Q1 cycle to output valid. Therefore, at higher clock frequencies, a write followed by a read may be problematic.

### 6.0 TIMERO MODULE

The Timer0 module timer/counter has the following features:

- 8-bit timer/counter
- Read/Write capabilities
- · 8-bit software programmable prescaler
- · Internal or external clock select
- Interrupt on overflow from FFh to 00h
- · Edge select for external clock

Figure 6-1 is a simplified block diagram of the Timer0 module. Additional information is available in the *PICmicro® Mid-Range MCU Family Reference Manual* (DS33023).

Timer mode is selected by clearing the T0CS bit (OPTION<5>). In Timer mode, the TMR0 register value will increment every instruction cycle (without prescaler). If the TMR0 register is written to, the increment is inhibited for the following two cycles. The user can work around this by writing an adjusted value to the TMR0 register.

Counter mode is selected by setting the T0CS bit. In this mode the TMR0 register value will increment either on every rising or falling edge of pin RA4/T0CKI. The incrementing edge is determined by the source edge (T0SE) control bit (OPTION<4>). Clearing the T0SE bit selects the rising edge. Restrictions on the external clock input are discussed in detail in **Section 6.2** "Using Timer0 with External Clock".

The prescaler is shared between the Timer0 module and the Watchdog Timer. The prescaler assignment is controlled in software by the control bit PSA (OPTION<3>). Clearing the PSA bit will assign the prescaler to Timer0. The prescaler is not readable or writable. When the prescaler is assigned to the Timer0 module, prescale value of 1:2, 1:4,..., 1:256 are selectable. **Section 6.3 "Timer0 Prescaler"** details the operation of the prescaler.

### 6.1 Timer0 Interrupt

Timer0 interrupt is generated when the TMR0 register timer/counter overflows from FFh to 00h. This overflow sets the T0IF bit. The interrupt can be masked by clearing the T0IE bit (INTCON<5>). The T0IF bit (INTCON<2>) must be cleared in software by the Timer0 module interrupt service routine before reenabling this interrupt. The Timer0 interrupt cannot wake the processor from Sleep since the timer is shut off during Sleep.

### 6.2 Using Timer0 with External Clock

When an external clock input is used for Timer0, it must meet certain requirements. The external clock requirement is due to internal phase clock (Tosc) synchronization. Also, there is a delay in the actual incrementing of Timer0 after synchronization.

## 6.2.1 EXTERNAL CLOCK SYNCHRONIZATION

When no prescaler is used, the external clock input is the same as the prescaler output. The synchronization of T0CKI with the internal phase clocks is accomplished by sampling the prescaler output on the Q2 and Q4 cycles of the internal phase clocks (Figure 6-1). Therefore, it is necessary for T0CKI to be high for at least 2Tosc (and a small RC delay of 20 ns) and low for at least 2Tosc (and a small RC delay of 20 ns). Refer to the electrical specification of the desired device.

When a prescaler is used, the external clock input is divided by the asynchronous ripple-counter type prescaler so that the prescaler output is symmetrical. For the external clock to meet the sampling requirement, the ripple-counter must be taken into account. Therefore, it is necessary for TOCKI to have a period of at least 4Tosc (and a small RC delay of 40 ns) divided by the prescaler value. The only requirement on TOCKI high and low time is that they do not violate the minimum pulse width requirement of 10 ns. Refer to parameters 40, 41 and 42 in the electrical specification of the desired device. See Table 17-8.


### 6.3 Timer0 Prescaler

An 8-bit counter is available as a prescaler for the Timer0 module, or as a postscaler for the Watchdog Timer. A prescaler assignment for the Timer0 module means that there is no postscaler for the Watchdog Timer, and vice-versa.

The PSA and PS2:PS0 bits (OPTION<3:0>) determine the prescaler assignment and prescale ratio.

When assigned to the Timer0 module, all instructions writing to the TMR0 register (e.g., CLRF 1, MOVWF 1, BSF 1, x...etc.) will clear the prescaler. When assigned to WDT, a CLRWDT instruction will clear the prescaler along with the Watchdog Timer. The prescaler is not readable or writable.

FIGURE 6-1: BLOCK DIAGRAM OF THE TIMERO/WDT



## 6.3.1 SWITCHING PRESCALER ASSIGNMENT

The prescaler assignment is fully under software control (i.e., it can be changed "on the fly" during program execution). Use the instruction sequences shown in Example 6-1 when changing the prescaler assignment from Timer0 to WDT, to avoid an unintended device Reset.

## EXAMPLE 6-1: CHANGING PRESCALER (TIMER0→WDT)

	(	
BCF	STATUS, RPO	;Skip if already in
		;Bank 0
CLRWDT		;Clear WDT
CLRF	TMR0	Clear TMR0 and
		;Prescaler
BSF	STATUS, RP0	;Bank 1
MOVLW	'00101111'b	These 3 lines
		;(5, 6, 7)
MOVWF	OPTION_REG	are required only
		;if desired PS<2:0>
		;are
CLRWDT		;000 or 001
MOVLW	'00101xxx'b	;Set Postscaler to
MOVWF	OPTION_REG	desired WDT rate
BCF	STATUS, RPO	Return to Bank 0
1		

To change prescaler from the WDT to the Timer0 module, use the sequence shown in Example 6-2. This precaution must be taken even if the WDT is disabled.

## EXAMPLE 6-2: CHANGING PRESCALER (WDT→TIMER0)

CLRWDT		;Clear WDT and
		;prescaler
BSF	STATUS, RP0	
MOVLW	b'xxxx0xxx'	;Select TMR0, new
		prescale value and
		clock source
MOVWF	OPTION_REG	
BCF	STATUS, RP0	
	BSF MOVLW MOVWF	BSF STATUS, RPO MOVLW b'xxxx0xxx'  MOVWF OPTION_REG

### TABLE 6-1: REGISTERS ASSOCIATED WITH TIMERO

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR	Value on All Other Resets
01h, 101h	TMR0	Timer0 m	nodule regi		xxxx xxxx	uuuu uuuu					
0Bh, 8Bh, 10Bh, 18Bh	INTCON	GIE	PEIE	TOIE	INTE	RBIE	TOIF	INTF	RBIF	0000 000x	0000 000u
81h, 181h	OPTION <sup>(2)</sup>	RBPU	INTEDG	T0CS	T0SE	PSA	PS2	PS1	PS0	1111 1111	1111 1111
85h	TRISA	TRISA7	TRISA6	TRISA5	TRISA4	TRISA3	TRISA2	TRISA1	TRISA0	1111 1111	1111 1111

**Legend:** — = Unimplemented locations, read as '0', u = unchanged, x = unknown

Note 1: Shaded bits are not used by Timer0 module.

2: Option is referred by  ${\tt OPTION\_REG}$  in MPLAB  $^{\!@}\!\!$  .

### 7.0 TIMER1 MODULE

The Timer1 module is a 16-bit timer/counter consisting of two 8-bit registers (TMR1H and TMR1L) which are readable and writable. The TMR1 register pair (TMR1H:TMR1L) increments from 0000h to FFFFh and rolls over to 0000h. The Timer1 Interrupt, if enabled, is generated on overflow of the TMR1 register pair which latches the interrupt flag bit TMR1IF (PIR1<0>). This interrupt can be enabled/disabled by setting/clearing the Timer1 interrupt enable bit TMR1IE (PIE1<0>).

Timer1 can operate in one of two modes:

- As a timer
- As a counter

The Operating mode is determined by the clock select bit, TMR1CS (T1CON<1>).

In Timer mode, the TMR1 register pair value increments every instruction cycle. In Counter mode, it increments on every rising edge of the external clock input.

Timer1 can be enabled/disabled by setting/clearing control bit TMR1ON (T1CON<0>).

Timer1 also has an internal "Reset input". This Reset can be generated by the CCP module (Section 9.0 "Capture/Compare/PWM (CCP) Module"). Register 7-1 shows the Timer1 control register.

For the PIC16F627A/628A/648A, when the Timer1 oscillator is enabled (T1OSCEN is set), the RB7/T1OSI and RB6/T1OSO/T1CKI pins become inputs. That is, the TRISB<7:6> value is ignored.

### REGISTER 7-1: T1CON: TIMER1 CONTROL REGISTER (ADDRESS: 10h)

U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
_	_	T1CKPS1	T1CKPS0	T1OSCEN	T1SYNC	TMR1CS	TMR10N
hit 7							hit 0

bit 7-6 **Unimplemented:** Read as '0'

bit 5-4 T1CKPS1:T1CKPS0: Timer1 Input Clock Prescale Select bits

11 = 1:8 Prescale value 10 = 1:4 Prescale value 01 = 1:2 Prescale value 00 = 1:1 Prescale value

bit 3 T10SCEN: Timer1 Oscillator Enable Control bit

1 = Oscillator is enabled 0 = Oscillator is shut off<sup>(1)</sup>

bit 2 T1SYNC: Timer1 External Clock Input Synchronization Control bit

TMR1CS = 1

1 = Do not synchronize external clock input

0 = Synchronize external clock input

TMR1CS = 0

This bit is ignored. Timer1 uses the internal clock when TMR1CS = 0.

bit 1 TMR1CS: Timer1 Clock Source Select bit

1 = External clock from pin RB6/T1OSO/T1CKI (on the rising edge)

0 = Internal clock (Fosc/4)

bit 0 TMR10N: Timer1 On bit

1 = Enables Timer1

0 = Stops Timer1

Note 1: The oscillator inverter and feedback resistor are turned off to eliminate power drain.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

### 7.1 Timer1 Operation in Timer Mode

Timer mode is selected by clearing the TMR1CS (T1CON<1>) bit. In this mode, the input clock to the timer is Fosc/4. The synchronize control bit  $\overline{\text{T1SYNC}}$  (T1CON<2>) has no effect since the internal clock is always in sync.

## 7.2 Timer1 Operation in Synchronized Counter Mode

Counter mode is selected by setting bit TMR1CS. In this mode the TMR1 register pair value increments on every rising edge of clock input on pin RB7/T1OSI when bit T1OSCEN is set or pin RB6/T1OSO/T1CKI when bit T1OSCEN is cleared.

If T1SYNC is cleared, then the external clock input is synchronized with internal phase clocks. The synchronization is done after the prescaler stage. The prescaler stage is an asynchronous ripple-counter.

In this configuration, during Sleep mode, the TMR1 register pair value will not increment even if the external clock is present, since the synchronization circuit is shut off. The prescaler however will continue to increment.


## 7.2.1 EXTERNAL CLOCK INPUT TIMING FOR SYNCHRONIZED COUNTER MODE

When an external clock input is used for Timer1 in synchronized Counter mode, it must meet certain requirements. The external clock requirement is due to internal phase clock (Tosc) synchronization. Also, there is a delay in the actual incrementing of the TMR1 register pair value after synchronization.

When the prescaler is 1:1, the external clock input is the same as the prescaler output. The synchronization of T1CKI with the internal phase clocks is accomplished by sampling the prescaler output on the Q2 and Q4 cycles of the internal phase clocks. Therefore, it is necessary for T1CKI to be high for at least 2Tosc (and a small RC delay of 20 ns) and low for at least 2Tosc (and a small RC delay of 20 ns). Refer to the appropriate electrical specifications, parameters 45, 46, and 47.

When a prescaler other than 1:1 is used, the external clock input is divided by the asynchronous ripple-counter type prescaler so that the prescaler output is symmetrical. In order for the external clock to meet the sampling requirement, the ripple-counter must be taken into account. Therefore, it is necessary for T1CKI to have a period of at least 4Tosc (and a small RC delay of 40 ns) divided by the prescaler value. The only requirement on T1CKI high and low time is that they do not violate the minimum pulse width requirements of 10 ns). Refer to the appropriate electrical specifications, parameters 45, 46, and 47.

### FIGURE 7-1: TIMER1 BLOCK DIAGRAM



Note 1: When the T1OSCEN bit is cleared, the inverter and feedback resistor are turned off. This eliminates power drain.

## 7.3 Timer1 Operation in Asynchronous Counter Mode

If control bit T1SYNC (T1CON<2>) is set, the external clock input is not synchronized. The timer continues to increment asynchronous to the internal phase clocks. The timer will continue to run during Sleep and can generate an interrupt on overflow, which will wake-up the processor. However, special precautions in software are needed to read/write the timer (Section 7.3.2 "Reading and Writing Timer1 in Asynchronous Counter Mode").

**Note:** In Asynchronous Counter mode, Timer1 cannot be used as a time-base for capture or compare operations.

## 7.3.1 EXTERNAL CLOCK INPUT TIMING WITH UNSYNCHRONIZED CLOCK

If control bit T1SYNC is set, the timer will increment completely asynchronously. The input clock must meet certain minimum high and low time requirements. Refer to Table 17-8 in the Electrical Specifications Section, timing parameters 45, 46, and 47.

## 7.3.2 READING AND WRITING TIMER1 IN ASYNCHRONOUS COUNTER MODE

Reading the TMR1H or TMR1L register while the timer is running, from an external asynchronous clock, will produce a valid read (taken care of in hardware). However, the user should keep in mind that reading the 16-bit timer in two 8-bit values itself poses certain problems since the timer may overflow between the reads

For writes, it is recommended that the user simply stop the timer and write the desired values. A write contention may occur by writing to the timer registers while the register is incrementing. This may produce an unpredictable value in the timer register.

Reading the 16-bit value requires some care. Example 7-1 is an example routine to read the 16-bit timer value. This is useful if the timer cannot be stopped.

### EXAMPLE 7-1: READING A 16-BIT FREE-RUNNING TIMER

```
; All interrupts are disabled
   MOVF
           TMR1H, W
                      ;Read high byte
   MOVWF
           TMPH
   MOVF
           TMR1L, W
                      ;Read low byte
   MOVWF
           TMPL
                      ;Read high byte
   MOVF
           TMR1H, W
   SUBWF
           TMPH, W
                      ;Sub 1st read with
                      ;2nd read
   BTFSC
           STATUS.Z
                      iIs result = 0
                      ;Good 16-bit read
   GOTO
           CONTINUE
; TMR1L may have rolled over between the
; read of the high and low bytes. Reading
; the high and low bytes now will read a good
; value.
           TMR1H, W
                      ;Read high byte
   MOVF
   MOVWF
           TMPH
                      ;
   MOVF
           TMR1L, W
                      ;Read low byte
   MOVWF
           TMPL
; Re-enable the Interrupts (if required)
CONTINUE
                      ;Continue with your
                      :code
```

### 7.4 Timer1 Oscillator

A crystal oscillator circuit is built in between pins T1OSI (input) and T1OSO (amplifier output). It is enabled by setting control bit T1OSCEN (T1CON<3>). It will continue to run during Sleep. It is primarily intended for a 32.768 kHz watch crystal. Table 7-1 shows the capacitor selection for the Timer1 oscillator.

The user must provide a software time delay to ensure proper oscillator start-up.

TABLE 7-1: CAPACITOR SELECTION FOR THE TIMER1 OSCILLATOR

Freq	C1	C2		
32.768 kHz	15 pF	15 pF		

These values are for design guidance only. Consult AN826 (DS00826) for further information on Crystal/Capacitor Selection.

### 7.5 Resetting Timer1 Using a CCP Trigger Output

If the CCP1 module is configured in Compare mode to generate a "special event trigger" (CCP1M3:CCP1M0 = 1011), this signal will Reset Timer1.

**Note:** The special event triggers from the CCP1 module will not set interrupt flag bit TMR1IF (PIR1<0>).

Timer1 must be configured for either timer or synchronized Counter mode to take advantage of this feature. If Timer1 is running in Asynchronous Counter mode, this Reset operation may not work.

In the event that a write to Timer1 coincides with a special event trigger from CCP1, the write will take precedence.

In this mode of operation, the CCPRxH:CCPRxL registers pair effectively becomes the period register for Timer1.

## 7.6 Resetting Timer1 Register Pair (TMR1H, TMR1L)

TMR1H and TMR1L registers are not reset to 00h on a POR or any other Reset except by the CCP1 special event triggers.

T1CON register is reset to 00h on a Power-on Reset or a Brown-out Reset, which shuts off the timer and leaves a 1:1 prescale. In all other Resets, the register is unaffected.

### 7.7 Timer1 Prescaler

The prescaler counter is cleared on writes to the TMR1H or TMR1L registers.

TABLE 7-2: REGISTERS ASSOCIATED WITH TIMER1 AS A TIMER/COUNTER

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR	Value on all other Resets
0Bh, 8Bh, 10Bh, 18Bh	INTCON	GIE	PEIE	TOIE	INTE	RBIE	TOIF	INTF	RBIF	0000 000x	0000 000u
0Ch	PIR1	EEIF	CMIF	RCIF	TXIF	I	CCP1IF	TMR2IF	TMR1IF	0000 -000	0000 -000
8Ch	PIE1	EEIE	CMIE	RCIE	TXIE	I	CCP1IE	TMR2IE	TMR1IE	0000 -000	0000 -000
0Eh	TMR1L		Holding register for the Least Significant Byte of the 16-bit TMR1 register								uuuu uuuu
0Fh	TMR1H		Holding register for the Most Significant Byte of the 16-bit TMR1 register xxxx								
10h	T1CON	1	_	T1CKPS1	T1CKPS0	T1OSCEN	T1SYNC	TMR1CS	TMR10N	00 0000	uu uuuu

Legend: x = unknown, u = unchanged, - = unimplemented read as '0'. Shaded cells are not used by the Timer1 module.

### 8.0 TIMER2 MODULE

Timer2 is an 8-bit timer with a prescaler and a postscaler. It can be used as the PWM time-base for PWM mode of the CCP module. The TMR2 register is readable and writable, and is cleared on any device Reset.

The input clock (Fosc/4) has a prescale option of 1:1, 1:4 or 1:16, selected by control bits T2CKPS1:T2CKPS0 (T2CON<1:0>).

The Timer2 module has an 8-bit period register PR2. The TMR2 register value increments from 00h until it matches the PR2 register value and then resets to 00h on the next increment cycle. The PR2 register is a readable and writable register. The PR2 register is initialized to FFh upon Reset.

The match output of Timer2 goes through a 4-bit postscaler (which gives a 1:1 to 1:16 scaling inclusive) to generate a Timer2 interrupt (latched in flag bit TMR2IF, (PIR1<1>)).

Timer2 can be shut off by clearing control bit TMR2ON (T2CON<2>) to minimize power consumption.

Register 8-1 shows the Timer2 control register.

### 8.1 Timer2 Prescaler and Postscaler

The prescaler and postscaler counters are cleared when any of the following occurs:


- a write to the TMR2 register
- · a write to the T2CON register
- any device Reset (Power-on Reset, MCLR Reset, Watchdog Timer Reset, or Brown-out Reset)

The TMR2 register is not cleared when T2CON is written.

### 8.2 TMR2 Output

The TMR2 output (before the postscaler) is fed to the Synchronous Serial Port module which optionally uses it to generate shift clock.

FIGURE 8-1: TIMER2 BLOCK DIAGRAM



### REGISTER 8-1: T2CON: TIMER2 CONTROL REGISTER (ADDRESS: 12h)

U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
_	TOUTPS3	TOUTPS2	TOUTPS1	TOUTPS0	TMR2ON	T2CKPS1	T2CKPS0
L:4 7							P:4 O

bit 7 bit 0

bit 7 Unimplemented: Read as '0'

bit 6-3 TOUTPS3:TOUTPS0: Timer2 Output Postscale Select bits

0000 = 1:1 Postscale Value 0001 = 1:2 Postscale Value

•

•

1111 = 1:16 Postscale

bit 2 TMR2ON: Timer2 On bit

1 = Timer2 is on 0 = Timer2 is off

bit 1-0 T2CKPS1:T2CKPS0: Timer2 Clock Prescale Select bits

00 = 1:1 Prescaler Value 01 = 1:4 Prescaler Value 1x = 1:16 Prescaler Value

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### TABLE 8-1: REGISTERS ASSOCIATED WITH TIMER2 AS A TIMER/COUNTER

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR	Value on all other
											Resets
0Bh, 8Bh, 10Bh, 18Bh	INTCON	GIE	PEIE	TOIE	INTE	RBIE	TOIF	INTF	RBIF	0000 000x	0000 000u
0Ch	PIR1	EEIF	CMIF	RCIF	TXIF	_	CCP1IF	TMR2IF	TMR1IF	0000 -000	0000 -000
8Ch	PIE1	EEIE	CMIE	RCIE	TXIE	_	CCP1IE	TMR2IE	TMR1IE	0000 -000	0000 -000
11h	TMR2	Timer2 mod	dule's registe		0000 0000	0000 0000					
12h	T2CON	_	TOUTPS3	TOUTPS2	TOUTPS1	TOUTPS0	TMR2ON	T2CKPS1	T2CKPS0	-000 0000	-000 0000
92h	PR2	Timer2 Peri	od Register							1111 1111	1111 1111

**Legend:** x = unknown, u = unchanged, - = unimplemented read as '0'. Shaded cells are not used by the Timer2 module.

NOTES:

## 9.0 CAPTURE/COMPARE/PWM (CCP) MODULE

The CCP (Capture/Compare/PWM) module contains a 16-bit register which can operate as a 16-bit capture register, as a 16-bit compare register or as a PWM master/slave Duty Cycle register. Table 9-1 shows the timer resources of the CCP module modes.

### **CCP1 Module**

Capture/Compare/PWM Register1 (CCPR1) is comprised of two 8-bit registers: CCPR1L (low byte) and CCPR1H (high byte). The CCP1CON register controls the operation of CCP1. All are readable and writable.

Additional information on the CCP module is available in the *PICmicro*<sup>®</sup> *Mid-Range Reference Manual* (DS33023).

## TABLE 9-1: CCP MODE - TIMER RESOURCE

CCP Mode	Timer Resource				
Capture	Timer1				
Compare	Timer1				
PWM	Timer2				

### REGISTER 9-1: CCP1CON REGISTER (ADDRESS: 17h)

U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
_	_	CCP1X	CCP1Y	CCP1M3	CCP1M2	CCP1M1	CCP1M0
bit 7							bit 0

bit 7-6 Unimplemented: Read as '0'

bit 5-4 CCP1X:CCP1Y: PWM Least Significant bits

Capture Mode: Unused Compare Mode: Unused

PWM Mode: These bits are the two LSbs of the PWM duty cycle. The eight MSbs are found in

CCPRxL.

bit 3-0 CCP1M3:CCP1M0: CCPx Mode Select bits

0000 = Capture/Compare/PWM off (resets CCP1 module)

0100 = Capture mode, every falling edge
0101 = Capture mode, every rising edge
0110 = Capture mode, every 4th rising edge

0111 = Capture mode, every 16th rising edge

1000 = Compare mode, set output on match (CCP1IF bit is set)

1001 = Compare mode, clear output on match (CCP1IF bit is set)

1010 = Compare mode, generate software interrupt on match (CCP1IF bit is set, CCP1 pin is unaffected)

1011 = Compare mode, trigger special event (CCP1IF bit is set; CCP1 resets TMR1

 $11xx = PWM \mod e$ 

### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### 9.1 Capture Mode

In Capture mode, CCPR1H:CCPR1L captures the 16-bit value of the TMR1 register when an event occurs on pin RB3/CCP1. An event is defined as:

- · Every falling edge
- · Every rising edge
- · Every 4th rising edge
- · Every 16th rising edge


An event is selected by control bits CCP1M3:CCP1M0 (CCP1CON<3:0>). When a capture is made, the interrupt request flag bit CCP1IF (PIR1<2>) is set. It must be cleared in software. If another capture occurs before the value in register CCPR1 is read, the old captured value will be lost.

### 9.1.1 CCP PIN CONFIGURATION

In Capture mode, the RB3/CCP1 pin should be configured as an input by setting the TRISB<3> bit.

**Note:** If the RB3/CCP1 is configured as an output, a write to the port can cause a capture condition.

## FIGURE 9-1: CAPTURE MODE OPERATION BLOCK DIAGRAM



### 9.1.2 TIMER1 MODE SELECTION

Timer1 must be running in Timer mode or synchronized Counter mode for the CCP module to use the capture feature. In Asynchronous Counter mode, the capture operation may not work.

### 9.1.3 SOFTWARE INTERRUPT

When the Capture mode is changed, a false capture interrupt may be generated. The user should keep bit CCP1IE (PIE1<2>) clear to avoid false interrupts and should clear the flag bit CCP1IF following any such change in Operating mode.

#### 9.1.4 CCP PRESCALER

There are four prescaler settings, specified by bits CCP1M3:CCP1M0. Whenever the CCP module is turned off, or the CCP module is not in Capture mode, the prescaler counter is cleared. This means that any Reset will clear the prescaler counter.

Switching from one capture prescaler to another may generate an interrupt. Also, the prescaler counter will not be cleared, therefore the first capture may be from a non-zero prescaler. Example 9-1 shows the recommended method for switching between capture prescalers. This example also clears the prescaler counter and will not generate the "false" interrupt.

## EXAMPLE 9-1: CHANGING BETWEEN CAPTURE PRESCALERS

CLRF	CCP1CON	;Turn CCP module off
MOVLW	NEW_CAPT_PS	3;Load the W reg with
		; the new prescaler
		; mode value and CCP ON
MOVWF	CCP1CON	;Load CCP1CON with this
		; value


### 9.2 Compare Mode

In Compare mode, the 16-bit CCPR1 register value is constantly compared against the TMR1 register pair value. When a match occurs, the RB3/CCP1 pin is:

- · Driven High
- Driven Low
- · Remains Unchanged

The action on the pin is based on the value of control bits CCP1M3:CCP1M0 (CCP1CON<3:0>). At the same time, interrupt flag bit CCP1IF is set.

## FIGURE 9-2: COMPARE MODE OPERATION BLOCK DIAGRAM



### 9.2.1 CCP PIN CONFIGURATION

The user must configure the RB3/CCP1 pin as an output by clearing the TRISB<3> bit.

Note:	Clearing the CCP1CON register will force
	the RB3/CCP1 compare output latch to the
	default low level. This is not the data latch.

### 9.2.2 TIMER1 MODE SELECTION

Timer1 must be running in Timer mode or Synchronized Counter mode if the CCP module is using the compare feature. In Asynchronous Counter mode, the compare operation may not work.

### 9.2.3 SOFTWARE INTERRUPT MODE

When generate software interrupt is chosen the CCP1 pin is not affected. Only a CCP interrupt is generated (if enabled).

### 9.2.4 SPECIAL EVENT TRIGGER

In this mode, an internal hardware trigger is generated which may be used to initiate an action.

The special event trigger output of CCP1 resets the TMR1 register pair. This allows the CCPR1 register to effectively be a 16-bit programmable period register for Timer1.

TABLE 9-2: REGISTERS ASSOCIATED WITH CAPTURE, COMPARE, AND TIMER1

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0		e on DR	all o	e on ther sets
0Bh, 8Bh, 10Bh, 18Bh	INTCON	GIE	PEIE	TOIE	INTE	RBIE	TOIF	INTF	RBIF	0000	000x	0000	000u
0Ch	PIR1	EEIF	CMIF	RCIF	TXIF		CCP1IF	TMR2IF	TMR1IF	0000	-000	0000	-000
8Ch	PIE1	EEIE	CMIE	RCIE	TXIE	_	CCP1IE	TMR2IE	TMR1IE	0000	-000	0000	-000
86h, 186h	TRISB	PORTI	PORTB Data Direction Register								1111	1111	1111
0Eh	TMR1L	Holding	g regist	er for the L	east Signific	cant Byte of	the 16-bit	ΓMR1 regis	ster	xxxx	xxxx	uuuu	uuuu
0Fh	TMR1H	Holding	g regist	er for the M	lost Signific	ant Byte of t	he 16-bit T	MR1regist	er	xxxx	xxxx	uuuu	uuuu
10h	T1CON	_	_	T1CKPS1	T1CKPS0	T1OSCEN	T1SYNC	TMR1CS	TMR10N	00	0000	uu	uuuu
15h	CCPR1L	Captur	e/Com	pare/PWM i	register1 (L	SB)				xxxx	xxxx	uuuu	uuuu
16h	CCPR1H	Captur	Capture/Compare/PWM register1 (MSB)								xxxx	uuuu	uuuu
17h	CCP1CON		_	CCP1X	CCP1Y	CCP1M3	CCP1M2	CCP1M1	CCP1M0	00	0000	00	0000

**Legend:** x = unknown, u = unchanged, - = unimplemented read as '0'. Shaded cells are not used by Capture and Timer1.

### 9.3 PWM Mode


In Pulse Width Modulation (PWM) mode, the CCP1 pin produces up to a 10-bit resolution PWM output. Since the CCP1 pin is multiplexed with the PORTB data latch, the TRISB<3> bit must be cleared to make the CCP1 pin an output.

Note: Clearing the CCP1CON register will force the CCP1 PWM output latch to the default low level. This is not the PORTB I/O data latch.

Figure 9-3 shows a simplified block diagram of the CCP module in PWM mode.


For a step by step procedure on how to set up the CCP module for PWM operation, see **Section 9.3.3 "Set-Up for PWM Operation"**.

## FIGURE 9-3: SIMPLIFIED PWM BLOCK DIAGRAM



A PWM output (Figure 9-4) has a time base (period) and a time that the output stays high (duty cycle). The frequency of the PWM is the inverse of the period (frequency = 1/period).

FIGURE 9-4: PWM OUTPUT



### 9.3.1 PWM PERIOD

The PWM period is specified by writing to the PR2 register. The PWM period can be calculated using the following formula:

PWM period = 
$$[(PR2) + 1] \cdot 4 \cdot \text{Tosc} \cdot \text{TMR2}$$
 prescale value

PWM frequency is defined as 1 / [PWM period].

When TMR2 is equal to PR2, the following three events occur on the next increment cycle:

- · TMR2 is cleared
- The CCP1 pin is set (exception: if PWM duty cycle = 0%, the CCP1 pin will not be set)
- The PWM duty cycle is latched from CCPR1L into CCPR1H

Note: The Timer2 postscaler (see Section 8.0) is not used in the determination of the PWM frequency. The postscaler could be used to have a servo update rate at a different frequency than the PWM output.

#### 9.3.2 PWM DUTY CYCLE

The PWM duty cycle is specified by writing to the CCPR1L register and to the CCP1CON<5:4> bits. Up to 10-bit resolution is available: the CCPR1L contains the eight MSbs and the CCP1CON<5:4> contains the two LSbs. This 10-bit value is represented by CCPR1L:CCP1CON<5:4>. The following equation is used to calculate the PWM duty cycle in time:

PWM duty cycle = 
$$(CCPR1L:CCP1CON < 5:4 >) \cdot Tosc \cdot TMR2 \text{ prescale }$$
 value

CCPR1L and CCP1CON<5:4> can be written to at any time, but the duty cycle value is not latched into CCPR1H until after a match between PR2 and TMR2 occurs (i.e., the period is complete). In PWM mode, CCPR1H is a read-only register.

The CCPR1H register and a 2-bit internal latch are used to double buffer the PWM duty cycle. This double buffering is essential for glitch less PWM operation.

When the CCPR1H and 2-bit latch match TMR2 concatenated with an internal 2-bit Q clock or 2 bits of the TMR2 prescaler, the CCP1 pin is cleared.

Maximum PWM resolution (bits) for a given PWM frequency:

$$\frac{\text{PWM}}{\text{Resolution}} = \frac{\log\left(\frac{Fosc}{Fpwm \times \text{TMR2 Prescaler}}\right)}{\log(2)} \text{ bits}$$

**Note:** If the PWM duty cycle value is longer than the PWM period the CCP1 pin will not be cleared.

For an example PWM period and duty cycle calculation, see the *PICmicro*® *Mid-Range Reference Manual* (DS33023).

### 9.3.3 SET-UP FOR PWM OPERATION

The following steps should be taken when configuring the CCP module for PWM operation:

- Set the PWM period by writing to the PR2 register.
- Set the PWM duty cycle by writing to the CCPR1L register and CCP1CON<5:4> bits.
- Make the CCP1 pin an output by clearing the TRISB<3> bit.
- 4. Set the TMR2 prescale value and enable Timer2 by writing to T2CON.
- 5. Configure the CCP1 module for PWM operation.

TABLE 9-3: EXAMPLE PWM FREQUENCIES AND RESOLUTIONS AT 20 MHz

PWM Frequency	1.22 kHz	4.88 kHz	19.53 kHz	78.12 kHz	156.3 kHz	208.3 kHz
Timer Prescaler (1, 4, 16)	16	4	1	1	1	1
PR2 Value	0xFF	0xFF	0xFF	0x3F	0x1F	0x17
Maximum Resolution (bits)	10	10	10	8	7	6.5

TABLE 9-4: REGISTERS ASSOCIATED WITH PWM AND TIMER2

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR	Value on all other Resets
0Bh, 8Bh, 10Bh, 18Bh	INTCON	GIE	PEIE	TOIE	INTE	RBIE	TOIF	INTF	RBIF	0000 000x	0000 000u
0Ch	PIR1	EEIF	CMIF	RCIF	TXIF	_	CCP1IF	TMR2IF	TMR1IF	0000 -000	0000 -000
8Ch	PIE1	EEIE	CMIE	RCIE	TXIE	1	CCP1IE	TMR2IE	TMR1IE	0000 -000	0000 -000
86h, 186h	TRISB			PC	RTB Data D	irection Regi	ster			1111 1111	1111 1111
11h	TMR2				Timer2 mod	ule's register	-			0000 0000	0000 0000
92h	PR2			Tin	ner2 module	s period regi	ster			1111 1111	1111 1111
12h	T2CON	1	TOUTPS3	TOUTPS2	TOUTPS1	TOUTPS0	TMR2ON	T2CKPS1	T2CKPS0	-000 0000	uuuu uuuu
15h	CCPR1L			Captur	e/Compare/F	PWM register	1 (LSB)			xxxx xxxx	uuuu uuuu
16h	CCPR1H		Capture/Compare/PWM register1 (MSB)								uuuu uuuu
17h	CCP1CON	_	_	CCP1X	CCP1Y	CCP1M3	CCP1M2	CCP1M1	CCP1M0	00 0000	00 0000

Legend: x = unknown, u = unchanged, - = unimplemented read as '0'. Shaded cells are not used by PWM and Timer2.

NOTES:

### 10.0 COMPARATOR MODULE

The Comparator module contains two analog comparators. The inputs to the comparators are multiplexed with the RA0 through RA3 pins. The on-chip Voltage Reference (Section 11.0 "Voltage Reference Module") can also be an input to the comparators.

The CMCON register, shown in Register 10-1, controls the comparator input and output multiplexers. A block diagram of the comparator is shown in Figure 10-1.

### REGISTER 10-1: CMCON REGISTER (ADDRESS: 01Fh)

R-0	R-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
C2OUT	C1OUT	C2INV	C1INV	CIS	CM2	CM1	CM0
hit 7	•	•		•	•		bit 0

bit 7 C2OUT: Comparator 2 Output

When C2INV = 0:

1 = C2 VIN+ > C2 VIN-

0 = C2 VIN+ < C2 VIN-

When C2INV = 1:

1 = C2 VIN+ < C2 VIN-

0 = C2 VIN+ > C2 VIN-

bit 6 C10UT: Comparator 1 Output

When C1INV = 0:

1 = C1 Vin+ > C1 Vin-

0 = C1 VIN+ < C1 VIN-

When C1INV = 1:

1 = C1 VIN+ < C1 VIN-

0 = C1 VIN+ > C1 VIN-

bit 5 C2INV: Comparator 2 Output Inversion

1 = C2 Output inverted

0 = C2 Output not inverted

bit 4 C1INV: Comparator 1 Output Inversion

1 = C1 Output inverted

0 = C1 Output not inverted

bit 3 CIS: Comparator Input Switch

When CM2:CM0: = 001

Then:

1 = C1 VIN- connects to RA3

0 = C1 VIN- connects to RA0

### When CM2:CM0 = 010

Then:

1 = C1 Vin- connects to RA3

C2 VIN- connects to RA2

0 = C1 VIN- connects to RA0

C2 VIN- connects to RA1

bit 2-0 CM2:CM0: Comparator Mode

Figure 10-1 shows the Comparator modes and CM2:CM0 bit settings

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented I	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown


### 10.1 Comparator Configuration

There are eight modes of operation for the comparators. The CMCON register is used to select the mode. Figure 10-1 shows the eight possible modes. The TRISA register controls the data direction of the comparator pins for each mode.

If the Comparator mode is changed, the comparator output level may not be valid for the specified mode change delay shown in Table 17-2.

- **Note 1:** Comparator interrupts should be disabled during a Comparator mode change, otherwise a false interrupt may occur.
  - **2:** Comparators can have an inverted output. See Figure 10-3.

FIGURE 10-1: COMPARATOR I/O OPERATING MODES



The code example in Example 10-1 depicts the steps required to configure the Comparator module. RA3 and RA4 are configured as digital output. RA0 and RA1 are configured as the V- inputs and RA2 as the V+ input to both comparators.

EXAMPLE 10-1: INITIALIZING COMPARATOR MODULE

FLAG_RE	EG EQU	0X20					
CLRF	FLAG_REG	;Init flag register					
CLRF	PORTA	;Init PORTA					
MOVF	CMCON, W	;Load comparator bits					
ANDLW	0xC0	;Mask comparator bits					
IORWF	FLAG_REG,F	;Store bits in flag register					
MOVLW	0x03	;Init comparator mode					
MOVWF	CMCON	;CM<2:0> = 011					
BSF	STATUS, RP0	;Select Bank1					
MOVLW	0x07	;Initialize data direction					
MOVWF	TRISA	;Set RA<2:0> as inputs					
		;RA<4:3> as outputs					
		;TRISA<7:5> always read '0'					
BCF		;Select Bank 0					
CALL	DELAY10	;10µs delay					
MOVF	CMCON, F	Read CMCONto end change					
		;condition					
BCF	•	Clear pending interrupts					
BSF	STATUS,RP0	;Select Bank 1					
BSF		;Enable comparator interrupts					
BCF	•	;Select Bank 0					
BSF		;Enable peripheral interrupts					
BSF	INTCON, GIE	Global interrupt enable					


### 10.2 Comparator Operation

A single comparator is shown in Figure 10-2 along with the relationship between the analog input levels and the digital output. When the analog input at VIN+ is less than the analog input VIN-, the output of the comparator is a digital low level. When the analog input at VIN+ is greater than the analog input VIN-, the output of the comparator is a digital high level. The shaded areas of the output of the comparator in Figure 10-2 represent the uncertainty due to input offsets and response time. See Table 17-2 for Common Mode Voltage.

### 10.3 Comparator Reference

An external or internal reference signal may be used depending on the comparator Operating mode. The analog signal that is present at VIN- is compared to the signal at VIN+, and the digital output of the comparator is adjusted accordingly (Figure 10-2).

### FIGURE 10-2: SINGLE COMPARATOR



### 10.3.1 EXTERNAL REFERENCE SIGNAL

When external voltage references are used, the Comparator module can be configured to have the comparators operate from the same or different reference sources. However, threshold detector applications may require the same reference. The reference signal must be between VSS and VDD, and can be applied to either pin of the comparator(s).

### 10.3.2 INTERNAL REFERENCE SIGNAL

The Comparator module also allows the selection of an internally generated voltage reference for the comparators. **Section 11.0 "Voltage Reference Module"**, contains a detailed description of the Voltage Reference Module that provides this signal. The internal reference signal is used when the comparators are in mode CM<2:0>=010 (Figure 10-1). In this mode, the internal voltage reference is applied to the VIN+ pin of both comparators.

### 10.4 Comparator Response Time

Response time is the minimum time, after selecting a new reference voltage or input source, before the comparator output is to have a valid level. If the internal reference is changed, the maximum delay of the internal voltage reference must be considered when using the comparator outputs. Otherwise, the maximum delay of the comparators should be used (Table 17-2).


### 10.5 Comparator Outputs

The comparator outputs are read through the CMCON register. These bits are read only. The comparator outputs may also be directly output to the RA3 and RA4 I/O pins. When the CM<2:0> = 110 or 001, multiplexors in the output path of the RA3 and RA4/T0CK1 pins will switch and the output of each pin will be the unsynchronized output of the comparator. The uncertainty of each of the comparators is related to the input offset voltage and the response time given in the specifications. Figure 10-3 shows the comparator output block diagram.

The TRISA bits will still function as an output enable/ disable for the RA3 and RA4/T0CK1 pins while in this mode.

- Note 1: When reading the PORT register, all pins configured as analog inputs will read as a '0'. Pins configured as digital inputs will convert an analog input, according to the Schmitt Trigger input specification.
  - 2: Analog levels on any pin that is defined as a digital input may cause the input buffer to consume more current than is specified.

### FIGURE 10-3: MODIFIED COMPARATOR OUTPUT BLOCK DIAGRAM



### 10.6 Comparator Interrupts

The comparator interrupt flag is set whenever there is a change in the output value of either comparator. Software will need to maintain information about the status of the output bits, as read from CMCON<7:6>, to determine the actual change that has occurred. The CMIF bit, PIR1<6>, is the comparator interrupt flag. The CMIF bit must be Reset by clearing '0'. Since it is also possible to write a '1' to this register, a simulated interrupt may be initiated.

The CMIE bit (PIE1<6>) and the PEIE bit (INTCON<6>) must be set to enable the interrupt. In addition, the GIE bit must also be set. If any of these bits are clear, the interrupt is not enabled, though the CMIF bit will still be set if an interrupt condition occurs.

Note: If a change in the CMCON register (C1OUT or C2OUT) should occur when a read operation is being executed (start of the Q2 cycle), then the CMIF (PIR1<6>) interrupt flag may not get set.

The user, in the interrupt service routine, can clear the interrupt in the following manner:

- a) Any write or read of CMCON. This will end the mismatch condition.
- b) Clear flag bit CMIF.

A mismatch condition will continue to set flag bit CMIF. Reading CMCON will end the mismatch condition and allow flag bit CMIF to be cleared.

## 10.7 Comparator Operation During Sleep

When a comparator is active and the device is placed in Sleep mode, the comparator remains active and the interrupt is functional if enabled. This interrupt will wake-up the device from Sleep mode when enabled. While the comparator is powered-up, higher Sleep currents than shown in the power-down current specification will occur. Each comparator that is operational will consume additional current as shown in the comparator specifications. To minimize power consumption while in Sleep mode, turn off the comparators, CM<2:0> = 111, before entering Sleep. If the device wakes up from Sleep, the contents of the CMCON register are not affected.

#### 10.8 Effects of a Reset

A device Reset forces the CMCON register to its Reset state. This forces the Comparator module to be in the comparator Reset mode, CM2:CM0 = 000. This ensures that all potential inputs are analog inputs. Device current is minimized when analog inputs are present at Reset time. The comparators will be powered-down during the Reset interval.

## 10.9 Analog Input Connection Considerations

A simplified circuit for an analog input is shown in Figure 10-4. Since the analog pins are connected to a digital output, they have reverse biased diodes to VDD and Vss. The analog input therefore, must be between Vss and VDD. If the input voltage deviates from this range by more than 0.6V in either direction, one of the diodes is forward biased and a latch-up may occur. A maximum source impedance of  $10 \text{ k}\Omega$ recommended for the analog sources. Any external component connected to an analog input pin, such as a capacitor or a Zener diode, should have very little leakage current.

FIGURE 10-4: ANALOG INPUT MODE




TABLE 10-1: REGISTERS ASSOCIATED WITH COMPARATOR MODULE

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR	Value on All Other Resets
1Fh	CMCON	C2OUT	C1OUT	C2INV	C1NV	CIS	CM2	CM1	CM0	0000 0000	0000 0000
0Bh, 8Bh, 10Bh, 18Bh	INTCON	GIE	PEIE	TOIE	INTE	RBIE	TOIF	INTF	RBIF	0000 000x	0000 000u
0Ch	PIR1	EEIF	CMIF	RCIF	TXIF	_	CCP1IF	TMR2IF	TMR1IF	0000 -000	0000 -000
8Ch	PIE1	EEIE	CMIE	RCIE	TXIE	_	CCP1IE	TMR2IE	TMR1IE	0000 -000	0000 -000
85h	TRISA	TRISA7	TRISA6	TRISA5	TRISA4	TRISA3	TRISA2	TRISA1	TRISA0	1111 1111	1111 1111

**Legend:** x = Unknown, u = Unchanged, - = Unimplemented, read as '0'

## 11.0 VOLTAGE REFERENCE MODULE

The Voltage Reference is a 16-tap resistor ladder network that provides a selectable voltage reference. The resistor ladder is segmented to provide two ranges of VREF values and has a power-down function to conserve power when the reference is not being used. The VRCON register controls the operation of the reference as shown in Figure 11-1. The block diagram is given in Figure 11-1.

### 11.1 Voltage Reference Configuration

The Voltage Reference can output 16 distinct voltage levels for each range.

The equations used to calculate the output of the Voltage Reference are as follows:

if 
$$VRR = 1$$
:

$$V_{REF} = \frac{V_{R} < 3:0>}{24} \times V_{DD}$$

if VRR = 0:

$$V_{REF} = \left(V_{DD} \times \frac{1}{4}\right) + \frac{V_{R} < 3:0>}{32} \times V_{DD}$$

The setting time of the Voltage Reference must be considered when changing the VREF output (Table 17-3). Example 11-1 demonstrates how Voltage Reference is configured for an output voltage of 1.25V with VDD = 5.0V.

### REGISTER 11-1: VRCON REGISTER (ADDRESS: 9Fh)

R/W-0	R/W-0	R/W-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0
VREN	VROE	Vrr	_	VR3	VR2	Vr1	Vr0
bit 7							bit 0

bit 7 VREN: VREF Enable

1 = VREF circuit powered on

0 = VREF circuit powered down, no IDD drain

bit 6 VROE: VREF Output Enable

1 = VREF is output on RA2 pin

0 = VREF is disconnected from RA2 pin

bit 5 VRR: VREF Range selection

1 = Low Range

0 = High Range

bit 4 **Unimplemented:** Read as '0'

bit 3-0 **VR<3:0>**: VREF value selection  $0 \le VR$  [3:0]  $\le 15$ 

When VRR = 1: VREF = (VR < 3:0 > / 24) \* VDD


When VRR = 0: VREF = 1/4 \* VDD + (VR<3:0>/32) \* VDD

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### FIGURE 11-1: VOLTAGE REFERENCE BLOCK DIAGRAM



## EXAMPLE 11-1: VOLTAGE REFERENCE CONFIGURATION

MOVLW	0x02	;4 Inputs Muxed
MOVWF	CMCON	;to 2 comps.
BSF	STATUS, RP0	;go to Bank 1
MOVLW	0x07	;RA3-RA0 are
MOVWF	TRISA	;outputs
MOVLW	0xA6	;enable VREF
MOVWF	VRCON	;low range set VR<3:0>=6
BCF	STATUS, RP0	;go to Bank 0
CALL	DELAY10	;10µs delay

### 11.2 Voltage Reference Accuracy/Error

The full range of Vss to VDD cannot be realized due to the construction of the module. The transistors on the top and bottom of the resistor ladder network (Figure 11-1) keep VREF from approaching Vss or VDD. The Voltage Reference is VDD derived and therefore, the VREF output changes with fluctuations in VDD. The tested absolute accuracy of the Voltage Reference can be found in Table 17-3.

### 11.3 Operation During Sleep

When the device wakes up from Sleep through an interrupt or a Watchdog Timer time out, the contents of the VRCON register are not affected. To minimize current consumption in Sleep mode, the Voltage Reference should be disabled.

### 11.4 Effects of a Reset

A device Reset disables the Voltage Reference by clearing bit VREN (VRCON<7>). This Reset also disconnects the reference from the RA2 pin by clearing bit VROE (VRCON<6>) and selects the high voltage range by clearing bit VRR (VRCON<5>). The VREF value select bits, VRCON<3:0>, are also cleared.

### 11.5 Connection Considerations

The Voltage Reference Module operates independently of the comparator module. The output of the reference generator may be connected to the RA2 pin if the TRISA<2> bit is set and the VROE bit, VRCON<6>, is set. Enabling the Voltage Reference output onto the RA2 pin with an input signal present will increase current consumption. Connecting RA2 as a digital output with VREF enabled will also increase current consumption.

The RA2 pin can be used as a simple D/A output with limited drive capability. Due to the limited drive capability, a buffer must be used in conjunction with the Voltage Reference output for external connections to VREF. Figure 11-2 shows an example buffering technique.

### FIGURE 11-2: VOLTAGE REFERENCE OUTPUT BUFFER EXAMPLE




TABLE 11-1: REGISTERS ASSOCIATED WITH VOLTAGE REFERENCE

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value On POR	Value On All Other Resets
9Fh	VRCON	VREN	VROE	VRR		VR3	VR2	VR1	VR0	000- 0000	000- 0000
1Fh	CMCON	C2OUT	C1OUT	C2INV	C1INV	CIS	CM2	CM1	CM0	0000 0000	0000 0000
85h	TRISA	TRISA7	TRISA6	TRISA5	TRISA4	TRISA3	TRISA2	TRISA1	TRISA0	1111 1111	1111 1111

**Legend:** — = Unimplemented, read as '0'.

# 12.0 UNIVERSAL SYNCHRONOUS ASYNCHRONOUS RECEIVER TRANSMITTER (USART) MODULE

The Universal Synchronous Asynchronous Receiver Transmitter (USART) is also known as a Serial Communications Interface or SCI. The USART can be configured as a full-duplex asynchronous system that can communicate with peripheral devices such as CRT terminals and personal computers, or it can be configured as a half-duplex synchronous system that can communicate with peripheral devices such as A/D or D/A integrated circuits, Serial EEPROMs, etc.

The USART can be configured in the following modes:

- Asynchronous (full-duplex)
- Synchronous Master (half-duplex)
- Synchronous Slave (half-duplex)

Bit SPEN (RCSTA<7>), and bits TRISB<2:1>, have to be set in order to configure pins RB2/TX/CK and RB1/RX/DT as the Universal Synchronous Asynchronous Receiver Transmitter.

Register 12-1 shows the Transmit Status and Control Register (TXSTA) and Register 12-2 shows the Receive Status and Control Register (RCSTA).

### REGISTER 12-1: TXSTA: TRANSMIT STATUS AND CONTROL REGISTER (ADDRESS: 98h)

R/W-0	R/W-0	R/W-0	R/W-0	U-0	R/W-0	R-1	R/W-0
CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D
bit 7							bit 0

bit 7 CSRC: Clock Source Select bit

Asynchronous mode

Don't care

Synchronous mode

- 1 = Master mode (Clock generated internally from BRG)
- 0 = Slave mode (Clock from external source)
- bit 6 TX9: 9-bit Transmit Enable bit
  - 1 = Selects 9-bit transmission
  - 0 = Selects 8-bit transmission
- bit 5 **TXEN**: Transmit Enable bit<sup>(1)</sup>
  - 1 = Transmit enabled
  - 0 = Transmit disabled
- bit 4 SYNC: USART Mode Select bit
  - 1 = Synchronous mode
  - 0 = Asynchronous mode
- bit 3 **Unimplemented:** Read as '0'
- bit 2 BRGH: High Baud Rate Select bit

Asynchronous mode

- 1 = High speed
- 0 = Low speed

Synchronous mode

Unused in this mode

bit 1 TRMT: Transmit Shift Register Status bit

1 = TSR empty

0 = TSR full

bit 0 **TX9D**: 9th bit of transmit data. Can be parity bit.

Note: SREN/CREN overrides TXEN in SYNC mode.

### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

#### REGISTER 12-2: RCSTA: RECEIVE STATUS AND CONTROL REGISTER (ADDRESS: 18h)

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R-0	R-0	R-x
SPEN	RX9	SREN	CREN	ADEN	FERR	OERR	RX9D
bit 7							bit 0

bit 0

bit 7 SPEN: Serial Port Enable bit

(Configures RB1/RX/DT and RB2/TX/CK pins as serial port pins when bits TRISB<2:1> are set)

1 = Serial port enabled 0 = Serial port disabled

bit 6 RX9: 9-bit Receive Enable bit

1 = Selects 9-bit reception

0 = Selects 8-bit reception

bit 5 SREN: Single Receive Enable bit

Asynchronous mode:

Don't care

Synchronous mode - master:

1 = Enables single receive

0 = Disables single receive

This bit is cleared after reception is complete.

Synchronous mode - slave:

Unused in this mode

bit 4 CREN: Continuous Receive Enable bit

Asynchronous mode:

1 = Enables continuous receive

0 = Disables continuous receive

Synchronous mode:

1 = Enables continuous receive until enable bit CREN is cleared (CREN overrides SREN)

0 = Disables continuous receive

bit 3 ADEN: Address Detect Enable bit

Asynchronous mode 9-bit (RX9 = 1):

1 = Enables address detection, enable interrupt and load of the receive buffer when RSR<8> is set

0 = Disables address detection, all bytes are received, and ninth bit can be used as parity bit Asynchronous mode 8-bit (RX9 = 0):

Unused in this mode

Synchronous mode

Unused in this mode

bit 2 FERR: Framing Error bit

1 = Framing error (Can be updated by reading RCREG register and receive next valid byte)

0 = No framing error

bit 1 **OERR**: Overrun Error bit

1 = Overrun error (Can be cleared by clearing bit CREN)

0 = No overrun error

bit 0 **RX9D**: 9th bit of received data (Can be parity bit)

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

# 12.1 USART Baud Rate Generator (BRG)

The BRG supports both the Asynchronous and Synchronous modes of the USART. It is a dedicated 8-bit baud rate generator. The SPBRG register controls the period of a free running 8-bit timer. In Asynchronous mode bit BRGH (TXSTA<2>) also controls the baud rate. In Synchronous mode bit BRGH is ignored. Table 12-1 shows the formula for computation of the baud rate for different USART modes, which only apply in Master mode (internal clock).

Given the desired baud rate and Fosc, the nearest integer value for the SPBRG register can be calculated using the formula in Table 12-1. From this, the error in baud rate can be determined.

Example 12-1 shows the calculation of the baud rate error for the following conditions:

Fosc = 16 MHz

Desired Baud Rate = 9600

BRGH = 0

SYNC = 0

## EXAMPLE 12-1: CALCULATING BAUD RATE ERROR

Desired Baud Rate = 
$$\frac{Fosc}{64(x+1)}$$

$$9600 = \frac{16000000}{64(x+1)}$$

$$x = 25.042$$

Calculated Baud Rate = 
$$\frac{16000000}{64(25+1)}$$
 = 9615

$$Error = \frac{(Calculated \ Baud \ Rate - Desired \ Baud \ Rate)}{Desired \ Baud \ Rate}$$

$$=\frac{9615-9600}{9600}=0.16\%$$

It may be advantageous to use the high baud rate (BRGH = 1) even for slower baud clocks. This is because the Fosc/(16(X + 1)) equation can reduce the baud rate error in some cases.

Writing a new value to the SPBRG register, causes the BRG timer to be Reset (or cleared), this ensures the BRG does not wait for a timer overflow before outputting the new baud rate.

TABLE 12-1: BAUD RATE FORMULA

SYNC	BRGH = 0 (Low Speed)	BRGH = 1 (High Speed)
0	(Asynchronous) Baud Rate = Fosc/(64(X+1))	Baud Rate= Fosc/(16(X+1))
1	(Synchronous) Baud Rate = Fosc/(4(X+1))	NA

**Legend:** X = value in SPBRG (0 to 255)

#### TABLE 12-2: REGISTERS ASSOCIATED WITH BAUD RATE GENERATOR

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR	Value on all other Resets
98h	TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000 -010	0000 -010
18h	RCSTA	SPEN	RX9	SREN	CREN	ADEN	FERR	OERR	RX9D	0000 000x	0000 000x
99h	SPBRG		Baud Rate Generator Register								0000 0000

**Legend:** x = unknown, - = unimplemented read as '0'.

Shaded cells are not used by the BRG.

TABLE 12-3: BAUD RATES FOR SYNCHRONOUS MODE

BAUD	Fosc = 20 M	lHz	SPBRG	16 MHz		SPBRG	10 MHz		SPBRG
RATE (K)	KBAUD	ERROR	value (decimal)	KBAUD	ERROR	value (decimal)	KBAUD	ERROR	value (decimal)
0.3	NA	_	_	NA	_	_	NA	_	_
1.2	NA	_	_	NA	_	_	NA	_	_
2.4	NA	_	_	NA	_	_	NA	_	_
9.6	NA	_	_	NA	_		9.766	+1.73%	255
19.2	19.53	+1.73%	255	19.23	+0.16%	207	19.23	+0.16%	129
76.8	76.92	+0.16%	64	76.92	+0.16%	51	75.76	-1.36%	32
96	96.15	+0.16%	51	95.24	-0.79%	41	96.15	+0.16%	25
300	294.1	-1.96	16	307.69	+2.56%	12	312.5	+4.17%	7
500	500	0	9	500	0	7	500	0	4
HIGH	5000	_	0	4000	_	0	2500		0
LOW	19.53	_	255	15.625	_	255	9.766	_	255

BAUD	Fosc = 7.15	909 MHz	SPBRG	5.0688 MHz		-	4 MHz		SPBRG
RATE (K)	KBAUD	ERROR	value (decimal)	KBAUD	ERROR	value (decimal)	KBAUD	ERROR	value (decimal)
0.3	NA	_	_	NA	_	_	NA	_	_
1.2	NA	_	_	NA	_	_	NA	_	_
2.4	NA	_	_	NA	_	_	NA	_	_
9.6	9.622	+0.23%	185	9.6	0	131	9.615	+0.16%	103
19.2	19.24	+0.23%	92	19.2	0	65	19.231	+0.16%	51
76.8	77.82	+1.32	22	79.2	+3.13%	15	75.923	+0.16%	12
96	94.20	-1.88	18	97.48	+1.54%	12	1000	+4.17%	9
300	298.3	-0.57	5	316.8	5.60%	3	NA	_	_
500	NA	_	_	NA	_	_	NA	_	_
HIGH	1789.8	_	0	1267	_	0	100	_	0
LOW	6.991		255	4.950		255	3.906	_	255

BAUD	Fosc = 3.579	9545 MHz	SPBRG	1 MHz		SPBRG	32.768 kHz		SPBRG
RATE (K)	KBAUD	ERROR	value (decimal)	KBAUD	ERROR	value (decimal)	KBAUD	ERROR	value (decimal)
0.3	NA	_	_	NA	_	_	0.303	+1.14%	26
1.2	NA	_	_	1.202	+0.16%	207	1.170	-2.48%	6
2.4	NA		_	2.404	+0.16%	103	NA	_	_
9.6	9.622	+0.23%	92	9.615	+0.16%	25	NA	_	_
19.2	19.04	-0.83%	46	19.24	+0.16%	12	NA	_	_
76.8	74.57	-2.90%	11	83.34	+8.51%	2	NA	_	_
96	99.43	+3.57%	8	NA	_	_	NA	_	_
300	298.3	0.57%	2	NA	_	_	NA	_	_
500	NA	_	_	NA	_	_		_	_
HIGH	894.9	_	0	250	_	0	8.192	_	0
LOW	3.496	_	255	0.9766	_	255	0.032		255

TABLE 12-4: BAUD RATES FOR ASYNCHRONOUS MODE (BRGH = 0)

BAUD	Fosc = 20 M	lHz	SPBRG	16 MHz		SPBRG	10 MHz		SPBRG
RATE (K)	KBAUD	ERROR	value (decimal)	KBAUD	ERROR	value (decimal)	KBAUD	ERROR	value (decimal)
0.3	NA	_	_	NA	_	_	NA	_	_
1.2	1.221	+1.73%	255	1.202	+0.16%	207	1.202	+0.16%	129
2.4	2.404	+0.16%	129	2.404	+0.16%	103	2.404	+0.16%	64
9.6	9.469	-1.36%	32	9.615	+0.16%	25	9.766	+1.73%	15
19.2	19.53	+1.73%	15	19.23	+0.16%	12	19.53	+1.73V	7
76.8	78.13	+1.73%	3	83.33	+8.51%	2	78.13	+1.73%	1
96	104.2	+8.51%	2	NA	_	_	NA	_	_
300	312.5	+4.17%	0	NA	_	_	NA	_	_
500	NA	_	_	NA	_	_	NA	_	_
HIGH	312.5	_	0	250	_	0	156.3	_	0
LOW	1.221	_	255	0.977	_	255	0.6104	_	255

BAUD	Fosc = 7.159	909 MHz		5.0688 MHz			4 MHz		SPBRG
RATE (K)	KBAUD	ERROR	value (decimal)	KBAUD	ERROR	value (decimal)	KBAUD	ERROR	value (decimal)
0.3	NA	_	_	0.31	+3.13%	255	0.3005	-0.17%	207
1.2	1.203	+0.23%	92	1.2	0	65	1.202	+1.67%	51
2.4	2.380	-0.83%	46	2.4	0	32	2.404	+1.67%	25
9.6	9.322	-2.90%	11	9.9	+3.13%	7	NA	_	_
19.2	18.64	-2.90%	5	19.8	+3.13%	3	NA	_	_
76.8	NA	_	_	79.2	+3.13%	0	NA	_	_
96	NA	_	_	NA	_	_	NA	_	_
300	NA	_	_	NA	_	_	NA	_	_
500	NA	_	_	NA	_	_	NA	_	_
HIGH	111.9	_	0	79.2	_	0	62.500	_	0
LOW	0.437	_	255	0.3094	_	255	3.906	_	255

BAUD	Fosc = 3.579	9545 MHz	SPBRG	1 MHz		_	32.768 kHz		SPBRG
RATE (K)	KBAUD	ERROR	value (decimal)	KBAUD	ERROR	value (decimal)	KBAUD	ERROR	value (decimal)
0.3	0.301	+0.23%	185	0.300	+0.16%	51	0.256	-14.67%	1
1.2	1.190	-0.83%	46	1.202	+0.16%	12	NA	_	_
2.4	2.432	+1.32%	22	2.232	-6.99%	6	NA	_	_
9.6	9.322	-2.90%	5	NA	_	_	NA	_	_
19.2	18.64	-2.90%	2	NA	_	_	NA	_	_
76.8	NA	_	_	NA	_	_	NA	_	_
96	NA	_	_	NA	_	_	NA	_	_
300	NA	_	_	NA	_	_	NA	_	_
500	NA	_	_	NA	_	_	NA	_	_
HIGH	55.93	_	0	15.63	_	0	0.512	_	0
LOW	0.2185	_	255	0.0610	_	255	0.0020	_	255

TABLE 12-5: BAUD RATES FOR ASYNCHRONOUS MODE (BRGH = 1)

BAUD	Fosc = 20 M	lHz	SPBRG	16 MHz		SPBRG	10 MHz		SPBRG	
RATE (K)	KBAUD	ERROR	value (decimal)	KBAUD	ERROR	value (decimal)	KBAUD	ERROR	value (decimal)	
9600	9.615	+0.16%	129	9.615	+0.16%	103	9.615	+0.16%	64	
19200	19.230	+0.16%	64	19.230	+0.16%	51	18.939	-1.36%	32	
38400	37.878	-1.36%	32	38.461	+0.16%	25	39.062	+1.7%	15	
57600	56.818	-1.36%	21	58.823	+2.12%	16	56.818	-1.36%	10	
115200	113.636	-1.36%	10	111.111	-3.55%	8	125	+8.51%	4	
250000	250	0	4	250	0	3	NA	_	_	
625000	625	0	1	NA	_	_	625	0	0	
1250000	1250	0	0	NA	_	_	NA	_	_	

BAUD	Fosc = 7.16	MHz	SPBRG	5.068 MHz		SPBRG	4 MHz		SPBRG
RATE (K)	KBAUD	ERROR	value (decimal)	KBAUD	ERROR	value (decimal)	KBAUD	ERROR	value (decimal)
9600	9.520	-0.83%	46	9598.485	0.016%	32	9615.385	0.160%	25
19200	19.454	+1.32%	22	18632.35	-2.956%	16	19230.77	0.160%	12
38400	37.286	-2.90%	11	39593.75	3.109%	7	35714.29	-6.994%	6
57600	55.930	-2.90%	7	52791.67	-8.348%	5	62500	8.507%	3
115200	111.860	-2.90%	3	105583.3	-8.348%	2	125000	8.507%	1
250000	NA	_	_	316750	26.700%	0	250000	0.000%	0
625000	NA	_	_	NA	_	_	NA	_	_
1250000	NA	_	_	NA	_	_	NA	_	_

BAUD	Fosc = 3.579	9 MHz	SPBRG	1 MHz		SPBRG	32.768 kHz		SPBRG
RATE (K)	KBAUD	ERROR	value (decimal)	KBAUD	ERROR	value (decimal)	KBAUD	ERROR	value (decimal)
9600	9725.543	1.308%	22	8.928	-6.994%	6	NA	NA	NA
19200	18640.63	-2.913%	11	20833.3	8.507%	2	NA	NA	NA
38400	37281.25	-2.913%	5	31250	-18.620%	1	NA	NA	NA
57600	55921.88	-2.913%	3	62500	+8.507	0	NA	NA	NA
115200	111243.8	-2.913%	1	NA	_	_	NA	NA	NA
250000	223687.5	-10.525%	0	NA	_	_	NA	NA	NA
625000	NA	_	_	NA	_	_	NA	NA	NA
1250000	NA	_	_	NA	_	_	NA	NA	NA

The data on the RB1/RX/DT pin is sampled three times by a majority detect circuit to determine if a high or a low level is present at the RX pin. If bit BRGH (TXSTA<2>) is clear (i.e., at the low baud rates), the sampling is done on the seventh, eighth and ninth falling edges of a x16 clock (Figure 12-3). If bit BRGH is set (i.e., at the high baud rates), the sampling is done on the 3 clock edges preceding the second rising edge after the first falling edge of a x4 clock (Figure 12-4 and Figure 12-5).

FIGURE 12-1: RX PIN SAMPLING SCHEME. BRGH = 0




FIGURE 12-2: RX PIN SAMPLING SCHEME, BRGH = 1






FIGURE 12-3: RX PIN SAMPLING SCHEME, BRGH = 1





### FIGURE 12-4: RX PIN SAMPLING SCHEME, BRGH = 0 OR BRGH = 1

### 12.2 USART Asynchronous Mode

In this mode, the USART uses standard non-return-to-zero (NRZ) format (one Start bit, eight or nine data bits and one Stop bit). The most common data format is 8-bit. A dedicated 8-bit baud rate generator is used to derive baud rate frequencies from the oscillator. The USART transmits and receives the LSb first. The USART's transmitter and receiver are functionally independent but use the same data format and baud rate. The baud rate generator produces a clock either x16 or x64 of the bit shift rate, depending on bit BRGH (TXSTA<2>). Parity is not supported by the hardware, but can be implemented in software (and stored as the ninth data bit). Asynchronous mode is stopped during Sleep.

Asynchronous mode is selected by clearing bit SYNC (TXSTA<4>).

The USART Asynchronous module consists of the following important elements:

- · Baud Rate Generator
- Sampling Circuit
- Asynchronous Transmitter
- Asynchronous Receiver

## 12.2.1 USART ASYNCHRONOUS TRANSMITTER

The USART transmitter block diagram is shown in Figure 12-5. The heart of the transmitter is the transmit (serial) shift register (TSR). The shift register obtains its data from the read/write transmit buffer, TXREG. The TXREG register is loaded with data in software. The TSR register is not loaded until the Stop bit has been transmitted from the previous load. As soon as the Stop bit is transmitted, the TSR is loaded with new data from the TXREG register (if available). Once the TXREG register transfers the data to the TSR register (occurs in one TCY), the TXREG register is empty and flag bit TXIF (PIR1<4>) is set. This interrupt can be enabled/disabled by setting/clearing enable bit TXIE (PIE1<4>). Flag bit TXIF will be set regardless of the state of enable bit TXIE and cannot be cleared in


software. It will Reset only when new data is loaded into the TXREG register. While flag bit TXIF indicated the status of the TXREG register, another bit TRMT (TXSTA<1>) shows the status of the TSR register. Status bit TRMT is a read only bit which is set when the TSR register is empty. No interrupt logic is tied to this bit, so the user has to poll this bit in order to determine if the TSR register is empty.

- **Note 1:** The TSR register is not mapped in data memory so it is not available to the user.
  - 2: Flag bit TXIF is set when enable bit TXEN is set.

Transmission is enabled by setting enable bit TXEN (TXSTA<5>). The actual transmission will not occur until the TXREG register has been loaded with data and the baud rate generator (BRG) has produced a shift clock (Figure 12-5). The transmission can also be started by first loading the TXREG register and then setting enable bit TXEN. Normally when transmission is first started, the TSR register is empty, so a transfer to the TXREG register will result in an immediate transfer to TSR resulting in an empty TXREG. A back-to-back transfer is thus possible (Figure 12-7). Clearing enable bit TXEN during a transmission will cause the transmission to be aborted and will Reset the transmitter. As a result the RB2/TX/CK pin will revert to hi-impedance.

In order to select 9-bit transmission, transmit bit TX9 (TXSTA<6>) should be set and the ninth bit should be written to TX9D (TXSTA<0>). The ninth bit must be written before writing the 8-bit data to the TXREG register. This is because a data write to the TXREG register can result in an immediate transfer of the data to the TSR register (if the TSR is empty). In such a case, an incorrect ninth data bit maybe loaded in the TSR register.


FIGURE 12-5: USART TRANSMIT BLOCK DIAGRAM




Follow these steps when setting up an Asynchronous Transmission:

- TRISB<1> bit needs to be set and TRISB<2> bit cleared in order to configure pins RB2/TX/CK and RB1/RX/DT as the Universal Synchronous Asynchronous Receiver Transmitter pins.
- Initialize the SPBRG register for the appropriate baud rate. If a high-speed baud rate is desired, set bit BRGH. (Section 12.1 "USART Baud Rate Generator (BRG)")
- 3. Enable the asynchronous serial port by clearing bit SYNC and setting bit SPEN.
- If interrupts are desired, then set enable bit TXIE.
- If 9-bit transmission is desired, then set transmit bit TX9.
- Enable the transmission by setting bit TXEN, which will also set bit TXIF.
- If 9-bit transmission is selected, the ninth bit should be loaded in bit TX9D.
- 8. Load data to the TXREG register (starts transmission).

### FIGURE 12-6: ASYNCHRONOUS TRANSMISSION



### FIGURE 12-7: ASYNCHRONOUS TRANSMISSION (BACK TO BACK)



### TABLE 12-6: REGISTERS ASSOCIATED WITH ASYNCHRONOUS TRANSMISSION

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR	Value on all other Resets
0Ch	PIR1	EEIF	CMIF	RCIF	TXIF		CCP1IF	TMR2IF	TMR1IF	0000 -000	0000 -000
18h	RCSTA	SPEN	RX9	SREN	CREN	ADEN	FERR	OERR	RX9D	0000 000x	0000 000x
19h	TXREG	USART Trai	nsmit dat	a register			_			0000 0000	0000 0000
8Ch	PIE1	EEIE	CMIE	RCIE	TXIE	_	CCP1IE	TMR2IE	TMR1IE	0000 -000	0000 -000
98h	TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000 -010	0000 -010
99h	SPBRG	Baud Rate Generator Register								0000 0000	0000 0000

 $\begin{tabular}{ll} \textbf{Legend:} & $x=$ unknown, $-=$ unimplemented locations read as '0'. \\ & Shaded cells are not used for Asynchronous Transmission. \\ \end{tabular}$ 

## 12.2.2 USART ASYNCHRONOUS RECEIVER


The receiver block diagram is shown in Figure 12-8. The data is received on the RB1/RX/DT pin and drives the data recovery block. The data recovery block is actually a high-speed shifter operating at x16 times the baud rate, whereas the main receive serial shifter operates at the bit rate or at Fosc.

When Asynchronous mode is selected, reception is enabled by setting bit CREN (RCSTA<4>).


The heart of the receiver is the receive (serial) shift register (RSR). After sampling the Stop bit, the received data in the RSR is transferred to the RCREG register (if it is empty). If the transfer is complete, flag bit RCIF (PIR1<5>) is set. The actual interrupt can be enabled/disabled by setting/clearing enable bit RCIE (PIE1<5>). Flag bit RCIF is a read-only bit, which is cleared by the hardware. It is cleared when the RCREG register has been read and is empty. The RCREG is a

double buffered register, (i.e., it is a two deep FIFO). It is possible for two bytes of data to be received and transferred to the RCREG FIFO and a third byte begin shifting to the RSR register. On the detection of the Stop bit of the third byte, if the RCREG register is still full then overrun error bit OERR (RCSTA<1>) will be set. The word in the RSR will be lost. The RCREG register can be read twice to retrieve the two bytes in the FIFO. Overrun bit OERR has to be cleared in software. This is done by resetting the receive logic (CREN is cleared and then set). If bit OERR is set, transfers from the RSR register to the RCREG register are inhibited, so it is essential to clear error bit OERR if it is set. Framing error bit FERR (RCSTA<2>) is set if a Stop bit is detected as clear. Bit FERR and the 9th receive bit are buffered the same way as the receive data. Reading the RCREG, will load bits RX9D and FERR with new values, therefore it is essential for the user to read the RCSTA register before reading RCREG register in order not to lose the old FERR and RX9D information.


FIGURE 12-8: USART RECEIVE BLOCK DIAGRAM




#### FIGURE 12-9: ASYNCHRONOUS RECEPTION WITH ADDRESS DETECT



### FIGURE 12-10: ASYNCHRONOUS RECEPTION WITH ADDRESS BYTE FIRST



# FIGURE 12-11: ASYNCHRONOUS RECEPTION WITH ADDRESS BYTE FIRST FOLLOWED BY VALID DATA BYTE



Follow these steps when setting up an Asynchronous Reception:

- TRISB<1> bit needs to be set and TRISB<2> bit cleared in order to configure pins RB2/TX/CK and RB1/RX/DT as the Universal Synchronous Asynchronous Receiver Transmitter pins.
- Initialize the SPBRG register for the appropriate baud rate. If a high-speed baud rate is desired, set bit BRGH. (Section 12.1 "USART Baud Rate Generator (BRG)").
- 3. Enable the asynchronous serial port by clearing bit SYNC, and setting bit SPEN.
- If interrupts are desired, then set enable bit RCIE.
- 5. If 9-bit reception is desired, then set bit RX9.
- 6. Enable the reception by setting bit CREN.
- Flag bit RCIF will be set when reception is complete and an interrupt will be generated if enable bit RCIE was set.
- 8. Read the RCSTA register to get the ninth bit (if enabled) and determine if any error occurred during reception.
- Read the 8-bit received data by reading the RCREG register.
- If any error occurred, clear the error by clearing enable bit CREN.

### TABLE 12-7: REGISTERS ASSOCIATED WITH ASYNCHRONOUS RECEPTION

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR	Value on all other Resets
0Ch	PIR1	EEIF	CMIF	RCIF	TXIF		CCP1IF	TMR2IF	TMR1IF	0000 -000	0000 -000
18h	RCSTA	SPEN	RX9	SREN	CREN	ADEN	FERR	OERR	RX9D	0000 000x	0000 000x
1Ah	RCREG	USART R	eceive d	ata regis	ter					0000 0000	0000 0000
8Ch	PIE1	EEIE	CMIE	RCIE	TXIE	_	CCP1IE	TMR2IE	TMR1IE	0000 -000	0000 -000
98h	TXSTA	CSRC	TX9	TXEN	SYNC	1	BRGH	TRMT	TX9D	0000 -010	0000 -010
99h	SPBRG	RG Baud Rate Generator Register							0000 0000	0000 0000	

 $\textbf{Legend:} \quad \textbf{x} = \text{unknown, -= unimplemented locations read as '0'}. \label{eq:locations} \textbf{Shaded cells are not used for Asynchronous Reception.}$ 

### 12.3 USART Address Detect Function

## 12.3.1 USART 9-BIT RECEIVER WITH ADDRESS DETECT

When the RX9 bit is set in the RCSTA register, 9 bits are received and the ninth bit is placed in the RX9D bit of the RCSTA register. The USART module has a special provision for multi-processor communication. Multiprocessor communication is enabled by setting the ADEN bit (RCSTA<3>) along with the RX9 bit. The port is now programmed such that when the last bit is received, the contents of the receive shift register (RSR) are transferred to the receive buffer, the ninth bit of the RSR (RSR<8>) is transferred to RX9D, and the receive interrupt is set if and only if RSR<8> = 1. This feature can be used in a multi-processor system as follows:

A master processor intends to transmit a block of data to one of many slaves. It must first send out an address byte that identifies the target slave. An address byte is identified by setting the ninth bit (RSR<8>) to a '1' (instead of a '0' for a data byte). If the ADEN and RX9 bits are set in the slave's RCSTA register, enabling multiprocessor communication, all data bytes will be ignored. However, if the ninth received bit is equal to a '1', indicating that the received byte is an address, the slave will be interrupted and the contents of the RSR register will be transferred into the receive buffer. This allows the slave to be interrupted only by addresses, so that the slave can examine the received byte to see if it is being addressed. The addressed slave will then clear its ADEN bit and prepare to receive data bytes from the master.

When ADEN is enabled (= '1'), all data bytes are ignored. Following the Stop bit, the data will not be loaded into the receive buffer, and no interrupt will occur. If another byte is shifted into the RSR register, the previous data byte will be lost.

The ADEN bit will only take effect when the receiver is configured in 9-bit mode (RX9 = '1'). When ADEN is disabled (= '0'), all data bytes are received and the 9th bit can be used as the parity bit.

The receive block diagram is shown in Figure 12-8.

Reception is enabled by setting bit CREN (RCSTA<4>).

### 12.3.1.1 Setting up 9-bit mode with Address Detect

Follow these steps when setting up Asynchronous Reception with Address Detect Enabled:

- TRISB<1> bit needs to be set and TRISB<2> bit cleared in order to configure pins RB2/TX/CK and RB1/RX/DT as the Universal Synchronous Asynchronous Receiver Transmitter pins.
- Initialize the SPBRG register for the appropriate baud rate. If a high-speed baud rate is desired, set bit BRGH.
- 3. Enable asynchronous communication by setting or clearing bit SYNC and setting bit SPEN.
- If interrupts are desired, then set enable bit RCIE.
- 5. Set bit RX9 to enable 9-bit reception.
- 6. Set ADEN to enable address detect.
- Enable the reception by setting enable bit CREN or SREN.
- Flag bit RCIF will be set when reception is complete, and an interrupt will be generated if enable bit RCIE was set.
- Read the 8-bit received data by reading the RCREG register to determine if the device is being addressed.
- 10. If any error occurred, clear the error by clearing enable bit CREN if it was already set.
- 11. If the device has been addressed (RSR<8> = '1' with address match enabled), clear the ADEN and RCIF bits to allow data bytes and address bytes to be read into the receive buffer and interrupt the CPU.

TABLE 12-8: REGISTERS ASSOCIATED WITH ASYNCHRONOUS RECEPTION

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR	Value on all other Resets
0Ch	PIR1	EEIF	CMIF	RCIF	TXIF	_	CCP1IF	TMR2IF	TMR1IF	0000 -000	0000 -000
18h	RCSTA	SPEN	RX9	SREN	CREN	ADEN	FERR	OERR	RX9D	0000 000x	0000 000x
1Ah	RCREG	USART	Receive	data regi	ster					0000 0000	0000 0000
8Ch	PIE1	EEIE	CMIE	RCIE	TXIE	_	CCP1IE	TMR2IE	TMR1IE	0000 -000	0000 -000
98h	TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000 -010	0000 -010
99h	SPBRG		Baud Rate Generator Register							0000 0000	0000 0000

 $\textbf{Legend:} \quad \textbf{x} = \text{unknown, -= unimplemented locations read as '0'}. \label{eq:second} \textbf{Shaded cells are not used for Asynchronous Reception.}$ 

# 12.4 USART Synchronous Master Mode

In Synchronous Master mode, the data is transmitted in a half-duplex manner, (i.e., transmission and reception do not occur at the same time). When transmitting data, the reception is inhibited and vice versa. Synchronous mode is entered by setting bit SYNC (TXSTA<4>). In addition enable bit SPEN (RCSTA<7>) is set in order to configure the RB2/TX/CK and RB1/RX/DT I/O pins to CK (clock) and DT (data) lines respectively. The Master mode indicates that the processor transmits the master clock on the CK line. The Master mode is entered by setting bit CSRC (TXSTA<7>).

### 12.4.1 USART SYNCHRONOUS MASTER TRANSMISSION

The USART transmitter block diagram is shown in Figure 12-5. The heart of the transmitter is the transmit (serial) shift register (TSR). The shift register obtains its data from the read/write transmit buffer register TXREG. The TXREG register is loaded with data in software. The TSR register is not loaded until the last bit has been transmitted from the previous load. As soon as the last bit is transmitted, the TSR is loaded with new data from the TXREG (if available). Once the TXREG register transfers the data to the TSR register (occurs in one Tcycle), the TXREG is empty and interrupt bit, TXIF (PIR1<4>) is set. The interrupt can be enabled/disabled by setting/clearing enable bit TXIE (PIE1<4>). Flag bit TXIF will be set regardless of the state of enable bit TXIE and cannot be cleared in software. It will Reset only when new data is loaded into the TXREG register. While flag bit TXIF indicates the status of the TXREG register, another bit TRMT (TXSTA<1>) shows the status of the TSR register. TRMT is a read only bit which is set when the TSR is empty. No interrupt logic is tied to this bit, so the user has to poll this bit in order to determine if the TSR register is empty. The TSR is not mapped in data memory so it is not available to the user.

Transmission is enabled by setting enable bit TXEN (TXSTA<5>). The actual transmission will not occur until the TXREG register has been loaded with data. The first data bit will be shifted out on the next available rising edge of the clock on the CK line. Data out is stable around the falling edge of the synchronous clock (Figure 12-12). The transmission can also be started by first loading the TXREG register and then setting bit TXEN (Figure 12-13). This is advantageous when slow baud rates are selected, since the BRG is kept in Reset when bits TXEN, CREN, and SREN are clear. Setting enable bit TXEN will start the BRG, creating a shift clock immediately. Normally when transmission is first started, the TSR register is empty, so a transfer to the TXREG register will result in an immediate transfer to TSR resulting in an empty TXREG. Back-to-back transfers are possible.

Clearing enable bit TXEN, during a transmission, will cause the transmission to be aborted and will Reset the transmitter. The DT and CK pins will revert to hi-impedance. If either bit CREN or bit SREN is set, during a transmission, the transmission is aborted and the DT pin reverts to a hi-impedance state (for a reception). The CK pin will remain an output if bit CSRC is set (internal clock). The transmitter logic however is not Reset although it is disconnected from the pins. In order to Reset the transmitter, the user has to clear bit TXEN. If bit SREN is set (to interrupt an on-going transmission and receive a single word), then after the single word is received, bit SREN will be cleared and the serial port will revert back to transmitting since bit TXEN is still set. The DT line will immediately switch from hi-impedance Receive mode to transmit and start driving. To avoid this, bit TXEN should be cleared.

In order to select 9-bit transmission, the TX9 (TXSTA<6>) bit should be set and the ninth bit should be written to bit TX9D (TXSTA<0>). The ninth bit must be written before writing the 8-bit data to the TXREG register. This is because a data write to the TXREG can result in an immediate transfer of the data to the TSR register (if the TSR is empty). If the TSR was empty and the TXREG was written before writing the "new" TX9D, the "present" value of bit TX9D is loaded.

Follow these steps when setting up a Synchronous Master Transmission:

- TRISB<1> bit needs to be set and TRISB<2> bit cleared in order to configure pins RB2/TX/CK and RB1/RX/DT as the Universal Synchronous Asynchronous Receiver Transmitter pins.
- Initialize the SPBRG register for the appropriate baud rate (Section 12.1 "USART Baud Rate Generator (BRG)").
- 3. Enable the synchronous master serial port by setting bits SYNC, SPEN, and CSRC.
- If interrupts are desired, then set enable bit TXIE.
- 5. If 9-bit transmission is desired, then set bit TX9.
- 6. Enable the transmission by setting bit TXEN.
- If 9-bit transmission is selected, the ninth bit should be loaded in bit TX9D.
- 8. Start transmission by loading data to the TXREG register.

TABLE 12-9: REGISTERS ASSOCIATED WITH SYNCHRONOUS MASTER TRANSMISSION

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR	Value on all other Resets
0Ch	PIR1	EEIF	CMIF	RCIF	TXIF		CCP1IF	TMR2IF	TMR1IF	0000 -000	0000 -000
18h	RCSTA	SPEN	RX9	SREN	CREN	ADEN	FERR	OERR	RX9D	0000 000x	0000 000x
19h	TXREG	USART 1	ransmit	data reg	jister					0000 0000	0000 0000
8Ch	PIE1	EEIE	CMIE	RCIE	TXIE		CCP1IE	TMR2IE	TMR1IE	0000 -000	0000 -000
98h	TXSTA	CSRC	TX9	TXEN	SYNC		BRGH	TRMT	TX9D	0000 -010	0000 -010
99h	SPBRG	Baud Rate Generator Register							0000 0000	0000 0000	

**Legend:** x = unknown, - = unimplemented, read as '0'. Shaded cells are not used for Synchronous Master Transmission.

### FIGURE 12-12: SYNCHRONOUS TRANSMISSION





FIGURE 12-13: SYNCHRONOUS TRANSMISSION (THROUGH TXEN)



## 12.4.2 USART SYNCHRONOUS MASTER RECEPTION

Once Synchronous mode is selected, reception is enabled by setting either enable bit SREN (RCSTA<5>) or enable bit CREN (RCSTA<4>). Data is sampled on the RB1/RX/DT pin on the falling edge of the clock. If enable bit SREN is set, then only a single word is received. If enable bit CREN is set, the reception is continuous until CREN is cleared. If both bits are set then CREN takes precedence. After clocking the last bit, the received data in the Receive Shift Register (RSR) is transferred to the RCREG register (if it is empty). When the transfer is complete, interrupt flag bit RCIF (PIR1<5>) is set. The actual interrupt can be enabled/disabled by setting/clearing enable bit RCIE (PIE1<5>). Flag bit RCIF is a read only bit which is Reset by the hardware. In this case it is Reset when the RCREG register has been read and is empty. The RCREG is a double buffered register, (i.e., it is a two deep FIFO). It is possible for two bytes of data to be received and transferred to the RCREG FIFO and a third byte to begin shifting into the RSR register. On the clocking of the last bit of the third byte, if the RCREG register is still full then overrun error bit OERR (RCSTA<1>) is set. The word in the RSR will be lost. The RCREG register can be read twice to retrieve the two bytes in the FIFO. Bit OERR has to be cleared in software (by clearing bit CREN). If bit OERR is set, transfers from the RSR to the RCREG are inhibited, so it is essential to clear bit OERR if it is set. The 9th receive bit is buffered the same way as the receive data. Reading the RCREG register, will load bit RX9D

with a new value, therefore it is essential for the user to read the RCSTA register before reading RCREG in order not to lose the old RX9D information.


Follow these steps when setting up a Synchronous Master Reception:

- TRISB<1> bit needs to be set and TRISB<2> bit cleared in order to configure pins RB2/TX/CK and RB1/RX/DT as the Universal Synchronous Asynchronous Receiver Transmitter pins.
- Initialize the SPBRG register for the appropriate baud rate. (Section 12.1 "USART Baud Rate Generator (BRG)").
- 3. Enable the synchronous master serial port by setting bits SYNC, SPEN, and CSRC.
- 4. Ensure bits CREN and SREN are clear.
- If interrupts are desired, then set enable bit RCIE.
- 6. If 9-bit reception is desired, then set bit RX9.
- 7. If a single reception is required, set bit SREN. For continuous reception set bit CREN.
- Interrupt flag bit RCIF will be set when reception is complete and an interrupt will be generated if enable bit RCIE was set.
- Read the RCSTA register to get the ninth bit (if enabled) and determine if any error occurred during reception.
- Read the 8-bit received data by reading the RCREG register.
- 11. If any error occurred, clear the error by clearing bit CREN.

TABLE 12-10: REGISTERS ASSOCIATED WITH SYNCHRONOUS MASTER RECEPTION

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR	Value on all other Resets
0Ch	PIR1	EEIF	CMIF	RCIF	TXIF	_	CCP1IF	TMR2IF	TMR1IF	0000 -000	0000 -000
18h	RCSTA	SPEN	RX9	SREN	CREN	ADEN	FERR	OERR	RX9D	0000 000x	0000 000x
1Ah	RCREG	USART F	Receive	data reg	ister					0000 0000	0000 0000
8Ch	PIE1	EEPIE	CMIE	RCIE	TXIE	_	CCP1IE	TMR2IE	TMR1IE	-000 0000	-000 -000
98h	TXSTA	CSRC	TX9	TXEN	SYNC	l	BRGH	TRMT	TX9D	0000 -010	0000 -010
99h	SPBRG	Baud Rate Generator Register								0000 0000	0000 0000

**Legend:** x = unknown, - = unimplemented read as '0'. Shaded cells are not used for Synchronous Master Reception.



### 12.5 USART Synchronous Slave Mode

Synchronous Slave mode differs from the Master mode in the fact that the shift clock is supplied externally at the RB2/TX/CK pin (instead of being supplied internally in Master mode). This allows the device to transfer or receive data while in Sleep mode. Slave mode is entered by clearing bit CSRC (TXSTA<7>).

## 12.5.1 USART SYNCHRONOUS SLAVE TRANSMIT

The operation of the synchronous Master and Slave modes are identical except in the case of the Sleep mode.

If two words are written to the TXREG and then the SLEEP instruction is executed, the following will occur:

- The first word will immediately transfer to the TSR register and transmit.
- b) The second word will remain in TXREG register.
- c) Flag bit TXIF will not be set.
- d) When the first word has been shifted out of TSR, the TXREG register will transfer the second word to the TSR and flag bit TXIF will now be set.
- e) If enable bit TXIE is set, the interrupt will wake the chip from Sleep and if the global interrupt is enabled, the program will branch to the interrupt vector (0004h).

Follow these steps when setting up a Synchronous Slave Transmission:

- TRISB<1> bit needs to be set and TRISB<2> bit cleared in order to configure pins RB2/TX/CK and RB1/RX/DT as the Universal Synchronous Asynchronous Receiver Transmitter pins.
- Enable the synchronous slave serial port by setting bits SYNC and SPEN and clearing bit CSRC.
- 3. Clear bits CREN and SREN.
- If interrupts are desired, then set enable bit TXIE.
- 5. If 9-bit transmission is desired, then set bit TX9.
- Enable the transmission by setting enable bit TXFN.
- If 9-bit transmission is selected, the ninth bit should be loaded in bit TX9D.
- 8. Start transmission by loading data to the TXREG register.

## 12.5.2 USART SYNCHRONOUS SLAVE RECEPTION

The operation of the Synchronous Master and Mlave modes is identical except in the case of the Sleep mode. Also, bit SREN is a don't care in Slave mode.

If receive is enabled, by setting bit CREN, prior to the SLEEP instruction, then a word may be received during Sleep. On completely receiving the word, the RSR register will transfer the data to the RCREG register and if enable bit RCIE bit is set, the interrupt generated will wake the chip from Sleep. If the global interrupt is enabled, the program will branch to the interrupt vector (0004h).

Follow these steps when setting up a Synchronous Slave Reception:

 TRISB<1> bit needs to be set and TRISB<2> bit cleared in order to configure pins RB2/TX/CK and RB1/RX/DT as the Universal Synchronous Asynchronous Receiver Transmitter pins.

- Enable the synchronous master serial port by setting bits SYNC and SPEN and clearing bit CSRC.
- If interrupts are desired, then set enable bit RCIE.
- 4. If 9-bit reception is desired, then set bit RX9.
- 5. To enable reception, set enable bit CREN.
- 6. Flag bit RCIF will be set when reception is complete and an interrupt will be generated, if enable bit RCIE was set.
- Read the RCSTA register to get the ninth bit (if enabled) and determine if any error occurred during reception.
- 8. Read the 8-bit received data by reading the RCREG register.
- If any error occurred, clear the error by clearing bit CREN.

TABLE 12-11: REGISTERS ASSOCIATED WITH SYNCHRONOUS SLAVE TRANSMISSION

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR	Value on all other Resets
0Ch	PIR1	EEIF	CMIF	RCIF	TXIF	ĺ	CCP1IF	TMR2IF	TMR1IF	0000 -000	0000 -000
18h	RCSTA	SPEN	RX9	SREN	CREN	ADEN	FERR	OERR	RX9D	0000 000x	0000 000x
19h	TXREG	USART 7	Fransmit	data reg	gister					0000 0000	0000 0000
8Ch	PIE1	EEIE	CMIE	RCIE	TXIE	_	CCP1IE	TMR2IE	TMR1IE	0000 -000	0000 -000
98h	TXSTA	CSRC	TX9	TXEN	SYNC	1	BRGH	TRMT	TX9D	0000 -010	0000 -010
99h	SPBRG	SPBRG Baud Rate Generator Register								0000 0000	0000 0000

Legend: x = unknown, - = unimplemented read as '0'. Shaded cells are not used for Synchronous Slave Transmission.

TABLE 12-12: REGISTERS ASSOCIATED WITH SYNCHRONOUS SLAVE RECEPTION

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR	Value on all other Resets
0Ch	PIR1	EEIF	CMIF	RCIF	TXIF		CCP1IF	TMR2IF	TMR1IF	0000 -000	0000 -000
18h	RCSTA	SPEN	RX9	SREN	CREN	ADEN	FERR	OERR	RX9D	0000 000x	0000 000x
1Ah	RCREG	USART I	Receive	data reg	ister					0000 0000	0000 0000
8Ch	PIE1	EEIE	CMIE	RCIE	TXIE	1	CCP1IE	TMR2IE	TMR1IE	0000 -000	0000 -000
98h	TXSTA	CSRC	TX9	TXEN	SYNC	l	BRGH	TRMT	TX9D	0000 -010	0000 -010
99h	SPBRG	Baud Rate Generator Register								0000 0000	0000 0000

Legend: x = unknown, - = unimplemented read as '0'. Shaded cells are not used for Synchronous Slave Reception.

NOTES:

### 13.0 DATA EEPROM MEMORY

The EEPROM data memory is readable and writable during normal operation (full VDD range). This memory is not directly mapped in the register file space. Instead it is indirectly addressed through the Special Function Registers (SFRs). There are four SFRs used to read and write this memory. These registers are:

- EECON1
- EECON2 (Not a physically implemented register)
- EEDATA
- EEADR

EEDATA holds the 8-bit data for read/write, and EEADR holds the address of the EEPROM location being accessed. PIC16F627A/628A devices have 128 bytes of data EEPROM with an address range from 0h to 7Fh. PIC16F648A device has 256 bytes of data EEPROM with an address range from 0h to FFh.

The EEPROM data memory allows byte read and write. A byte write automatically erases the location and writes the new data (erase before write). The EEPROM data memory is rated for high erase/write cycles. The write time is controlled by an on-chip timer. The write-time will vary with voltage and temperature as well as from chip to chip. Please refer to AC specifications for exact limits.

When the device is code protected, the CPU can continue to read and write the data EEPROM memory. A device programmer can no longer access this memory.

Additional information on the data EEPROM is available in the *PICmicro*<sup>®</sup> *Mid-Range Reference Manual* (DS33023).

### REGISTER 13-1: EEDATA REGISTER (ADDRESS: 9Ah)

R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
EEDAT7	EEDAT6	EEDAT5	EEDAT4	EEDAT3	EEDAT2	EEDAT1	EEDAT0
bit 7					•		bit 0

bit 7-0 **EEDATn**: Byte value to write to or read from Data EEPROM memory location.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

### REGISTER 13-2: EEADR REGISTER (ADDRESS: 9Bh)

R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
EADR7	EADR6	EADR5	EADR4	EADR3	EADR2	EADR1	EADR0
bit 7							bit 0

bit 7 PIC16F627A/628A - Unimplemented Address: Must be set to '0'

PIC16F648A - EEADR: Set to '1' specifies top 128 locations (128-256) of EEPROM Read/Write Operation

bit 6-0 **EEADR**: Specifies one of 128 locations of EEPROM Read/Write Operation

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented I	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

#### **13.1 EEADR**

The PIC16F648A EEADR register addresses 256 bytes of data EEPROM. All eight bits in the register (EEADR<7:0>) are required.

The PIC16F627A/628A EEADR register addresses only the first 128 bytes of data EEPROM so only seven of the eight bits in the register (EEADR<6:0>) are required. The upper bit is address decoded. This means that this bit should always be '0' to ensure that the address is in the 128 byte memory space.

# 13.2 EECON1 AND EECON2 REGISTERS

EECON1 is the control register with four low order bits physically implemented. The upper-four bits are non-existent and read as '0's.

Control bits RD and WR initiate read and write, respectively. These bits cannot be cleared, only set, in software. They are cleared in hardware at completion of the read or write operation. The inability to clear the WR bit in software prevents the accidental, premature termination of a write operation.

The WREN bit, when set, will allow a write operation. On power-up, the WREN bit is clear. The WRERR bit is set when a write operation is interrupted by a MCLR Reset or a WDT Time out Reset during normal operation. In these situations, following Reset, the user can check the WRERR bit and rewrite the location. The data and address will be unchanged in the EEDATA and EEADR registers.

Interrupt flag bit EEIF in the PIR1 register is set when write is complete. This bit must be cleared in software.

EECON2 is not a physical register. Reading EECON2 will read all '0's. The EECON2 register is used exclusively in the Data EEPROM write sequence.

### REGISTER 13-3: EECON1 REGISTER (ADDRESS: 9Ch) DEVICES

U-0	U-0	U-0	U-0	R/W-x	R/W-0	R/S-0	R/S-0
_	_	_	_	WRERR	WREN	WR	RD
bit 7							bit 0

bit 7-4 **Unimplemented:** Read as '0'

bit 3 WRERR: EEPROM Error Flag bit

1 = A write operation is prematurely terminated (any MCLR Reset, any WDT Reset during normal operation or BOR Reset)

0 = The write operation completed

bit 2 WREN: EEPROM Write Enable bit

1 = Allows write cycles

0 = Inhibits write to the data EEPROM

bit 1 WR: Write Control bit

1 = initiates a write cycle. (The bit is cleared by hardware once write is complete. The WR bit can only be set (not cleared) in software.

0 = Write cycle to the data EEPROM is complete

bit 0 RD: Read Control bit

1 = Initiates an EEPROM read (read takes one cycle. RD is cleared in hardware. The RD bit can only be set (not cleared) in software).

0 = Does not initiate an EEPROM read

#### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

# 13.3 READING THE EEPROM DATA MEMORY

To read a data memory location, the user must write the address to the EEADR register and then set control bit RD (EECON1<0>). The data is available, in the very next cycle, in the EEDATA register; therefore it can be read in the next instruction. EEDATA will hold this value until another read or until it is written to by the user (during a write operation).

#### EXAMPLE 13-1: DATA EEPROM READ

BSF	STATUS, RP0	;Bank 1
MOVLW	CONFIG_ADDR	;
MOVWF	EEADR	;Address to read
BSF	EECON1, RD	;EE Read
MOVF	EEDATA, W	;W = EEDATA
BCF	STATUS, RP0	;Bank 0

# 13.4 WRITING TO THE EEPROM DATA MEMORY

To write an EEPROM data location, the user must first write the address to the EEADR register and the data to the EEDATA register. Then the user must follow a specific sequence to initiate the write for each byte.

#### **EXAMPLE 13-2: DATA EEPROM WRITE**

```
BSF
        STATUS, RPO
                        ;Bank 1
                        ;Enable write
BSF
        EECON1, WREN
        INTCON, GIE
                        ;Disable INTs.
BCF
MOVLW
        55h
MOVWF
        EECON2
                       ;Write 55h
MOVLW
        AAh
MOVWF
        EECON2
                        ;Write AAh
        EECON1.WR
                        ;Set WR bit
BSF
                        ;begin write
BSF INTCON, GIE
                        ;Enable INTs.
```

The write will not initiate if the above sequence is not exactly followed (write 55h to EECON2, write AAh to EECON2, then set WR bit) for each byte. We strongly recommend that interrupts be disabled during this code segment. A cycle count is executed during the required sequence. Any number what is not equal to the required cycles to execute the required sequence will cause the data not to be written into the EEPROM.

Additionally, the WREN bit in EECON1 must be set to enable write. This mechanism prevents accidental writes to data EEPROM due to errant (unexpected) code execution (i.e., lost programs). The user should keep the WREN bit clear at all times, except when updating EEPROM. The WREN bit is not cleared by hardware.

After a write sequence has been initiated, clearing the WREN bit will not affect this write cycle. The WR bit will be inhibited from being set unless the WREN bit is set.

At the completion of the write cycle, the WR bit is cleared in hardware and the EE Write Complete Interrupt Flag bit (EEIF) is set. The user can either enable this interrupt or poll this bit. The EEIF bit in the PIR1 registers must be cleared by software.

#### 13.5 WRITE VERIFY

Depending on the application, good programming practice may dictate that the value written to the Data EEPROM should be verified (Example 13-3) to the desired value to be written. This should be used in applications where an EEPROM bit will be stressed near the specification limit.

#### **EXAMPLE 13-3: WRITE VERIFY**

```
STATUS, RP0; Bank 1
 MOVF
       EEDATA, W
 BSF
       EECON1, RD ; Read the
                   ; value written
; Is the value written (in W reg) and
;read (in EEDATA) the same?
 SUBWF EEDATA, W
                  ;Is difference 0?
 BTFSS STATUS, Z
 GOTO WRITE_ERR
                  ;NO, Write error
 :
                   ;YES, Good write
 :
                   ;Continue program
```

# 13.6 PROTECTION AGAINST SPURIOUS WRITE

There are conditions when the device may not want to write to the data EEPROM memory. To protect against spurious EEPROM writes, various mechanisms have been built in. On power-up, WREN is cleared. Also when enabled, the Power-up Timer (72 ms duration) prevents EEPROM write.

The write initiate sequence, and the WREN bit together help prevent an accidental write during brown-out, power glitch, or software malfunction.

### 13.7 Using the Data EEPROM

The data EEPROM is a high endurance, byte addressable array that has been optimized for the storage of frequently changing information (e.g., program variables or other data that are updated often). Frequently changing values will typically be updated more often than specification D124. If this is not the case, an array refresh must be performed.

For this reason, variables that change infrequently (such as constants, IDs, calibration, etc.) should be stored in Flash program memory.

A simple data EEPROM refresh routine is shown in Example 13-4.

**Note:** If data EEPROM is only used to store constants and/or data that changes rarely, an array refresh is likely not required. See specification D124.

#### **EXAMPLE 13-4: DATA EEPROM REFRESH ROUTINE**

BANKSEL	0X80	;select Bank1				
CLRF	EEADR	;start at address 0				
BCF	INTCON, GIE	disable interrupts				
BSF	EECON1, WREN	;enable EE writes				
Loop						
BSF	EECON1, RD	retrieve data into EEDATA;				
MOVLW	0x55	;first step of				
MOVWF	EECON2	; required sequence				
MOVLW	0xAA	;second step of				
MOVWF	EECON2	; required sequence				
BSF	EECON1, WR	start write sequence				
BTFSC	EECON1, WR	;wait for write complete				
GOTO	\$ - 1					
#IFDEF16F64	18A	;256 bytes in 16F648A				
INCFSZ	EEADR, f	;test for end of memory				
#ELSE		;128 bytes in 16F627A/628A				
INCF	EEADR, f	next address;				
BTFSS	EEADR, 7	;test for end of memory				
#ENDIF		;end of conditional assembly				
GOTO	Loop	repeat for all locations				
BCF	EECON1, WREN	;disable EE writes				
BSF	INTCON, GIE	<pre>;enable interrupts (optional)</pre>				

# 13.8 DATA EEPROM OPERATION DURING CODE PROTECT

When the device is code protected, the CPU is able to read and write data to the Data EEPROM.

TABLE 13-1: REGISTERS/BITS ASSOCIATED WITH DATA EEPROM

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on Power-on Reset	Value on all other Resets
9Ah	EEDATA	EEPROM	EEPROM data register								uuuu uuuu
9Bh	EEADR	EEPROM	address	register						xxxx xxxx	uuuu uuuu
9Ch	EECON1	_	WRERR WREN WR RD							x000	q000
9Dh	EECON2 <sup>(1)</sup>	EEPROM	EEPROM control register 2								

**Legend:** x = unknown, u = unchanged, - = unimplemented read as '0', q = value depends upon condition.

Shaded cells are not used by data EEPROM.

Note 1: EECON2 is not a physical register.

# 14.0 SPECIAL FEATURES OF THE CPU

Special circuits to deal with the needs of real-time applications are what sets a microcontroller apart from other processors. The PIC16F627A/628A/648A family has a host of such features intended to maximize system reliability, minimize cost through elimination of external components, provide power saving Operating modes and offer code protection.

#### These are:

- 1. OSC selection
- 2. Reset
- 3. Power-on Reset (POR)
- 4. Power-up Timer (PWRT)
- 5. Oscillator Start-Up Timer (OST)
- 6. Brown-out Reset (BOR)
- 7. Interrupts
- 8. Watchdog Timer (WDT)
- 9. Sleep
- 10. Code protection
- 11. ID Locations
- 12. In-Circuit Serial Programming™ (ICSP™)

The PIC16F627A/628A/648A has a Watchdog Timer which is controlled by configuration bits. It runs off its own RC oscillator for added reliability. There are two timers that offer necessary delays on power-up. One is the Oscillator Start-up Timer (OST), intended to keep the chip in Reset until the crystal oscillator is stable. The other is the Power-up Timer (PWRT), which provides a fixed delay of 72 ms (nominal) on power-up only, designed to keep the part in Reset while the power supply stabilizes. There is also circuitry to Reset the device if a Brown-out occurs. With these three functions on-chip, most applications need no external Reset circuitry.

The Sleep mode is designed to offer a very low current Power-down mode. The user can wake-up from Sleep through external Reset, Watchdog Timer wake-up or through an interrupt. Several oscillator options are also made available to allow the part to fit the application. The RC oscillator option saves system cost while the LP crystal option saves power. A set of configuration bits are used to select various options.

### 14.1 Configuration Bits

The configuration bits can be programmed (read as '0') or left unprogrammed (read as '1') to select various device configurations. These bits are mapped in program memory location 2007h.

The user will note that address 2007h is beyond the user program memory space. In fact, it belongs to the special configuration memory space (2000h – 3FFFh), which can be accessed only during programming. See Programming Specification (DS41196) for additional information.

### **REGISTER 14-1: CONFIGURATION WORD**

CP	_	_	_	_	CPD	LVP	BOREN	MCLRE	FOSC2	PWRTE	WDTE	F0SC1	F0SC0
bit 13													bit 0
bit 13:			am Memor	y Code Pro	tection bit <sup>(</sup>	2)							
	(PIC1	<u> 6F648A)</u>  1 = Code i	orotection o	off									
	(510)	0 = 0000h		code protec	ted								
	(PIC1	(PIC16F628A)  1 = Code protection off											
	(510)	0 = 0000h to 07FFh code protected											
	(PIC	(PIC16F627A)  1 = Code protection off											
				ode protec	ted								
bit 12-9:	Unim	Unimplemented: Read as '0'											
bit 8:	CPD:	Data Code	e Protection	n bit <sup>(3)</sup>									
			y code pro										
	0 = L	ata memor	y code pro	tected									
bit 7:	I VD:	Low Voltac	e Program	ming Enabl	۵								
Dit 7.						programm	ing enable	b					
	0 = R	B4/PGM is	digital I/O,	HV on MC	LR must b	e used for p	orogrammir	ng					
1 '' 0	200	<b>-</b> N 5			1)								
bit 6:		OR Reset		Enable bit <sup>(</sup>	-,								
	0 = B	OR Reset	disabled										
			<del></del>										
bit 5:			CLR pin ful pin function	nction selec	ct								
					nput, MCLF	internally	tied to VDD						
bit 3:			•	Enable bit	(1)								
		WRT disab WRT enab											
bit 2:			dog Timer I	Enable bit									
		/DT enable /DT disable											
	0 – •	ID T Glodbit	Ju										
bit 4, 1-0:	FOS	C2:FOSC0	Oscillator	Selection b	its <sup>(4)</sup>								
										on RA7/OS 7/OSC1/CL			
										7/OSC1/CL			
							OUT pin, I/O on RA7/OS			C1/CLKIN			
							ON KA7/OS OSC2/CLK(			CLKIN			
							UT and RA						
	000 =	= LP OSCIII	ator. Low p	owei ciysta	II OII KAO/C	JSC2/CLN	DUT and R	A7/03C1/C	LKIN				
Note 1:										it did in the			
2:										F627/628. <sup>-</sup> g Specificat			
3:	The ent	ire data EE	PROM nee							on off. See			
4:		<u>6 for</u> detail ICLR is as		ITOSC mod	de, the inte	rnal clock	scillator is	disabled.					
		,			. ,								
Legend:													j
R = Reada	ble bit			W = Wr	itable bit		U = U	nimplemen	ted bit. rea	d as '0'			
-n = Value				'1' = bit				it is cleared			bit is unkn	own	
	-												

### 14.2 Oscillator Configurations

#### 14.2.1 OSCILLATOR TYPES


The PIC16F627A/628A/648A can be operated in eight different oscillator options. The user can program three configuration bits (FOSC2 through FOSC0) to select one of these eight modes:

- LP Low Power Crystal
- XT Crystal/Resonator
- HS High Speed Crystal/Resonator
- RC External Resistor/Capacitor (2 modes)
- INTOSC Internal Precision Oscillator (2 modes)
- EC External Clock In

## 14.2.2 CRYSTAL OSCILLATOR / CERAMIC RESONATORS

In XT, LP or HS modes a crystal or ceramic resonator is connected to the OSC1 and OSC2 pins to establish oscillation (Figure 14-1). The PIC16F627A/628A/648A oscillator design requires the use of a parallel cut crystal. Use of a series cut crystal may give a frequency out of the crystal manufacturers specifications. When in XT, LP or HS modes, the device can have an external clock source to drive the OSC1 pin (Figure 14-4).

FIGURE 14-1: CRYSTAL OPERATION
(OR CERAMIC
RESONATOR) (HS, XT OR
LP OSC
CONFIGURATION)



Note 1: A series resistor may be required for AT strip cut crystals.

2: See Table 14-1 and Table 14-2 for recommended values of C1 and C2.

TABLE 14-1: CAPACITOR SELECTION FOR CERAMIC RESONATORS

Mode	Freq	OSC1(C1)	OSC2(C2)
XT	455 kHz	22 - 100 pF	22 - 100 pF
	2.0 MHz	15 - 68 pF	15 - 68 pF
	4.0 MHz	15 - 68 pF	15 - 68 pF
HS	8.0 MHz	10 - 68 pF	10 - 68 pF
	16.0 MHz	10 - 22 pF	10 - 22 pF

Note:

Higher capacitance increases the stability of the oscillator but also increases the start-up time. These values are for design guidance only. Since each resonator has its own characteristics, the user should consult the resonator manufacturer for appropriate values of external components.

TABLE 14-2: CAPACITOR SELECTION FOR CRYSTAL OSCILLATOR

Mode	Freq	OSC1(C1)	OSC2(C2)
LP	32 kHz	15 - 30 pF	15 - 30 pF
	200 kHz	0 - 15 pF	0 - 15 pF
XT	100 kHz	68 - 150 pF	150 - 200 pF
	2 MHz	15 - 30 pF	15 - 30 pF
	4 MHz	15 - 30 pF	15 - 30 pF
HS	8 MHz	15 - 30 pF	15 - 30 pF
	10 MHz	15 - 30 pF	15 - 30 pF
	20 MHz	15 - 30 pF	15 - 30 pF

Note:

Higher capacitance increases the stability of the oscillator but also increases the start-up time. These values are for design guidance only. A series resistor (RS) may be required in HS mode as well as XT mode to avoid overdriving crystals with low drive level specification. Since each crystal has its own characteristics, the user should consult the crystal manufacturer for appropriate values of external components.

## 14.2.3 EXTERNAL CRYSTAL OSCILLATOR CIRCUIT

Either a prepackaged oscillator can be used or a simple oscillator circuit with TTL gates can be built. Prepackaged oscillators provide a wide operating range and better stability. A well-designed crystal oscillator will provide good performance with TTL gates. Two types of crystal oscillator circuits can be used; one with series resonance, or one with parallel resonance.

Figure 14-2 shows implementation of a parallel resonant oscillator circuit. The circuit is designed to use the fundamental frequency of the crystal. The 74AS04 inverter performs the  $180^\circ$  phase shift that a parallel oscillator requires. The  $4.7~k\Omega$  resistor provides the negative feedback for stability. The  $10~k\Omega$  potentiometers bias the 74AS04 in the linear region. This could be used for external oscillator designs.

# FIGURE 14-2: EXTERNAL PARALLEL RESONANT CRYSTAL OSCILLATOR CIRCUIT





Figure 14-3 shows a series resonant oscillator circuit. This circuit is also designed to use the fundamental frequency of the crystal. The inverter performs a 180° phase shift in a series resonant oscillator circuit. The 330 k $\Omega$  resistors provide the negative feedback to bias the inverters in their linear region.

FIGURE 14-3: EXTERNAL SERIES
RESONANT CRYSTAL
OSCILLATOR CIRCUIT




# 14.2.4 PRECISION INTERNAL 4 MHz OSCILLATOR

The internal precision oscillator provides a fixed 4 MHz (nominal) system clock at VDD = 5 V and 25°C. See **Section 17.0 "Electrical Specifications"**, for information on variation over voltage and temperature.

### 14.2.5 EXTERNAL CLOCK IN

For applications where a clock is already available elsewhere, users may directly drive the PIC16F627A/628A/648A provided that this external clock source meets the AC/DC timing requirements listed in **Section 17.6 "Timing Diagrams and Specifications"**. Figure 14-4 below shows how an external clock circuit should be configured.

FIGURE 14-4: EXTERNAL CLOCK INPUT OPERATION (EC, HS, XT OR LP OSC CONFIGURATION)




### 14.2.6 RC OSCILLATOR

For applications where precise timing is not a requirement, the RC oscillator option is available. The operation and functionality of the RC oscillator is dependent upon a number of variables. The RC oscillator frequency is a function of:

- · Supply voltage
- Resistor (REXT) and capacitor (CEXT) values
- · Operating temperature.

The oscillator frequency will vary from unit to unit due to normal process parameter variation. The difference in lead frame capacitance between package types will also affect the oscillation frequency, especially for low CEXT values. The user also needs to account for the tolerance of the external R and C components. Figure 14-5 shows how the R/C combination is connected.

FIGURE 14-5: RC OSCILLATOR MODE



The RC Oscillator mode has two options that control the unused OSC2 pin. The first allows it to be used as a general purpose I/O port. The other configures the pin as an output providing the Fosc signal (internal clock divided by 4) for test or external synchronization purposes.

### 14.2.7 CLKOUT

The PIC16F627A/628A/648A can be configured to provide a clock out signal by programming the configuration word. The oscillator frequency, divided by 4 can be used for test purposes or to synchronize other logic.

# 14.2.8 SPECIAL FEATURE: DUAL SPEED OSCILLATOR MODES

A software programmable dual speed Oscillator mode is provided when the PIC16F627A/628A/648A is configured in the INTOSC Oscillator mode. This feature allows users to dynamically toggle the oscillator speed between 4 MHz and 37 kHz nominal in the INTOSC mode. Applications that require low current power savings, but cannot tolerate putting the part into Sleep, may use this mode.

There is a time delay associated with the transition between Fast and Slow oscillator speeds. This Oscillator Speed Transition delay consists of two existing clock pulses and eight new speed clock pulses. During this Clock Speed Transition Delay the System Clock is halted causing the processor to be frozen in time. During this delay the Program Counter and the Clock Out stop.

The OSCF bit in the PCON register is used to control Dual Speed mode. See **Section 4.2.2.6 "PCON Register"**, Register 4-6.

#### 14.3 Reset

The PIC16F627A/628A/648A differentiates between various kinds of Reset:


- a) Power-on Reset (POR)
- b) MCLR Reset during normal operation
- c) MCLR Reset during Sleep
- d) WDT Reset (normal operation)
- e) WDT wake-up (Sleep)
- f) Brown-out Reset (BOR)

Some registers are not affected in any Reset condition; their status is unknown on POR and unchanged in any other Reset. Most other registers are reset to a "Reset state" on Power-on Reset, Brown-out Reset, MCLR Reset, WDT Reset and MCLR Reset during Sleep. They are not affected by a WDT wake-up, since this is viewed as the resumption of normal operation. TO and PD bits are set or cleared differently in different Reset situations as indicated in Table 14-4. These bits are used in software to determine the nature of the Reset. See Table 14-7 for a full description of Reset states of all registers.

A simplified block diagram of the on-chip Reset circuit is shown in Figure 14-6.

The MCLR Reset path has a noise filter to detect and ignore small pulses. See Table 17-7 for pulse width specification.

FIGURE 14-6: SIMPLIFIED BLOCK DIAGRAM OF ON-CHIP RESET CIRCUIT



### 14.4 Power-on Reset (POR), Power-up Timer (PWRT), Oscillator Start-up Timer (OST) and Brown-out Reset (BOR)

### 14.4.1 POWER-ON RESET (POR)

The on-chip POR circuit holds the chip in Reset until VDD has reached a high enough level for proper operation. To take advantage of the POR, just tie the MCLR pin through a resistor to VDD. This will eliminate external RC components usually needed to create Power-on Reset. A maximum rise time for VDD is required. See Electrical Specifications for details.

The POR circuit does not produce an internal Reset when VDD declines.

When the device starts normal operation (exits the Reset condition), device operating parameters (voltage, frequency, temperature, etc.) must be met to ensure operation. If these conditions are not met, the device must be held in Reset until the operating conditions are met.

For additional information, refer to Application Note AN607, "Power-up Trouble Shooting".

### 14.4.2 POWER-UP TIMER (PWRT)

The PWRT provides a fixed 72 ms (nominal) time out on power-up (POR) or if enabled from a Brown-out Reset. The PWRT operates on an internal RC oscillator. The chip is kept in Reset as long as PWRT is active. The PWRT delay allows the VDD to rise to an acceptable level. A configuration bit, PWRTE can disable (if set) or enable (if cleared or programmed) the PWRT. It is recommended that the PWRT be enabled when Brown-out Reset is enabled.

The Power-Up Time delay will vary from chip to chip and due to VDD, temperature and process variation. See DC parameters Table 17-7 for details.

# 14.4.3 OSCILLATOR START-UP TIMER (OST)

The OST provides a 1024 oscillator cycle (from OSC1 input) delay after the PWRT delay is over. Program execution will not start until the OST time out is complete. This ensures that the crystal oscillator or resonator has started and stabilized.

The OST time out is invoked only for XT, LP and HS modes and only on Power-on Reset or wake-up from Sleep. See Table 17-7.


### 14.4.4 BROWN-OUT RESET (BOR)

The PIC16F627A/628A/648A have on-chip BOR circuitry. A configuration bit, BOREN, can disable (if clear/programmed) or enable (if set) the BOR Reset circuitry. If VDD falls below VBOR for longer than TBOR, the brown-out situation will Reset the chip. A Reset is not guaranteed to occur if VDD falls below VBOR for shorter than TBOR. VBOR and TBOR are defined in Table 17-2 and Table 17-7, respectively.

On any Reset (Power-on, Brown-out, Watchdog, etc.), the chip will remain in Reset until VDD rises above BVDD (see Figure 14-7). The Power-up Timer will now be invoked, if enabled, and will keep the chip in Reset an additional 72 ms.

If VDD drops below VBOR while the Power-up Timer is running, the chip will go back into a Brown-out Reset and the Power-up Timer will be re-initialized. Once VDD rises above VBOR, the Power-Up Timer will execute a 72 ms Reset. Figure 14-7 shows typical Brown-out situations.





#### 14.4.5 TIME OUT SEQUENCE

On power-up the time out sequence is as follows: First PWRT time out is invoked after POR has expired. Then OST is activated. The total time out will vary based on oscillator configuration and  $\overline{\text{PWRTE}}$  bit Status. For example, in RC mode with  $\overline{\text{PWRTE}}$  bit set (PWRT disabled), there will be no time out at all. Figure 14-8, Figure 14-9 and Figure 14-10 depict time out sequences.

Since the time outs occur from the POR pulse, if MCLR is kept low long enough, the time outs will expire. Then bringing MCLR high will begin execution immediately (see Figure 14-9). This is useful for testing purposes or to synchronize more than one PIC16F627A/628A/648A device operating in parallel.

Table 14-6 shows the Reset conditions for some special registers, while Table 14-7 shows the Reset conditions for all the registers.

## 14.4.6 POWER CONTROL (PCON) STATUS REGISTER

The power control/Status Register, PCON (address 8Eh) has two bits.

Bit 0 is  $\overline{BOR}$  (Brown-out Reset).  $\overline{BOR}$  is unknown on Power-on-Reset. It must then be set by the user and checked on subsequent Resets to see if  $\overline{BOR} = 0$  indicating that a brown-out has occurred. The  $\overline{BOR}$  Status bit is a don't care and is not necessarily predictable if the brown-out circuit is disabled (by setting BOREN bit = 0 in the Configuration word).

Bit 1 is POR (Power-on Reset). It is a '0' on Power-on Reset and unaffected otherwise. The user must write a '1' to this bit following a Power-on Reset. On a subsequent Reset if POR is '0', it will indicate that a Power-on Reset must have occurred (VDD may have gone too low).

TABLE 14-3: TIME OUT IN VARIOUS SITUATIONS

Oscillator Configuration	Powe	er-up	Brown-o	Wake-up	
Oscillator Configuration	PWRTEN = 0	PWRTEN = 1	PWRTEN = 0	PWRTEN = 1	from Sleep
XT, HS, LP	72 ms + 1024•Tosc	1024•Tosc	72 ms + 1024•Tosc	1024•Tosc	1024•Tosc
RC, EC	72 ms	_	72 ms	_	_
INTOSC	72 ms	_	72 ms	_	6 μs

TABLE 14-4: STATUS/PCON BITS AND THEIR SIGNIFICANCE

POR	BOR	TO	PD	Condition
0	Х	1	1	Power-on Reset
0	Х	0	Х	Illegal, TO is set on POR
0	Х	Х	0	Illegal, PD is set on POR
1	0	X	X	Brown-out Reset
1	1	0	u	WDT Reset
1	1	0	0	WDT Wake-up
1	1	u	u	MCLR Reset during normal operation
1	1	1	0	MCLR Reset during Sleep

**Legend:** u = unchanged, x = unknown

### TABLE 14-5: SUMMARY OF REGISTERS ASSOCIATED WITH BROWN-OUT RESET

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR Reset	Value on all other Resets <sup>(1)</sup>
03h, 83h, 103h, 183h	STATUS	IRP	RP1	RPO	TO	PD	Z	DC	С	0001 1xxx	000q quuu
8Eh	PCON	-	_	_	_	OSCF	_	POR	BOR	1-0x	u-uq

**Legend:** x = unknown, u = unchanged, - = unimplemented read as '0', q = value depends upon condition. Shaded cells are not used by Brown-out Reset.

Note 1: Other (non Power-up) Resets include MCLR Reset, Brown-out Reset and Watchdog Timer Reset during normal operation.

### TABLE 14-6: INITIALIZATION CONDITION FOR SPECIAL REGISTERS

Condition	Program Counter	Status Register	PCON Register
Power-on Reset	000h	0001 1xxx	1-0x
MCLR Reset during normal operation	000h	000u uuuu	1-uu
MCLR Reset during Sleep	000h	0001 0uuu	1-uu
WDT Reset	000h	0000 uuuu	1-uu
WDT Wake-up	PC + 1	uuu0 0uuu	u-uu
Brown-out Reset	000h	000x xuuu	1-u0
Interrupt Wake-up from Sleep	PC + 1 <sup>(1)</sup>	uuu1 0uuu	u-uu

**Legend:** u = unchanged, x = unknown, - = unimplemented bit, reads as '0'.

Note 1: When the wake-up is due to an interrupt and global enable bit, GIE is set, the PC is loaded with the interrupt vector (0004h) after execution of PC+1.

TABLE 14-7: INITIALIZATION CONDITION FOR REGISTERS

Register	Address	Power-on Reset	MCLR Reset during normal operation     MCLR Reset during Sleep     WDT Reset     Brown-out Reset (1)	<ul> <li>Wake-up from Sleep<sup>(7)</sup>         through interrupt</li> <li>Wake-up from Sleep<sup>(7)</sup>         through WDT time out</li> </ul>
W	_	xxxx xxxx	uuuu uuuu	uuuu uuuu
INDF	00h	_	_	_
TMR0	01h, 101h	xxxx xxxx	uuuu uuuu	uuuu uuuu
PCL	02h, 82h, 102h, 182h	0000 0000	0000 0000	PC + 1 <sup>(3)</sup>
STATUS	03h, 83h, 103h, 183h	0001 1xxx	000q quuu <sup>(4)</sup>	uuuq Ouuu <sup>(4)</sup>
FSR	04h, 84h, 104h, 184h	xxxx xxxx	uuuu uuuu	uuuu uuuu
PORTA	05h	xxxx 0000	xxxx 0000	uuuu uuuu
PORTB	06h, 106h	xxxx xxxx	uuuu uuuu	uuuu uuuu
PCLATH	0Ah, 8Ah, 10Ah, 18Ah	0 0000	0 0000	u uuuu
INTCON	0Bh, 8Bh, 10Bh,18Bh	0000 000x	0000 000u	uuuu uqqq <sup>(2)</sup>
PIR1	0Ch	0000 -000	0000 -000	qqqq -qqq <sup>(2)</sup>
TMR1L	0Eh	xxxx xxxx	uuuu uuuu	uuuu uuuu
TMR1H	0Fh	xxxx xxxx	uuuu uuuu	uuuu uuuu
T1CON	10h	00 0000	uu uuuu <sup>(6)</sup>	uu uuuu
TMR2	11h	0000 0000	0000 0000	uuuu uuuu
T2CON	12h	-000 0000	-000 0000	-uuu uuuu
CCPR1L	15h	xxxx xxxx	uuuu uuuu	uuuu uuuu
CCPR1H	16h	xxxx xxxx	uuuu uuuu	uuuu uuuu
CCP1CON	17h	00 0000	00 0000	uu uuuu
RCSTA	18h	0000 000x	0000 000x	uuuu uuuu
TXREG	19h	0000 0000	0000 0000	uuuu uuuu
RCREG	1Ah	0000 0000	0000 0000	uuuu uuuu
CMCON	1Fh	0000 0000	0000 0000	uu uuuu
OPTION	81h,181h	1111 1111	1111 1111	uuuu uuuu
TRISA	85h	1111 1111	1111 1111	uuuu uuuu
TRISB	86h, 186h	1111 1111	1111 1111	uuuu uuuu
PIE1	8Ch	0000 -000	0000 -000	uuuu -uuu
PCON	8Eh	1-0x	1-uq <sup>(1,5)</sup>	u-uu
PR2	92h	1111 1111	1111 1111	uuuu uuuu
TXSTA	98h	0000 -010	0000 -010	uuuu -uuu
SPBRG	99h	0000 0000	0000 0000	uuuu uuuu
EEDATA	9Ah	xxxx xxxx	uuuu uuuu	uuuu uuuu
EEADR	9Bh	xxxx xxxx	uuuu uuuu	uuuu uuuu
EECON1	9Ch	x000	q000p	uuuu
EECON2	9Dh	_	_	_
VRCON	9Fh	000- 0000	000- 0000	uuu- uuuu

**Legend:** u = unchanged, x = unknown, - = unimplemented bit, reads as '0', <math>q = value depends on condition.

Note 1: If VDD goes too low, Power-on Reset will be activated and registers will be affected differently.

<sup>2:</sup> One or more bits in INTCON and PIR1 will be affected (to cause wake-up).

<sup>3:</sup> When the wake-up is due to an interrupt and the GIE bit is set, the PC is loaded with the interrupt vector (0004h).

<sup>4:</sup> See Table 14-6 for Reset value for specific condition.

**<sup>5:</sup>** If Reset was due to brown-out, then bit 0 = 0. All other Resets will cause bit 0 = u.

<sup>6:</sup> Reset to '--00 0000' on a Brown-out Reset (BOR).

<sup>7:</sup> Peripherals generating interrupts for wake-up from Sleep will change the resulting bits in the associated registers.

FIGURE 14-8: TIME OUT SEQUENCE ON POWER-UP (MCLR NOT TIED TO VDD): CASE




FIGURE 14-9: TIME OUT SEQUENCE ON POWER-UP (MCLR NOT TIED TO VDD): CASE 2






FIGURE 14-10: TIME OUT SEQUENCE ON POWER-UP (MCLR TIED TO VDD)




# FIGURE 14-11: EXTERNAL POWER-ON RESET CIRCUIT (FOR SLOW VDD POWER-UP)




- Note 1: External Power-on Reset circuit is required only if VDD power-up slope is too slow. The diode D helps discharge the capacitor quickly when VDD powers down.
  - 2:  $R < 40 \text{ k}\Omega$  is recommended to make sure that voltage drop across R does not violate the device's electrical specification.
  - 3: R1 =  $100\Omega$  to  $1 \text{ k}\Omega$  will limit any current flowing into  $\overline{\text{MCLR}}$  from external capacitor C in the event of  $\overline{\text{MCLR}}$ /VPP pin breakdown due to Electrostatic Discharge (ESD) or Electrical Overstress (EOS).

# FIGURE 14-12: EXTERNAL BROWN-OUT PROTECTION CIRCUIT 1



- Note 1: This circuit will activate Reset when VDD goes below (Vz + 0.7V) where Vz = Zener voltage.
  - 2: Internal Brown-out Reset circuitry should be disabled when using this circuit.

# FIGURE 14-13: EXTERNAL BROWN-OUT PROTECTION CIRCUIT 2



Note 1: This Brown-out Circuit is less expensive, albeit less accurate. Transistor Q1 turns off when VDD is below a certain level such that:

$$VDD \times \frac{R1}{R1 + R2} = 0.7 \text{ V}$$

- 2: Internal Brown-out Reset should be disabled when using this circuit.
- **3:** Resistors should be adjusted for the characteristics of the transistor.

### 14.5 Interrupts

The PIC16F627A/628A/648A has 10 sources of interrupt:

- External Interrupt RB0/INT
- TMR0 Overflow Interrupt
- PORTB Change Interrupts (pins RB7:RB4)
- Comparator Interrupt
- USART Interrupt TX
- USART Interrupt RX
- CCP Interrupt
- TMR1 Overflow Interrupt
- TMR2 Match Interrupt
- Data EEPROM Interrupt

The interrupt control register (INTCON) records individual interrupt requests in flag bits. It also has individual and global interrupt enable bits.

A global interrupt enable bit, GIE (INTCON<7>) enables (if set) all un-masked interrupts or disables (if cleared) all interrupts. Individual interrupts can be disabled through their corresponding enable bits in INTCON register. GIE is cleared on Reset.

The "return from interrupt" instruction, RETFIE, exits interrupt routine as well as sets the GIE bit, which reenable RB0/INT interrupts.

The INT pin interrupt, the RB port change interrupt and the TMR0 overflow interrupt flags are contained in the INTCON register.


The peripheral interrupt flag is contained in the special register PIR1. The corresponding interrupt enable bit is contained in special registers PIE1.

When an interrupt is responded to, the GIE is cleared to disable any further interrupt, the return address is pushed into the stack and the PC is loaded with 0004h. Once in the interrupt service routine the source(s) of the interrupt can be determined by polling the interrupt flag bits. The interrupt flag bit(s) must be cleared in software before re-enabling interrupts to avoid RB0/INT recursive interrupts.

For external interrupt events, such as the INT pin or PORTB change interrupt, the interrupt latency will be three or four instruction cycles. The exact latency depends when the interrupt event occurs (Figure 14-15). The latency is the same for one or two cycle instructions. Once in the interrupt service routine the source(s) of the interrupt can be determined by polling the interrupt flag bits. The interrupt flag bit(s) must be cleared in software before re-enabling interrupts to avoid multiple interrupt requests. Individual interrupt flag bits are set regardless of the status of their corresponding mask bit or the GIE bit.

- Note 1: Individual interrupt flag bits are set regardless of the status of their corresponding mask bit or the GIE bit.
  - 2: When an instruction that clears the GIE bit is executed, any interrupts that were pending for execution in the next cycle are ignored. The CPU will execute a NOP in the cycle immediately following the instruction which clears the GIE bit. The interrupts which were ignored are still pending to be serviced when the GIE bit is set again.

FIGURE 14-14: INTERRUPT LOGIC



#### 14.5.1 RB0/INT INTERRUPT

External interrupt on RB0/INT pin is edge triggered: either rising if INTEDG bit (OPTION<6>) is set, or falling, if INTEDG bit is clear. When a valid edge appears on the RB0/INT pin, the INTF bit (INTCON<1>) is set. This interrupt can be disabled by clearing the INTE control bit (INTCON<4>). The INTF bit must be cleared in software in the interrupt service routine before re-enabling this interrupt. The RB0/INT interrupt can wake-up the processor from Sleep, if the INTE bit was set prior to going into Sleep. The status of the GIE bit decides whether or not the processor branches to the interrupt vector following wake-up. See Section 14.8 "Power-Down Mode (Sleep)" for details on Sleep, and Figure 14-17 for timing of wake-up from Sleep through RB0/INT interrupt.

### 14.5.2 TMR0 INTERRUPT

An overflow (FFh  $\rightarrow$  00h) in the TMR0 register will set the T0IF (INTCON<2>) bit. The interrupt can be enabled/disabled by setting/clearing T0IE (INTCON<5>) bit. For operation of the Timer0 module, see **Section 6.0 "Timer0 Module"**.

#### 14.5.3 PORTB INTERRUPT


An input change on PORTB <7:4> sets the RBIF (INTCON<0>) bit. The interrupt can be enabled/disabled by setting/clearing the RBIE (INTCON<4>) bit. For operation of PORTB (Section 5.2 "PORTB and TRISB Registers").

Note: If a change on the I/O pin should occur when the read operation is being executed (starts during the Q2 cycle and ends before the start of the Q3 cycle), then the RBIF interrupt flag may not get set.

### 14.5.4 COMPARATOR INTERRUPT

See **Section 10.6 "Comparator Interrupts"** for complete description of comparator interrupts.





- Note 1: INTF flag is sampled here (every Q1).
  - 2: Asynchronous interrupt latency = 3-4 Tcy. Synchronous latency = 3 Tcy, where Tcy = instruction cycle time. Latency is the same whether Inst (PC) is a single cycle or a 2-cycle instruction.
  - 3: CLKOUT is available in RC and INTOSC Oscillator mode.
  - 4: For minimum width of INT pulse, refer to AC specs.
  - 5: INTF is enabled to be set anytime during the Q4-Q1 cycles.

TABLE 14-8: SUMMARY OF INTERRUPT REGISTERS

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR Reset	Value on all other Resets <sup>(1)</sup>
0Bh, 8Bh, 10Bh, 18Bh	INTCON	GIE	PEIE	TOIE	INTE	RBIE	TOIF	INTF	RBIF	0000 000x	0000 000u
0Ch	PIR1	EEIF	CMIF	RCIF	TXIF	_	CCP1IF	TMR2IF	TMR1IF	0000 -000	0000 -000
8Ch	PIE1	EEIE	CMIE	RCIE	TXIE	_	CCP1IE	TMR2IE	TMR1IE	0000 -000	0000 -000

Note 1: Other (non Power-up) Resets include MCLR Reset, Brown-out Reset and Watchdog Timer Reset during normal operation.

### 14.6 Context Saving During Interrupts

During an interrupt, only the return PC value is saved on the stack. Typically, users may wish to save key registers during an interrupt (e.g., W register and Status Register). This must be implemented in software.

Example 14-2 stores and restores the Status and W registers. The user register, W\_TEMP, must be defined in a common memory location (i.e., W\_TEMP is defined at 0x70 in Bank 0 and is therefore, accessible at 0xF0, 0x170 and 0x1F0). The Example 14-2:

- · Stores the W register
- · Stores the Status Register
- · Executes the ISR code
- · Restores the Status (and bank select bit register)
- · Restores the W register

### EXAMPLE 14-2: SAVING THE STATUS AND W REGISTERS IN RAM

```
MOVWF W_TEMP
                  ;copy W to temp register,
                  ; could be in any bank
SWAPF STATUS.W
                  ; swap status to be saved
     STATUS, RPO ; change to bank 0
                  ;regardless of current
                  ;bank
MOVWF STATUS TEMP ; save status to bank 0
                  ;register
    :(ISR)
SWAPF STATUS_TEMP, W; swap STATUS_TEMP register
                  ;into W, sets bank to original
                  ;state
MOVWF STATUS
                  ;move W into STATUS register
SWAPF W TEMP.F
                  ;swap W TEMP
SWAPF W_TEMP,W
                  ;swap W_TEMP into W
```

### 14.7 Watchdog Timer (WDT)

The watchdog timer is a free running on-chip RC oscillator which does not require any external components. This RC oscillator is separate from the RC oscillator of the CLKIN pin. That means that the WDT will run, even if the clock on the OSC1 and OSC2 pins of the device has been stopped, for example, by execution of a SLEEP instruction. During normal operation, a WDT time out generates a device Reset. If the device is in Sleep mode, a WDT time out causes the device to wake-up and continue with normal operation. The WDT can be permanently disabled by programming the configuration bit WDTE as clear (Section 14.1 "Configuration Bits").

#### 14.7.1 WDT PERIOD

The WDT has a nominal time out period of 18 ms (with no prescaler). The time out periods vary with temperature, VDD and process variations from part to part (see DC Specifications, Table 17-7). If longer time out periods are desired, a postscaler with a division ratio of up to 1:128 can be assigned to the WDT under software control by writing to the OPTION register. Thus, time out periods up to 2.3 seconds can be realized.

The CLRWDT and SLEEP instructions clear the WDT and the postscaler, if assigned to the WDT, and prevent it from timing out and generating a device Reset.

The TO bit in the Status Register will be cleared upon a Watchdog Timer time out.

### 14.7.2 WDT PROGRAMMING CONSIDERATIONS

It should also be taken in account that under worst case conditions (VDD = Min., Temperature = Max., max. WDT prescaler) it may take several seconds before a WDT time out occurs.

FIGURE 14-16: WATCHDOG TIMER BLOCK DIAGRAM




TABLE 14-9: SUMMARY OF WATCHDOG TIMER REGISTERS

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR Reset	Value on all other Resets
2007h	Config. bits	LVP	BOREN	MCLRE	FOSC2	PWRTE	WDTE	FOSC1	FOSC0	uuuu uuuu	uuuu uuuu
81h, 181h	OPTION	RBPU	INTEDG	T0CS	T0SE	PSA	PS2	PS1	PS0	1111 1111	1111 1111

Legend: x = unknown, u = unchanged, - = unimplemented read as '0', q = value depends upon condition.

**Note:** Shaded cells are not used by the Watchdog Timer.

#### 14.8 Power-Down Mode (Sleep)

The Power-down mode is entered by executing a SLEEP instruction.

If enabled, the Watchdog Timer will be cleared but keeps running, the PD bit in the Status Register is cleared, the TO bit is set, and the oscillator driver is turned off. The I/O ports maintain the status they had, before SLEEP was executed (driving high, low, or hi-impedance).

For lowest current consumption in this mode, all I/O pins should be either at VDD, or Vss, with no external circuitry drawing current from the I/O pin and the comparators, and VREF should be disabled. I/O pins that are hi-impedance inputs should be pulled high or low externally to avoid switching currents caused by floating inputs. The TOCKI input should also be at VDD or Vss for lowest current consumption. The contribution from on chip pull-ups on PORTB should be considered.

The MCLR pin must be at a logic high level (VIHMC).

Note: It should be noted that a Reset generated by a WDT time out does not drive MCLR pin low.

#### 14.8.1 WAKE-UP FROM SLEEP

The device can wake-up from Sleep through one of the following events:

- 1. External Reset input on MCLR pin
- 2. Watchdog Timer wake-up (if WDT was enabled)
- Interrupt from RB0/INT pin, RB Port change, or any Peripheral Interrupt.


The first event will cause a device Reset. The two latter events are considered a continuation of program execution. The TO and PD bits in the Status Register can be used to determine the cause of device Reset. PD bit, which is set on power-up is cleared when Sleep is invoked. TO bit is cleared if WDT wake-up occurred.

When the SLEEP instruction is being executed, the next instruction (PC + 1) is pre-fetched. For the device to wake-up through an interrupt event, the corresponding interrupt enable bit must be set (enabled). Wake-up is regardless of the state of the GIE bit. If the GIE bit is clear (disabled), the device continues execution at the instruction after the SLEEP instruction. If the GIE bit is set (enabled), the device executes the instruction after the SLEEP instruction and then branches to the interrupt address (0004h). In cases where the execution of the instruction following SLEEP is not desirable, the user should have an NOP after the SLEEP instruction.

ote: If the global interrupts are disabled (GIE is cleared), but any interrupt source has both its interrupt enable bit and the corresponding interrupt flag bits set, the device will not enter Sleep. The SLEEP instruction is executed as a NOP instruction.

The WDT is cleared when the device wakes up from Sleep, regardless of the source of wake-up.

#### FIGURE 14-17: WAKE-UP FROM SLEEP THROUGH INTERRUPT



- Note 1: XT, HS or LP Oscillator mode assumed.
  - 2: Tost = 1024Tosc (drawing not to scale). Approximately 1 µs delay will be there for RC Osc mode.
  - 3: GIE = '1' assumed. In this case after wake-up, the processor jumps to the interrupt routine. If GIE = '0', execution will continue in-line.
  - 4: CLKOUT is not available in these Osc modes, but shown here for timing reference.

#### 14.9 Code Protection

With the Code Protect bit is cleared (Code Protect enabled) the contents of the program memory locations are read out as "00". See Programing Specification, DS41196, for details.

Note: Only a Bulk Erase function can set the CP and CPD bits by turning off the code protection. The entire data EEPROM and Flash program memory will be erased to turn the code protection off.

#### 14.10 User ID Locations

Four memory locations (2000h-2003h) are designated as user ID locations where the user can store checksum or other code-identification numbers. These locations are not accessible during normal execution but are readable and writable during program/verify. Only the Least Significant 4 bits of the user ID locations are used.

#### 14.11 In-Circuit Serial Programming


The PIC16F627A/628A/648A microcontrollers can be serially programmed while in the end application circuit. This is simply done with two lines for clock and data, and three other lines for power, ground, and the programming voltage. This allows customers to manufacture boards with unprogrammed devices and then program the microcontroller just before shipping the product. This also allows the most recent firmware, or a custom firmware to be programmed.

The device is placed into a Program/Verify mode by holding the RB6 and RB7 pins low while raising the MCLR (VPP) pin from VIL to VIHH (see programming specification). RB6 becomes the programming clock and RB7 becomes the programming data. Both RB6 and RB7 are Schmitt Trigger inputs in this mode.

After Reset, to place the device into Programming/Verify mode, the program counter (PC) is at location 00h. A 6-bit command is then supplied to the device. Depending on the command, 14 bits of program data are then supplied to or from the device, depending if the command was a load or a read. For complete details of serial programming, please refer to the Programming Specifications (DS41196).

A typical In-Circuit Serial Programming connection is shown in Figure 14-18.

FIGURE 14-18: TYPICAL IN-CIRCUIT
SERIAL PROGRAMMING
CONNECTION



#### 14.12 Low Voltage Programming

The LVP bit of the configuration word, enables the low voltage programming. This mode allows the microcontroller to be programmed via ICSP using only a 5V source. This mode removes the requirement of VIHH to be placed on the  $\overline{\text{MCLR}}$  pin. The LVP bit is normally erased to '1' which enables the low voltage programming. In this mode, the RB4/PGM pin is dedicated to the programming function and ceases to be a general purpose I/O pin. The device will enter Programming mode when a '1' is placed on the RB4/PGM pin. The HV Programming mode is still available by placing VIHH on the  $\overline{\text{MCLR}}$  pin.

- Note 1: While in this mode the RB4 pin can no longer be used as a general purpose I/O pin.
  - 2: VDD must be 5.0V ±10% during erase operations.

If low-voltage Programming mode is not used, the LVP bit should be programmed to a '0' so that RB4/PGM becomes a digital I/O pin. To program the device, VIHH must be placed onto MCLR during programming. The LVP bit may only be programmed when programming is entered with VIHH on MCLR. The LVP bit cannot be programmed when programming is entered with RB4/PGM.

It should be noted, that once the LVP bit is programmed to 0, only high voltage Programming mode can be used to program the device.

NOTES:

#### 15.0 INSTRUCTION SET SUMMARY

Each PIC16F627A/628A/648A instruction is a 14-bit word divided into an OPCODE which specifies the instruction type and one or more operands which further specify the operation of the instruction. The PIC16F627A/628A/648A instruction set summary in Table 15-2 lists **byte-oriented**, **bit-oriented**, and **literal and control** operations. Table 15-1 shows the opcode field descriptions.

For **byte-oriented** instructions, 'f' represents a file register designator and 'd' represents a destination designator. The file register designator specifies which file register is to be used by the instruction.

The destination designator specifies where the result of the operation is to be placed. If 'd' is zero, the result is placed in the W register. If 'd' is one, the result is placed in the file register specified in the instruction.

For **bit-oriented** instructions, 'b' represents a bit field designator which selects the number of the bit affected by the operation, while 'f' represents the number of the file in which the bit is located.

For **literal and control** operations, 'k' represents an eight or eleven bit constant or literal value.

TABLE 15-1: OPCODE FIELD DESCRIPTIONS

	DESCRIF HORS				
Field	Description				
f	Register file address (0x00 to 0x7F)				
W	Working register (accumulator)				
b	Bit address within an 8-bit file register				
k	Literal field, constant data or label				
х	Don't care location (= 0 or 1) The assembler will generate code with x = 0. It is the recommended form of use for compatibility with all Microchip software tools.				
d	Destination select; d = 0: store result in W, d = 1: store result in file register f. Default is d = 1				
label	Label name				
TOS	Top of Stack				
PC	Program Counter				
PCLATH	Program Counter High Latch				
GIE	Global Interrupt Enable bit				
WDT	Watchdog Timer/Counter				
TO	Time out bit				
PD	Power-down bit				
dest	Destination either the W register or the specified register file location				
[]	Options				
( )	Contents				
$\rightarrow$	Assigned to				
<>	Register bit field				
€	In the set of				
italics	User defined term (font is courier)				

The instruction set is highly orthogonal and is grouped into three basic categories:

- Byte-oriented operations
- · Bit-oriented operations
- · Literal and control operations

All instructions are executed within one single instruction cycle, unless a conditional test is true or the program counter is changed as a result of an instruction. In this case, the execution takes two instruction cycles with the second cycle executed as a NOP. One instruction cycle consists of four oscillator periods. Thus, for an oscillator frequency of 4 MHz, the normal instruction execution time is 1  $\mu s$ . If a conditional test is true or the program counter is changed as a result of an instruction, the instruction execution time is 2  $\mu s$ .

Table 15-2 lists the instructions recognized by the MPASM™ assembler.

Figure 15-1 shows the three general formats that the instructions can have.

- **Note 1:** Any unused opcode is reserved. Use of any reserved opcode may cause unexpected operation.
  - **2:** To maintain upward compatibility with future PICmicro products, <u>do not use</u> the OPTION and TRIS instructions.

All examples use the following format to represent a hexadecimal number:

0xhh

where h signifies a hexadecimal digit.

### FIGURE 15-1: GENERAL FORMAT FOR INSTRUCTIONS




TABLE 15-2: PIC16F627A/628A/648A INSTRUCTION SET

Mnemonic, Operands		Description			14-Bit	Opcode	Status	Notes	
				MSb			LSb	Affected	notes
BYTE-ORIE	NTED FI	LE REGISTER OPERATIONS							
ADDWF	f, d	Add W and f	1	00	0111	dfff	ffff	C,DC,Z	1,2
ANDWF	f, d	AND W with f	1	00	0101	dfff	ffff	Z	1,2
CLRF	f	Clear f	1	0.0	0001	lfff	ffff	Z	2
CLRW	_	Clear W	1	0.0	0001	0000	0011	Z	
COMF	f, d	Complement f	1	0.0	1001	dfff	ffff	Z	1,2
DECF	f, d	Decrement f	1	0.0	0011	dfff	ffff	Z	1,2
DECFSZ	f, d	Decrement f, Skip if 0	1(2)	0.0	1011	dfff	ffff		1,2,3
INCF	f, d	Increment f	1	0.0	1010	dfff	ffff	Z	1,2
INCFSZ	f, d	Increment f, Skip if 0	1(2)	0.0	1111	dfff	ffff		1,2,3
IORWF	f, d	Inclusive OR W with f	1	0.0	0100	dfff	ffff	Z	1,2
MOVF	f, d	Move f	1	0.0	1000	dfff	ffff	Z	1,2
MOVWF	f	Move W to f	1	0.0	0000	lfff	ffff		
NOP	_	No Operation	1	0.0	0000	0xx0	0000		
RLF	f, d	Rotate Left f through Carry	1	0.0	1101	dfff	ffff	С	1,2
RRF	f, d	Rotate Right f through Carry	1	0.0	1100	dfff	ffff	С	1,2
SUBWF	f, d	Subtract W from f	1	0.0	0010	dfff	ffff	C,DC,Z	1,2
SWAPF	f, d	Swap nibbles in f	1	0.0	1110	dfff	ffff		1,2
XORWF	f, d	Exclusive OR W with f	1	00	0110	dfff	ffff	Z	1,2
BIT-ORIENT	ED FILE	REGISTER OPERATIONS							
BCF	f, b	Bit Clear f	1	01	00bb	bfff	ffff		1,2
BSF	f, b	Bit Set f	1	01	01bb	bfff	ffff		1,2
BTFSC	f, b	Bit Test f, Skip if Clear	1(2)	01	10bb	bfff	ffff		3
BTFSS	f, b	Bit Test f, Skip if Set	1 <sup>(2)</sup>	01	11bb	bfff	ffff		3
LITERAL AN	ID CONT	TROL OPERATIONS							
ADDLW	k	Add literal and W	1	11	111x	kkkk	kkkk	C,DC,Z	
ANDLW	k	AND literal with W	1	11	1001	kkkk	kkkk	Z	
CALL	k	Call subroutine	2	10	0kkk	kkkk	kkkk		
CLRWDT	_	Clear Watchdog Timer	1	0.0	0000	0110	0100	TO,PD	
GOTO	k	Go to address	2	10	1kkk	kkkk	kkkk		
IORLW	k	Inclusive OR literal with W	1	11	1000	kkkk	kkkk	Z	
MOVLW	k	Move literal to W	1	11	00xx	kkkk	kkkk		
RETFIE	_	Return from interrupt	2	00	0000	0000	1001		
RETLW	k	Return with literal in W	2	11	01xx	kkkk	kkkk		
RETURN	_	Return from Subroutine	2	00	0000	0000	1000	l	
SLEEP	_	Go into Standby mode	1	00	0000	0110	0011	TO,PD	
SUBLW	k	Subtract W from literal	1	11	110x	kkkk	kkkk	C,DC,Z	
XORLW	k	Exclusive OR literal with W	1	11	1010	kkkk	kkkk	Z	

Note 1: When an I/O register is modified as a function of itself (e.g., MOVF PORTB, 1), the value used will be that value present on the pins themselves. For example, if the data latch is '1' for a pin configured as input and is driven low by an external device, the data will be written back with a '0'.

<sup>2:</sup> If this instruction is executed on the TMR0 register (and, where applicable, d = 1), the prescaler will be cleared if assigned to the Timer0 Module.

<sup>3:</sup> If Program Counter (PC) is modified or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.

### 15.1 Instruction Descriptions

ADDLW	Add Lit	eral and	ı w			
Syntax:	[ label ] ADDLW k					
Operands:	$0 \le k \le 1$	255				
Operation:	(W) + k	$\rightarrow$ (W)				
Status Affected:	C, DC,	Z				
Encoding:	11	111x	kkkk	kkkk		
Description:	The contents of the W register are added to the eight bit literal 'k' and the result is placed in the W register.					
Words:	1					
Cycles:	1					
Example	ADDLW	0x15				
	After In:	Instruction Instruction Instruction Instruction Instruction Instruction	10			

ANDLW	AND Literal with W					
Syntax:	[label] ANDLW k					
Operands:	$0 \leq k \leq 255$					
Operation:	(W) .AND. (k) $\rightarrow$ (W)					
Status Affected:	Z					
Encoding:	11 1001 kkkk kkkk					
Description:	The contents of W register are AND'ed with the eight bit literal 'k'. The result is placed in the W register.					
Words:	1					
Cycles:	1					
Example	ANDLW 0x5F					
	Before Instruction W = 0xA3 After Instruction W = 0x03					

ADDWF	Add W and f					
Syntax:	[ label ] ADDWF f,d					
Operands:	$0 \le f \le 127$ $d \in [0,1]$					
Operation:	$(W) + (f) \to (dest)$					
Status Affected:	C, DC, Z					
Encoding:	00 0111 dfff ffff					
Description:	Add the contents of the W register with register 'f'. If 'd' is 0 the result is stored in the W register. If 'd' is 1 the result is stored back in register 'f'.					
Words:	1					
Cycles:	1					
Example	ADDWF REG1, 0					
	Before Instruction $W = 0x17$ $REG1 = 0xC2$ After Instruction $W = 0xD9$ $REG1 = 0xC2$ $Z = 0$ $C = 0$ $DC = 0$					

ANDWF	AND W	with f		
Syntax:	[ label ] ANDWF f,d			
Operands:	$0 \le f \le 1$ $d \in [0,1]$			
Operation:	AA. (W)	ID. (f) $\rightarrow$	(dest)	
Status Affected:	Z			
Encoding:	00	0101	dfff	ffff
Description:	If 'd' is 0 register.	the result	er with regins is stored in the result is	n the W
Words:	1			
Cycles:	1			
Example	ANDWF	REG1,	1	
	After In:	REG1 =	= 0x17 = 0xC2 = 0x17	

BCF	Bit Clea	ar f				
Syntax:	[ label ] BCF f,b					
Operands:	$0 \le f \le 127$ $0 \le b \le 7$					
Operation:	$0 \rightarrow (f <$	b>)				
Status Affected:	None					
Encoding:	01	00bb	bfff	ffff		
Description:	Bit 'b' in	register 'f	' is cleared	l.		
Words:	1					
Cycles:	1					
Example	BCF	REG1,	7			
	After In:	Instruction REG1 : struction REG1 :	= 0xC7			

BSF	Bit Set	f				
Syntax:	[ label ]	BSF f,	b			
Operands:	$0 \le f \le 127$ $0 \le b \le 7$					
Operation:	$1 \rightarrow (f <$	b>)				
Status Affected:	None					
Encoding:	01	01bb	bfff	ffff		
Description:	Bit 'b' in	register	'f' is set.			
Words:	1					
Cycles:	1					
Example	BSF	REG1,	7			
	After In:	Instruction REG1 struction REG1	= 0x0A			

BTFSC	Bit Test f, Skip if Clear					
Syntax:	[ label ] BTFSC f,b					
Operands:	$0 \le f \le 127$ $0 \le b \le 7$					
Operation:	skip if $(f < b >) = 0$					
Status Affected:	None					
Encoding:	01 10bb bfff ffff					
Description:	If bit 'b' in register 'f' is '0' then the next instruction is skipped.  If bit 'b' is '0' then the next instruction fetched during the current instruction execution is discarded, and a NOP is executed instead, making this a two-cycle instruction.					
Words:	1					
Cycles:	1(2)					
Example	HERE BTFSC REG1 FALSE GOTO PROCESS_CODE TRUE • • • •					
	Before Instruction PC = address HERE After Instruction if REG<1> = 0, PC = address TRUE if REG<1>=1, PC = address FALSE					

BTFSS	Bit Test	t f, Skip if	Set		
Syntax:	[ label ] BTFSS f,b				
Operands:	$0 \le f \le 1$ $0 \le b < 1$				
Operation:	skip if (f	<b>) = 1</b>			
Status Affected:	None				
Encoding:	01	11bb	bfff	ffff	
Description:	next ins If bit 'b' instructi current discarde	in register truction is is '1', ther on fetched instruction ed and a Making thon.	skipped.  the next d during to execution  OP is exe	he on, is ecuted	
Words:	1				
Cycles:	1(2)				
Example	HERE FALSE TRUE	BTFSS GOTO •	REG1 PROCES	S_CODE	
	After Ins	nstruction PC = a struction if FLAG< PC = a <1> = 1, PC = a	ddress F 1>=0, address F	FALSE	

CALL	Call Subroutine					
Syntax:	[label] CALL k					
Operands:	$0 \le k \le 2047$					
Operation:	(PC)+ 1 $\rightarrow$ TOS, k $\rightarrow$ PC<10:0>, (PCLATH<4:3>) $\rightarrow$ PC<12:11>					
Status Affected:	None					
Encoding:	10 0kkk kkkk kkkk					
Description:	Call Subroutine. First, return address (PC+1) is pushed onto the stack. The eleven bit immediate address is loaded into PC bits <10:0>. The upper bits of the PC are loaded from PCLATH. CALL is a two-cycle instruction.					
Words:	1					
Cycles:	2					
Example	HERE CALL THERE					
	Before Instruction PC = Address HERE After Instruction PC = Address THERE TOS = Address HERE+1					

CLRF	Clear f
Syntax:	[ label ] CLRF f
Operands:	$0 \le f \le 127$
Operation:	$00h \to (f)$ $1 \to Z$
Status Affected:	Z
Encoding:	00 0001 1fff ffff
Description:	The contents of register 'f' are cleared and the Z bit is set.
Words:	1
Cycles:	1
Example	CLRF REG1
	Before Instruction  REG1 = 0x5A  After Instruction  REG1 = 0x00  Z = 1

CLRW	Clear W	1		
Syntax:	[ label ]	CLRW		
Operands:	None			
Operation:	$\begin{array}{c} 00h \rightarrow 0 \\ 1 \rightarrow Z \end{array}$	(W)		
Status Affected:	Z			
Encoding:	00	0001	0000	0011
Description:	W regis (Z) is se		ared. Zer	o bit
Words:	1			
Cycles:	1			
Example	CLRW			
	After Ins	Instruction W = 0x Struction W = 0x Z = 1	5A	

COMF	Complement f
Syntax:	[ label ] COMF f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	$(\bar{f})  o (dest)$
Status Affected:	Z
Encoding:	00 1001 dfff ffff
Description:	The contents of register 'f' are complemented. If 'd' is 0 the result is stored in W. If 'd' is 1 the result is stored back in register 'f'.
Words:	1
Cycles:	1
Example	COMF REG1, 0
	Before Instruction $REG1 = 0x13$ After Instruction $REG1 = 0x13$ $W = 0xEC$

CLRWDT	Clear W	/atchdo	g Timer	
Syntax:	[ label ]	CLRW	DT	
Operands:	None			
Operation:	$00h \rightarrow V$ $0 \rightarrow \underline{WC}$ $1 \rightarrow \underline{TO}$ $1 \rightarrow \underline{PD}$	OT presc	aler,	
Status Affected:	$\overline{TO}, \overline{PD}$			
Encoding:	00	0000	0110	0100
Description:	Watchdo the pres	og Time	ion resets r. It also r the WDT. are set.	esets
Words:	1			
Cycles:	1			
Example	CLRWDT			
	After Ins	struction WDT co	unter = 3	0x00

DECF	Decrement f
Syntax:	[label] DECF f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(f) - 1 $\rightarrow$ (dest)
Status Affected:	Z
Encoding:	00 0011 dfff ffff
Description:	Decrement register 'f'. If 'd' is 0 the result is stored in the W register. If 'd' is 1 the result is stored back in register 'f'.
Words:	1
Cycles:	1
Example	DECF CNT, 1
	Before Instruction $CNT = 0x01$ $Z = 0$ After Instruction $CNT = 0x00$ $Z = 1$

DECFSZ	Decrement f, Skip if 0
Syntax:	[label] DECFSZ f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(f) - 1 $\rightarrow$ (dest); skip if result = 0
Status Affected:	None
Encoding:	00 1011 dfff ffff
Description:	The contents of register 'f' are decremented. If 'd' is 0 the result is placed in the W register. If 'd' is 1 the result is placed back in register 'f'.  If the result is 0, the next instruction, which is already fetched, is discarded. A NOP is executed instead making it a two-cycle instruction.
Words:	1
Cycles:	1(2)
Example	HERE DECFSZ REG1, 1 GOTO LOOP CONTINUE • •
	Before Instruction PC = address HERE  After Instruction REG1 = REG1 - 1 if REG1 = 0, PC = address CONTINUE if REG1 ≠ 0, PC = address HERE+1

GOTO	Uncond	ditional	Branch	
Syntax:	[ label ]	GOTO	k	
Operands:	$0 \le k \le 2$	2047		
Operation:	$k \rightarrow PC$ PCLATE	1.0.0.	→ PC<12	:11>
Status Affected:	None			
Encoding:	10	1kkk	kkkk	kkkk
Description:	branch. ate valu <10:0>. are load	The eleventer is load. The upplied from	enditional ven-bit im led into P per bits of PCLATH vcle instru	C bits PC <4:3>.
Words:	1			
Cycles:	2			
Example	GOTO TH	HERE		
		struction = Add	ress THE	ERE

INCF	Increment f
Syntax:	[ label ] INCF f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	$(f) + 1 \rightarrow (dest)$
Status Affected:	Z
Encoding:	00 1010 dfff ffff
Description:	The contents of register 'f' are incremented. If 'd' is 0 the result is placed in the W register. If 'd' is 1 the result is placed back in register 'f'.
Words:	1
Cycles:	1
Example	INCF REG1, 1
	Before Instruction $REG1 = 0xFF$ $Z = 0$ After Instruction $REG1 = 0x00$ $Z = 1$

INCFSZ	Increment f, Skip if 0
Syntax:	[label] INCFSZ f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(f) + 1 $\rightarrow$ (dest), skip if result = 0
Status Affected:	None
Encoding:	00 1111 dfff ffff
Description:	The contents of register 'f' are incremented. If 'd' is 0 the result is placed in the W register. If 'd' is 1 the result is placed back in register 'f'. If the result is 0, the next instruction, which is already fetched, is discarded. A NOP is executed instead making it a two-cycle instruction.
Words:	1
Cycles:	1(2)
Example	HERE INCFSZ REG1, 1 GOTO LOOP  CONTINUE  • • •
	Before Instruction PC = address HERE After Instruction REG1 = REG1 + 1 if CNT = 0, PC = address CONTINUE if REG1 ≠ 0,

PC = address HERE +1

IORLW	Inclusive OR Literal with W
Syntax:	[ label ] IORLW k
Operands:	$0 \le k \le 255$
Operation:	(W) .OR. $k \rightarrow$ (W)
Status Affected:	Z
Encoding:	11 1000 kkkk kkkk
Description:	The contents of the W register is OR'ed with the eight bit literal 'k'. The result is placed in the W register.
Words:	1
Cycles:	1
Example	IORLW 0x35
	Before Instruction W = 0x9A After Instruction W = 0xBF Z = 0

MOVLW	Move L	iteral to	W	
Syntax:	[ label]	MOVL	W k	
Operands:	$0 \le k \le 3$	255		
Operation:	$k \rightarrow (W)$	)		
Status Affected:	None			
Encoding:	11	00xx	kkkk	kkkk
Description:	into W r		ral 'k' is lo The don't s 0's.	
Words:	1			
Cycles:	1			
Example	MOVLW	0x5A		
		struction = 0x5	4	

IORWF	Inclusive OR W with f
Syntax:	[ label ] IORWF f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(W) .OR. (f) $\rightarrow$ (dest)
Status Affected:	Z
Encoding:	00 0100 dfff ffff
Description:	Inclusive OR the W register with register 'f'. If 'd' is 0 the result is placed in the W register. If 'd' is 1 the result is placed back in register 'f'.
Words:	1
Cycles:	1
Example	IORWF REG1, 0
	Before Instruction  REG1 = 0x13  W = 0x91  After Instruction  REG1 = 0x13  W = 0x93  7 = 1

MOVF	Move f			
Syntax:	[ label ] MOVF f,d			
Operands:	$0 \le f \le 127$ $d \in [0,1]$			
Operation:	$(f) \to (dest)$			
Status Affected:	Z			
Encoding:	00 1000 dfff ffff			
Description:	The contents of register f is moved to a destination dependent upon the status of d. If d = 0, destination is W register. If d = 1, the destination is file register f itself. d = 1 is useful to test a file register since status flag Z is affected.			
Words:	1			
Cycles:	1			
Example	MOVF REG1, 0			
	After Instruction  W= value in REG1 register  Z = 1			

MOVWF	Move W to f		
Syntax:	[ label ] MOVWF f		
Operands:	$0 \le f \le 127$		
Operation:	$(W) \rightarrow (f)$		
Status Affected:	None		
Encoding:	00 0000 lfff ffff		
Description:	Move data from W register to register 'f'.		
Words:	1		
Cycles:	1		
Example	MOVWF REG1		
	Before Instruction  REG1 = 0xFF  W = 0x4F  After Instruction  REG1 = 0x4F  W = 0x4F		

OPTION	Load Op	otion Re	gister	
Syntax: Operands:	[ label ] OPTION			
Operation: Status Affected:	(W) → OPTION None			
Encoding:	00	0000	0110	0010
Description:	The contents of the W register are loaded in the OPTION register. This instruction is supported for code compatibility with PIC16C5X products. Since OPTION is a readable/writable register, the user can directly address it. Using only register instruction such as			
Words:	1			
Cycles: Example	1			
	To maintain upward compatibility with future PICmicro® products, do not use this instruction.			

NOP	No Operation			
Syntax:	[ label ]	NOP		
Operands:	None			
Operation:	No operation			
Status Affected:	None			
Encoding:	00	0000	0xx0	0000
Description:	No oper	ation.		
Words:	1			
Cycles:	1			
Example	NOP			

RETFIE	Return	Return from Interrupt			
Syntax:	[ label ]	RETF	IE		
Operands:	None				
Operation:		$TOS \rightarrow PC$ , $1 \rightarrow GIE$			
Status Affected:	None				
Encoding:	00	0000	0000	1001	
Description:	Return from Interrupt. Stack is POPed and Top of Stack (TOS) is loaded in the PC. Interrupts are enabled by setting Global Interrupt Enable bit, GIE (INTCON<7>). This is a two-cycle instruction.				
Words:	1				
Cycles:	2				
Example	RETFIE				
	After Interrupt PC = TOS GIE = 1				

RETLW	Return with Literal in W		
Syntax:	[label] RETLW k		
Operands:	$0 \le k \le 255$		
Operation:	$k \rightarrow (W);$ TOS $\rightarrow$ PC		
Status Affected:	None		
Encoding:	11 01xx kkkk kkkk		
Description:	The W register is loaded with the eight bit literal 'k'. The program counter is loaded from the top of the stack (the return address). This is a two-cycle instruction.		
Words:	1		
Cycles:	2		
Example	CALL TABLE; W contains table ; offset value • ; W now has table value •		
TABLE	ADDWF PC;W = offset RETLW k1;Begin table RETLW k2;  RETLW kn; End of table  Before Instruction W = 0x07  After Instruction W = value of k8		

RLF	Rotate Left f through Carry			
Syntax:	[ label ]	RLF	f,d	
Operands:	$0 \le f \le 12$ $d \in [0,1]$			
Operation:	See des	cription b	oelow	
Status Affected:	С			
Encoding:	00	1101	dfff	ffff
Description:	rotated of the Carry is placed	one bit to y Flag. If I in the W sult is sto	register 'f' the left the left the 'd' is 0 the left the	nrough e result If 'd' is
Words:	1			
Cycles:	1			
Example	RLF	REG1,	0	
	C After Ins	31=1110 = 0 truction 31=1110	0110	

#### **RETURN Return from Subroutine**

Syntax:	[ label ] RETURN			
Operands:	None			
Operation:	$TOS \to$	PC		
Status Affected:	None			
Encoding:	00	0000	0000	1000
Description:	Return from subroutine. The stack is POPed and the top of the stack (TOS) is loaded into the program counter. This is a two-cycle instruction.			
Words:	1			
Cycles:	2			
Example	RETURN			
	After In	errupt		

PC = TOS

RRF	Rotate Right f through Carry	SUBLW	Subtract W from Literal		
Syntax:	[label] RRF f,d	Syntax:	[ label ] SUBLW k		
Operands:	$0 \le f \le 127$	Operands:	$0 \le k \le 255$		
	d ∈ [0,1]	Operation:	$k - (W) \rightarrow (W)$		
Operation: Status Affected:	See description below C	Status Affected:	C, DC, Z		
Encoding:	00 1100 dfff ffff	Encoding:	11 110x kkkk kkkk		
Description:	The contents of register 'f' are	Description:	The W register is subtracted (2's		
	rotated one bit to the right through the Carry Flag. If 'd' is 0 the result is placed in the W		complement method) from the eight bit literal 'k'. The result is placed in the W register.		
	register. If 'd' is 1 the result is	Words:	1		
	placed back in register 'f'.	Cycles:	1		
	C REGISTER F	Example 1:	SUBLW 0x02		
Words:	1		Before Instruction		
Cycles:	1		W = 1		
Example	RRF REG1, 0		C = ?		
p.o	Before Instruction		After Instruction		
	REG1 = 1110 0110		W = 1		
	C = 0		C = 1; result is positive		
	After Instruction  REG1 = 1110 0110	Example 2:	Before Instruction		
	W = 0111 0011		W = 2 C = ?		
	C = 0		After Instruction		
			W = 0		
SLEEP			C = 1; result is zero		
Syntax:	[ label ] SLEEP	Example 3:	Before Instruction		
Operands:	None		W = 3 C = ?		
Operation:	00h → WDT,		After Instruction		
	$0 \to \underline{\text{WDT prescaler}},$ $1 \to \overline{\text{TO}},$		W = 0xFF		
	$0 \rightarrow \overline{PD}$		C = 0; result is negative		
Status Affected:	TO, PD				
Encoding:	00 0000 0110 0011				
Description:	The power-down Status bit, PD				
	is cleared. Time out Status bit, TO is set. Watchdog Timer and				
	its prescaler are cleared.				
	The processor is put into Sleep				
	mode with the oscillator stopped. See <b>Section 14.8</b>				
	"Power-Down Mode (Sleep)"				
	for more details.				
Words:	1				
Cycles:	1				
Example:	SLEEP				

SUBWF	Subtract W from f
Syntax:	[ label ] SUBWF f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(f) - (W) $\rightarrow$ (dest)
Status Affected:	C, DC, Z
Encoding:	00 0010 dfff ffff
Description:	Subtract (2's complement method) W register from register 'f'. If 'd' is 0 the result is stored in the W register. If 'd' is 1 the result is stored back in register 'f'.
Words:	1
Cycles:	1
Example 1:	SUBWF REG1, 1
	Before Instruction
	REG1 = 3 W = 2 C = ?
	After Instruction
	REG1 = 1 W = 2 C = 1; result is positive DC = 1 Z = 0
Example 2:	Before Instruction
	REG1 = 2 W = 2 C = ?
	After Instruction
	REG1 = 0 W = 2 C = 1; result is zero Z = DC = 1
Example 3:	Before Instruction
	REG1 = 1 W = 2 C = ?
	After Instruction
	REG1 = 0xFF W = 2 C = 0; result is negative Z = DC = 0

SWAPF	Swap Nibbles in f		
Syntax:	[label] SWAPF f,d		
Operands:	$0 \le f \le 127$ $d \in [0,1]$		
Operation:	$ \begin{array}{l} (\text{f$<$3:0$>}) \rightarrow (\text{dest$<$7:4$>}), \\ (\text{f$<$7:4$>}) \rightarrow (\text{dest$<$3:0$>}) \end{array} $		
Status Affected:	None		
Encoding:	00 1110 dfff ffff		
Description:	The upper and lower nibbles of register 'f' are exchanged. If 'd' is 0 the result is placed in W register. If 'd' is 1 the result is placed in register 'f'.		
Words:	1		
Cycles:	1		
Example	SWAPF REG1, 0		
	Before Instruction		
	REG1 = 0xA5		
	After Instruction		
	REG1 = 0xA5 $W = 0x5A$		

TRIS	Load TR	IS Regis	ster	
Syntax:	[label] TRIS f			
Operands:	$5 \le f \le 7$			
Operation:	$(W) \rightarrow T$	RIS regi	ster f;	
Status Affected:	None			
Encoding:	00	0000	0110	Offf
Description:	The instruction is supported for code compatibility with the PIC16C5X products. Since TRIS registers are readable and writable, the user can directly address them.			
Words:	1	1		
Cycles:	1			
Example				
	ity with	future P s, do no	vard com lCmicro <sup>©</sup> it use thi	8

XORLW	Exclusive OR Literal with W							
Syntax:	[label] XORLW k							
Operands:	$0 \le k \le 255$							
Operation:	(W) .XOR. $k \rightarrow (W)$							
Status Affected:	Z							
Encoding:	11 1010 kkkk kkkk							
Description:	The contents of the W register are XOR'ed with the eight bit literal 'k'. The result is placed in the W register.							
Words:	1							
Cycles:	1							
Example:	XORLW 0xAF							
	Before Instruction							
	W = 0xB5							
	After Instruction							
	W = 0x1A							

XORWF	Exclusive OR W with f						
Syntax:	[ label ] XORWF f,d						
Operands:	$0 \le f \le 127$ $d \in [0,1]$						
Operation:	(W) .XOR. (f) $\rightarrow$ (dest)						
Status Affected:	Z						
Encoding:	00 0110 dfff ffff						
Description:	Exclusive OR the contents of the W register with register 'f'. If 'd' is 0 the result is stored in the W register. If 'd' is 1 the result is stored back in register 'f'.						
Words:	1						
Cycles:	1						
Example	XORWF REG1, 1						
	Before Instruction						
	REG1 = 0xAF $W = 0xB5$						
	After Instruction						
	REG1 = 0x1A $W = 0xB5$						

#### 16.0 DEVELOPMENT SUPPORT

The PICmicro<sup>®</sup> microcontrollers are supported with a full range of hardware and software development tools:

- Integrated Development Environment
  - MPLAB® IDE Software
- Assemblers/Compilers/Linkers
  - MPASM™ Assembler
  - MPLAB C17 and MPLAB C18 C Compilers
  - MPLINK<sup>™</sup> Object Linker/ MPLIB<sup>™</sup> Object Librarian
  - MPLAB C30 C Compiler
  - MPLAB ASM30 Assembler/Linker/Library
- Simulators
  - MPLAB SIM Software Simulator
  - MPLAB dsPIC30 Software Simulator
- Emulators
  - MPLAB ICE 2000 In-Circuit Emulator
  - MPLAB ICE 4000 In-Circuit Emulator
- In-Circuit Debugger
  - MPLAB ICD 2
- Device Programmers
  - PRO MATE® II Universal Device Programmer
  - PICSTART® Plus Development Programmer
  - MPLAB PM3 Device Programmer
- Low-Cost Demonstration Boards
  - PICDEM™ 1 Demonstration Board
  - PICDEM.net™ Demonstration Board
  - PICDEM 2 Plus Demonstration Board
  - PICDEM 3 Demonstration Board
  - PICDEM 4 Demonstration Board
  - PICDEM 17 Demonstration Board
  - PICDEM 18R Demonstration Board
  - PICDEM LIN Demonstration Board
  - PICDEM USB Demonstration Board
- Evaluation Kits
  - KEELOQ®
  - PICDEM MSC
  - microID®
  - CAN
  - PowerSmart®
  - Analog

### 16.1 MPLAB Integrated Development Environment Software

The MPLAB IDE software brings an ease of software development previously unseen in the 8/16-bit microcontroller market. The MPLAB IDE is a Windows® based application that contains:

- An interface to debugging tools
  - simulator
  - programmer (sold separately)
  - emulator (sold separately)
  - in-circuit debugger (sold separately)
- · A full-featured editor with color coded context
- · A multiple project manager
- Customizable data windows with direct edit of contents
- · High-level source code debugging
- Mouse over variable inspection
- · Extensive on-line help

The MPLAB IDE allows you to:

- Edit your source files (either assembly or C)
- One touch assemble (or compile) and download to PICmicro emulator and simulator tools (automatically updates all project information)
- · Debug using:
  - source files (assembly or C)
  - mixed assembly and C
  - machine code

MPLAB IDE supports multiple debugging tools in a single development paradigm, from the cost effective simulators, through low-cost in-circuit debuggers, to full-featured emulators. This eliminates the learning curve when upgrading to tools with increasing flexibility and power.

#### 16.2 MPASM Assembler

The MPASM assembler is a full-featured, universal macro assembler for all PICmicro MCUs.

The MPASM assembler generates relocatable object files for the MPLINK object linker, Intel® standard hex files, MAP files to detail memory usage and symbol reference, absolute LST files that contain source lines and generated machine code and COFF files for debugging.

The MPASM assembler features include:

- · Integration into MPLAB IDE projects
- User defined macros to streamline assembly code
- Conditional assembly for multi-purpose source files
- Directives that allow complete control over the assembly process

# 16.3 MPLAB C17 and MPLAB C18 C Compilers

The MPLAB C17 and MPLAB C18 Code Development Systems are complete ANSI C compilers for Microchip's PIC17CXXX and PIC18CXXX family of microcontrollers. These compilers provide powerful integration capabilities, superior code optimization and ease of use not found with other compilers.

For easy source level debugging, the compilers provide symbol information that is optimized to the MPLAB IDE debugger.

#### 16.4 MPLINK Object Linker/ MPLIB Object Librarian

The MPLINK object linker combines relocatable objects created by the MPASM assembler and the MPLAB C17 and MPLAB C18 C compilers. It can link relocatable objects from precompiled libraries, using directives from a linker script.

The MPLIB object librarian manages the creation and modification of library files of precompiled code. When a routine from a library is called from a source file, only the modules that contain that routine will be linked in with the application. This allows large libraries to be used efficiently in many different applications.

The object linker/library features include:

- Efficient linking of single libraries instead of many smaller files
- Enhanced code maintainability by grouping related modules together
- Flexible creation of libraries with easy module listing, replacement, deletion and extraction

#### 16.5 MPLAB C30 C Compiler

The MPLAB C30 C compiler is a full-featured, ANSI compliant, optimizing compiler that translates standard ANSI C programs into dsPIC30F assembly language source. The compiler also supports many command line options and language extensions to take full advantage of the dsPIC30F device hardware capabilities and afford fine control of the compiler code generator.

MPLAB C30 is distributed with a complete ANSI C standard library. All library functions have been validated and conform to the ANSI C library standard. The library includes functions for string manipulation, dynamic memory allocation, data conversion, time-keeping and math functions (trigonometric, exponential and hyperbolic). The compiler provides symbolic information for high-level source debugging with the MPLAB IDE.

### 16.6 MPLAB ASM30 Assembler, Linker and Librarian

MPLAB ASM30 assembler produces relocatable machine code from symbolic assembly language for dsPIC30F devices. MPLAB C30 compiler uses the assembler to produce it's object file. The assembler generates relocatable object files that can then be archived or linked with other relocatable object files and archives to create an executable file. Notable features of the assembler include:

- Support for the entire dsPIC30F instruction set
- · Support for fixed-point and floating-point data
- · Command line interface
- Rich directive set
- Flexible macro language
- MPLAB IDE compatibility

#### 16.7 MPLAB SIM Software Simulator

The MPLAB SIM software simulator allows code development in a PC hosted environment by simulating the PICmicro series microcontrollers on an instruction level. On any given instruction, the data areas can be examined or modified and stimuli can be applied from a file, or user defined key press, to any pin. The execution can be performed in Single-Step, Execute Until Break or Trace mode.

The MPLAB SIM simulator fully supports symbolic debugging using the MPLAB C17 and MPLAB C18 C Compilers, as well as the MPASM assembler. The software simulator offers the flexibility to develop and debug code outside of the laboratory environment, making it an excellent, economical software development tool.

#### 16.8 MPLAB SIM30 Software Simulator

The MPLAB SIM30 software simulator allows code development in a PC hosted environment by simulating the dsPIC30F series microcontrollers on an instruction level. On any given instruction, the data areas can be examined or modified and stimuli can be applied from a file, or user defined key press, to any of the pins.

The MPLAB SIM30 simulator fully supports symbolic debugging using the MPLAB C30 C Compiler and MPLAB ASM30 assembler. The simulator runs in either a Command Line mode for automated tasks, or from MPLAB IDE. This high-speed simulator is designed to debug, analyze and optimize time intensive DSP routines.

# 16.9 MPLAB ICE 2000 High-Performance Universal In-Circuit Emulator

The MPLAB ICE 2000 universal in-circuit emulator is intended to provide the product development engineer with a complete microcontroller design tool set for PICmicro microcontrollers. Software control of the MPLAB ICE 2000 in-circuit emulator is advanced by the MPLAB Integrated Development Environment, which allows editing, building, downloading and source debugging from a single environment.

The MPLAB ICE 2000 is a full-featured emulator system with enhanced trace, trigger and data monitoring features. Interchangeable processor modules allow the system to be easily reconfigured for emulation of different processors. The universal architecture of the MPLAB ICE in-circuit emulator allows expansion to support new PICmicro microcontrollers.

The MPLAB ICE 2000 in-circuit emulator system has been designed as a real-time emulation system with advanced features that are typically found on more expensive development tools. The PC platform and Microsoft® Windows 32-bit operating system were chosen to best make these features available in a simple, unified application.

# 16.10 MPLAB ICE 4000 High-Performance Universal In-Circuit Emulator

The MPLAB ICE 4000 universal in-circuit emulator is intended to provide the product development engineer with a complete microcontroller design tool set for highend PICmicro microcontrollers. Software control of the MPLAB ICE in-circuit emulator is provided by the MPLAB Integrated Development Environment, which allows editing, building, downloading and source debugging from a single environment.

The MPLAB ICD 4000 is a premium emulator system, providing the features of MPLAB ICE 2000, but with increased emulation memory and high-speed performance for dsPIC30F and PIC18XXXX devices. Its advanced emulator features include complex triggering and timing, up to 2 Mb of emulation memory and the ability to view variables in real-time.

The MPLAB ICE 4000 in-circuit emulator system has been designed as a real-time emulation system with advanced features that are typically found on more expensive development tools. The PC platform and Microsoft Windows 32-bit operating system were chosen to best make these features available in a simple, unified application.

#### 16.11 MPLAB ICD 2 In-Circuit Debugger

Microchip's In-Circuit Debugger, MPLAB ICD 2, is a powerful, low-cost, run-time development tool, connecting to the host PC via an RS-232 or high-speed USB interface. This tool is based on the Flash PICmicro MCUs and can be used to develop for these and other PICmicro microcontrollers. The MPLAB ICD 2 utilizes the in-circuit debugging capability built into the Flash devices. This feature, along with Microchip's In-Circuit Serial Programming™ (ICSP™) protocol, offers cost effective in-circuit Flash debugging from the graphical user interface of the MPLAB Integrated Development Environment. This enables a designer to develop and debug source code by setting breakpoints, single-stepping and watching variables, CPU status and peripheral registers. Running at full speed enables testing hardware and applications in real-time. MPLAB ICD 2 also serves as a development programmer for selected PICmicro devices.

# 16.12 PRO MATE II Universal Device Programmer

The PRO MATE II is a universal, CE compliant device programmer with programmable voltage verification at VDDMIN and VDDMAX for maximum reliability. It features an LCD display for instructions and error messages and a modular detachable socket assembly to support various package types. In Stand-Alone mode, the PRO MATE II device programmer can read, verify and program PICmicro devices without a PC connection. It can also set code protection in this mode.

#### 16.13 MPLAB PM3 Device Programmer

The MPLAB PM3 is a universal, CE compliant device programmer with programmable voltage verification at VDDMIN and VDDMAX for maximum reliability. It features a large LCD display (128 x 64) for menus and error messages and a modular detachable socket assembly to support various package types. The ICSP™ cable assembly is included as a standard item. In Stand-Alone mode, the MPLAB PM3 device programmer can read, verify and program PICmicro devices without a PC connection. It can also set code protection in this mode. MPLAB PM3 connects to the host PC via an RS-232 or USB cable. MPLAB PM3 has high-speed communications and optimized algorithms for quick programming of large memory devices and incorporates an SD/MMC card for file storage and secure data applications.

# 16.14 PICSTART Plus Development Programmer

The PICSTART Plus development programmer is an easy-to-use, low-cost, prototype programmer. It connects to the PC via a COM (RS-232) port. MPLAB Integrated Development Environment software makes using the programmer simple and efficient. The PICSTART Plus development programmer supports most PICmicro devices up to 40 pins. Larger pin count devices, such as the PIC16C92X and PIC17C76X, may be supported with an adapter socket. The PICSTART Plus development programmer is CE compliant.

#### 16.15 PICDEM 1 PICmicro Demonstration Board

The PICDEM 1 demonstration board demonstrates the capabilities of the PIC16C5X (PIC16C54 to PIC16C58A), PIC16C61, PIC16C62X, PIC16C71, PIC16C8X, PIC17C42, PIC17C43 and PIC17C44. All necessary hardware and software is included to run basic demo programs. The sample microcontrollers provided with the PICDEM 1 demonstration board can be programmed with a PRO MATE II device programmer or a PICSTART Plus development programmer. The PICDEM 1 demonstration board can be connected to the MPLAB ICE in-circuit emulator for testing. A prototype area extends the circuitry for additional application components. Features include an RS-232 interface, a potentiometer for simulated analog input, push button switches and eight LEDs.

### 16.16 PICDEM.net Internet/Ethernet Demonstration Board

The PICDEM.net demonstration board is an Internet/ Ethernet demonstration board using the PIC18F452 microcontroller and TCP/IP firmware. The board supports any 40-pin DIP device that conforms to the standard pinout used by the PIC16F877 or PIC18C452. This kit features a user friendly TCP/IP stack, web server with HTML, a 24L256 Serial EEPROM for Xmodem download to web pages into Serial EEPROM, ICSP/MPLAB ICD 2 interface connector, an Ethernet interface, RS-232 interface and a 16 x 2 LCD display. Also included is the book and CD-ROM "TCP/IP Lean, Web Servers for Embedded Systems," by Jeremy Bentham

### 16.17 PICDEM 2 Plus Demonstration Board

The PICDEM 2 Plus demonstration board supports many 18, 28 and 40-pin microcontrollers, including PIC16F87X and PIC18FXX2 devices. All the necessary hardware and software is included to run the demonstration programs. The sample microcontrollers provided with the PICDEM 2 demonstration board can be programmed with a PRO MATE II device programmer, PICSTART Plus development programmer, or MPLAB ICD 2 with a Universal Programmer Adapter. The MPLAB ICD 2 and MPLAB ICE in-circuit emulators may also be used with the PICDEM 2 demonstration board to test firmware. A prototype area extends the circuitry for additional application components. Some of the features include an RS-232 interface, a 2 x 16 LCD display, a piezo speaker, an on-board temperature sensor, four LEDs and sample PIC18F452 and PIC16F877 Flash microcontrollers.

#### 16.18 PICDEM 3 PIC16C92X Demonstration Board

The PICDEM 3 demonstration board supports the PIC16C923 and PIC16C924 in the PLCC package. All the necessary hardware and software is included to run the demonstration programs.

## 16.19 PICDEM 4 8/14/18-Pin Demonstration Board

The PICDEM 4 can be used to demonstrate the capabilities of the 8, 14 and 18-pin PIC16XXXX and PIC18XXXX MCUs, including the PIC16F818/819, PIC16F87/88, PIC16F62XA and the PIC18F1320 family of microcontrollers. PICDEM 4 is intended to showcase the many features of these low pin count parts, including LIN and Motor Control using ECCP. Special provisions are made for low-power operation with the supercapacitor circuit and jumpers allow onboard hardware to be disabled to eliminate current draw in this mode. Included on the demo board are provisions for Crystal, RC or Canned Oscillator modes, a five volt regulator for use with a nine volt wall adapter or battery, DB-9 RS-232 interface, ICD connector for programming via ICSP and development with MPLAB ICD 2, 2 x 16 liquid crystal display, PCB footprints for H-Bridge motor driver, LIN transceiver and EEPROM. Also included are: header for expansion, eight LEDs, four potentiometers, three push buttons and a prototyping area. Included with the kit is a PIC16F627A and a PIC18F1320. Tutorial firmware is included along with the User's Guide.

#### 16.20 PICDEM 17 Demonstration Board

The PICDEM 17 demonstration board is an evaluation board that demonstrates the capabilities of several Microchip microcontrollers, including PIC17C752, PIC17C756A, PIC17C762 and PIC17C766. A programmed sample is included. The PRO MATE II device programmer, or the PICSTART Plus development programmer, can be used to reprogram the device for user tailored application development. The PICDEM 17 demonstration board supports program download and execution from external on-board Flash memory. A generous prototype area is available for user hardware expansion.

### 16.21 PICDEM 18R PIC18C601/801 Demonstration Board

The PICDEM 18R demonstration board serves to assist development of the PIC18C601/801 family of Microchip microcontrollers. It provides hardware implementation of both 8-bit Multiplexed/Demultiplexed and 16-bit Memory modes. The board includes 2 Mb external Flash memory and 128 Kb SRAM memory, as well as serial EEPROM, allowing access to the wide range of memory types supported by the PIC18C601/801.

### 16.22 PICDEM LIN PIC16C43X Demonstration Board

The powerful LIN hardware and software kit includes a series of boards and three PICmicro microcontrollers. The small footprint PIC16C432 and PIC16C433 are used as slaves in the LIN communication and feature on-board LIN transceivers. A PIC16F874 Flash microcontroller serves as the master. All three microcontrollers are programmed with firmware to provide LIN bus communication.

#### 16.23 PICkit<sup>™</sup> 1 Flash Starter Kit

A complete "development system in a box", the PICkit Flash Starter Kit includes a convenient multi-section board for programming, evaluation and development of 8/14-pin Flash PIC® microcontrollers. Powered via USB, the board operates under a simple Windows GUI. The PICkit 1 Starter Kit includes the User's Guide (on CD ROM), PICkit 1 tutorial software and code for various applications. Also included are MPLAB® IDE (Integrated Development Environment) software, software and hardware "Tips 'n Tricks for 8-pin Flash PIC® Microcontrollers" Handbook and a USB interface cable. Supports all current 8/14-pin Flash PIC microcontrollers, as well as many future planned devices.

#### 16.24 PICDEM USB PIC16C7X5 Demonstration Board

The PICDEM USB Demonstration Board shows off the capabilities of the PIC16C745 and PIC16C765 USB microcontrollers. This board provides the basis for future USB products.

#### 16.25 Evaluation and Programming Tools

In addition to the PICDEM series of circuits, Microchip has a line of evaluation kits and demonstration software for these products.

- KEELOQ evaluation and programming tools for Microchip's HCS Secure Data Products
- CAN developers kit for automotive network applications
- Analog design boards and filter design software
- PowerSmart battery charging evaluation/ calibration kits
- IrDA® development kit
- microID development and rfLab<sup>TM</sup> development software
- SEEVAL® designer kit for memory evaluation and endurance calculations
- PICDEM MSC demo boards for Switching mode power supply, high-power IR driver, delta sigma ADC and flow rate sensor

Check the Microchip web page and the latest Product Selector Guide for the complete list of demonstration and evaluation kits.

NOTES:

#### 17.0 ELECTRICAL SPECIFICATIONS

#### **Absolute Maximum Ratings(†)**

Ambient temperature under bias	40 to +125°C
Storage temperature	65°C to +150°C
Voltage on VDD with respect to Vss	0.3 to +6.5V
Voltage on MCLR and RA4 with respect to Vss	0.3 to +14V
Voltage on all other pins with respect to Vss	0.3V to VDD + 0.3V
Total power dissipation <sup>(1)</sup>	800 mW
Maximum current out of Vss pin	300 mA
Maximum current into VDD pin	250 mA
Input clamp current, lik (Vi < 0 or Vi > VDD)	± 20 mA
Output clamp current, lok (Vo < 0 or Vo >VDD)	± 20 mA
Maximum output current sunk by any I/O pin	25 mA
Maximum output current sourced by any I/O pin	25 mA
Maximum current sunk by PORTA and PORTB (Combined)	200 mA
Maximum current sourced by PORTA and PORTB (Combined)	200 mA
<b>Note 1:</b> Power dissipation is calculated as follows: PDIS = VDD x {IDD - $\sum$ IOH} + $\sum$ {(VDD-VOH)	$x IOH$ + $\sum (VOI x IOL)$

**† NOTICE**: Stresses above those listed under "Absolute Maximum Ratings" may cause permanent damage to the device. This is a stress rating only and functional operation of the device at those or any other conditions above those indicated in the operation listings of this specification is not implied. Exposure to maximum rating conditions for extended periods may affect device reliability.

Note: Voltage spikes below Vss at the  $\overline{\text{MCLR}}$  pin, inducing currents greater than 80 mA, may cause latch-up. Thus, a series resistor of 50-100  $\Omega$  should be used when applying a "low" level to the  $\overline{\text{MCLR}}$  pin rather than pulling this pin directly to Vss.

FIGURE 17-1: PIC16F627A/628A/648A VOLTAGE-FREQUENCY GRAPH, -40°C ≤ TA ≤ +125°C





FIGURE 17-2: PIC16LF627A/628A/648A VOLTAGE-FREQUENCY GRAPH, -40°C ≤ TA ≤ +85°C



# 17.1 DC Characteristics: PIC16F627A/628A/648A (Industrial, Extended) PIC16LF627A/628A/648A (Industrial)

			Standard Operating Conditions (unless otherwise stated)  Operating temperature -40°C ≤ Ta ≤ +85°C for industrial						
PIC16F627A/628A/648A (Industrial, Extended)			Standard Operating Conditions (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for industrial and $-40^{\circ}\text{C} \le \text{Ta} \le +125^{\circ}\text{C}$ for extended						
Param No.	Sym	Characteristic/Device	Min Typ† Max Units Conditions						
	VDD	Supply Voltage							
D001		PIC16LF627A/628A/648A	2.0	_	5.5	V			
		PIC16F627A/628A/648A	3.0	_	5.5	V			
D002	VDR	RAM Data Retention Voltage <sup>(1)</sup>	_	1.5*		V	Device in Sleep mode		
D003	VPOR	VDD Start Voltage to ensure Power-on Reset	_	Vss	_	V	See <b>Section 14.4</b> on Power-on Reset for details		
D004	SVDD	VDD Rise Rate to ensure Power-on Reset	0.05*	_	_	V/ms	See <b>Section 14.4</b> on Power-on Reset for details		
D005	VBOR	Brown-out Reset Voltage	3.65 3.65	4.0 4.0	4.35 4.4	V V	BOREN configuration bit is set BOREN configuration bit is set, Extended		

Legend: Rows with standard voltage device data only are shaded for improved readability.

Note 1: This is the limit to which VDD can be lowered in Sleep mode without losing RAM data.

<sup>\*</sup> These parameters are characterized but not tested.

<sup>†</sup> Data in "Typ" column is at 5.0 V, 25°C, unless otherwise stated. These parameters are for design guidance only and are not tested.

# 17.2 DC Characteristics: PIC16F627A/628A/648A (Industrial) PIC16LF627A/628A/648A (Industrial)

			Standard Operating Cor Operating temperature				nerwise stated) C for industrial	
Param No.	LF and F Device Characteristics	Min†	Тур	Max	Units		Conditions	
						VDD	Note	
Supply Volt				1		ı		
D001	LF	2.0	-	5.5	V			
	LF/F	3.0	_	5.5	V	_		
Power-dow	n Base Current (IPD)							
	LF	_	0.1	0.80	μΑ	2.0	WDT, BOR, Comparators, VREF, and	
D020	LF/F	_	0.1	0.85	μΑ	3.0	T10SC: disabled	
	*		0.2	2.7	μΑ	5.0		
Peripheral	Module Current (∆IMOD) <sup>(1)</sup>			1	T	1		
	LF		1	2.0	μΑ	2.0	WDT Current	
D021	LF/F		2	3.4	μΑ	3.0		
	LI /I		9	17.0	μΑ	5.0		
D022	LF/F		32	TBD	μΑ	4.5	BOR Current	
DOZZ	LI /I	_	33	TBD	μΑ	5.0		
	LF	_	15	TBD	μΑ	2.0	Comparator Current	
D023	LF/F		27	TBD	μΑ	3.0		
	LI /I	_	49	TBD	μΑ	5.0		
	LF	_	34	TBD	μΑ	2.0	VREF Current	
D024	LF/F	_	50	TBD	μΑ	3.0		
	LF/F	_	80	TBD	μΑ	5.0		
	LF	_	1.2	2.0	μΑ	2.0	T1Osc Current	
D025	LF/F		1.3	2.2	μΑ	3.0		
	LF/F	_	1.8	2.9	μΑ	5.0		
Supply Cur	rent (IDD)							
	LF		12	15	μΑ	2.0	Fosc = 32 kHz	
D010	LF/F		21	25	μΑ	3.0	LP Oscillator Mode	
	LI*/F		38	48	μΑ	5.0		
	LF		130	190	μΑ	2.0	Fosc = 1 MHz	
D011	LF/F		220	340	μΑ	3.0	XT Oscillator Mode	
	Lľ/ľ		370	520	μΑ	5.0		
	LF		270	350	μΑ	2.0	Fosc = 4 MHz	
D012	15/5	_	430	600	μΑ	3.0	XT Oscillator Mode	
	LF/F	_	780	995	μΑ	5.0		
D012	15/5	_	2.6	2.9	mA	4.5	Fosc = 20 MHz	
D013	LF/F	_	3	3.3	mA	5.0	HS Oscillator Mode	

Note 1: The "\Delta" current is the additional current consumed when this peripheral is enabled. This current should be added to the base IDD or IPD measurement. Max values should be used when calculating total current consumption.

#### 17.3 DC Characteristics: PIC16F627A/628A/648A (Extended)

		Standard Operating Cor Operating temperature					therwise stated) 5°C for extended
Param No.	Device Characteristics	Min†	Тур	Max	Units		Conditions
						VDD	Note
Supply V	oltage (VDD)		1	T	1	1	
D001	_	3.0	_	5.5	V	_	
Power-do	own Base Current (IPD)						
D020E	_	_	0.1	TBD	μΑ	3.0	WDT, BOR, Comparators, VREF, and
DUZUE			0.2	TBD	μΑ	5.0	T1OSC: disabled
Periphera	al Module Current (∆IMOD) <sup>(1)</sup>						
D021E			2	TBD	μА	3.0	WDT Current
DUZTE	_	_	9	TBD	μΑ	5.0	
DoooF		_	32	TBD	μΑ	4.5	BOR Current
D022E	_	_	33	TBD	μΑ	5.0	7
Doool		_	27	TBD	μΑ	3.0	Comparator Current
D023E	_	_	49	TBD	μΑ	5.0	7
500.15		_	50	TBD	μΑ	3.0	VREF Current
D024E	_	_	83	TBD	μΑ	5.0	
		_	1.3	TBD	μΑ	3.0	T1Osc Current
D025E	_	_	1.8	TBD	μΑ	5.0	
Supply C	urrent (IDD)		ı				•
	· ·		21	TBD	μА	3.0	Fosc = 32 kHz
D010E	_		38	TBD	μA	5.0	LP Oscillator Mode
		<b>1</b> —	220	TBD	μA	3.0	Fosc = 1 MHz
D011E	_	_	370	TBD	μA	5.0	XT Oscillator Mode
		<b>†</b> –	430	TBD	μA	3.0	Fosc = 4 MHz
D012E	_	_	780	TBD	μΑ	5.0	XT Oscillator Mode
		_	2.6	TBD	mA	4.5	Fosc = 20 MHz
D013E	_		3	TBD	mA	5.0	HS Oscillator Mode

Note 1: The "\Delta" current is the additional current consumed when this peripheral is enabled. This current should be added to the base IDD or IPD measurement. Max values should be used when calculating total current consumption.

# 17.4 DC Characteristics: PIC16F627A/628A/648A (Industrial, Extended) PIC16LF627A/628A/648A (Industrial)

DC CHARACTERISTICS			Operating tempe	Standard Operating Conditions (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial and $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for extended  Operating voltage VDD range as described in DC spec Table 17-2 and Table 17-3						
Param. No.	Sym	Characteristic/Device	Min	Typ†	Max	Conditions				
	VIL	Input Low Voltage								
D030		I/O ports with TTL buffer	Vss Vss	_	0.8 0.15 VDD	V	VDD = 4.5V to 5.5V otherwise			
D031 D032		with Schmitt Trigger input <sup>(4)</sup> MCLR, RA4/T0CKI,OSC1 (in RC mode)	Vss Vss	_	0.2 VDD 0.2 VDD	V	(Note1)			
D033		OSC1 (in HS) OSC1 (in LP and XT)	Vss Vss	_	0.3 VDD 0.8	V V				
	VIH	Input High Voltage	T							
D040		I/O ports with TTL buffer	2.0 V .25 VDD + 0.8 V	_	VDD VDD	V	VDD = 4.5V to 5.5V otherwise			
D041 D042 D043		with Schmitt Trigger input <sup>(4)</sup> MCLR RA4/T0CKI OSC1 (XT, HS and LP)	0.8 VDD 0.8 VDD 0.7 VDD 0.9 VDD	_ 	VDD VDD VDD VDD	V V V	(Noted)			
D043A D070	IPURB	OSC1 (in RC mode)  PORTB weak pull-up	50	200	400	μΑ	(Note1)  VDD = 5.0V, VPIN = VSS			
	liL	current Input Leakage Current <sup>(2), (3)</sup>								
D060 D061 D063		I/O ports (Except PORTA) PORTA <sup>(4)</sup> RA4/T0CKI OSC1, MCLR	_ _ _ _	_ _ _	±1.0 ±0.5 ±1.0 ±5.0	μΑ μΑ μΑ μΑ	VSS ≤ VPIN ≤ VDD, pin at hi-impedance VSS ≤ VPIN ≤ VDD, pin at hi-impedance VSS ≤ VPIN ≤ VDD VSS ≤ VPIN ≤ VDD, XT, HS and LP osc configuration			
	Vol	Output Low Voltage	•							
D080		I/O ports <sup>(4)</sup>			0.6 0.6	V	IOL=8.5 mA, VDD=4.5 V, -40° to +85°C IOL=7.0 mA, VDD=4.5 V, +85° to +125°C			
	Voн	Output High Voltage <sup>(3)</sup>								
D090		I/O ports (Except RA4 <sup>(4)</sup>	VDD-0.7 VDD-0.7	_	_	V	IOH=-3.0 mA, VDD=4.5 V, -40° to +85°C IOH=-2.5 mA, VDD=4.5 V, +85° to +125°C			
D150	Vod	Open-Drain High Voltage	_	_	8.5*	V	RA4 pin PIC16F627A/628A/648A, PIC16LF627A/628A/648A			
		Capacitive Loading Specs on	Output Pins			•				
D100*	COSC2	OSC2 pin	_	_	15	pF	In XT, HS and LP modes when external clock used to drive OSC1.			
D101*	Cio	All I/O pins/OSC2 (in RC mode)	_	_	50	pF				

<sup>\*</sup> These parameters are characterized but not tested.

<sup>†</sup> Data in "Typ" column is at 5.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Note 1: In RC oscillator configuration, the OSC1 pin is a Schmitt Trigger input. It is not recommended that the PIC16F627A/628A/648A be driven with external clock in RC mode.

<sup>2:</sup> The leakage current on the MCLR pin is strongly dependent on applied voltage level. The specified levels represent normal operating conditions. Higher leakage current may be measured at different input voltages.

<sup>3:</sup> Negative current is defined as coming out of the pin.

<sup>4:</sup> Includes OSC1 and OSC2 when configured as I/O pins, CLKIN, or CLKOUT.

TABLE 17-1: DC Characteristics: PIC16F627A/628A/648A (Industrial, Extended) PIC16LF627A/628A/648A (Industrial)

DC Characteristics			Standard Operating Conditions (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial and $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for extended  Operating voltage VDD range as described in DC spec Table 17-2 and Table 17						
Parameter No.	Sym	Characteristic	Min	Тур†	Max	Units	Conditions		
		Data EEPROM Memory							
D120 D120A D121	Ed Ed Vdrw	Endurance Endurance VDD for read/write	100K 10K VMIN	1M 100K	 5.5	E/W E/W V	-40°C ≤ TA ≤ 85°C 85°C ≤ TA ≤ 125°C VMIN = Minimum operating		
			VIVIIN				voltage		
D122	TDEW	Erase/Write cycle time	_	4	8*	ms			
D123	TRETD	Characteristic Retention	100	_	_	Year	Provided no other specifications are violated		
D124	TREF	Number of Total Erase/Write Cycles before Refresh <sup>(1)</sup>	1M	10M	_	E/W	-40°C to +85°C		
		Program Flash Memory							
D130	EР	Endurance	10K	100K	_	E/W	-40°C ≤ TA ≤ 85°C		
D130A	EР	Endurance	1000	10K	_	E/W	85°C ≤ Ta ≤ 125°C		
D131	VPR	VDD for read	VMIN	_	5.5	V	VMIN = Minimum operating voltage		
D132	VIE	VDD for Block erase	4.5		5.5	V			
D132A	VPEW	VDD for write	VMIN	_	5.5	V	VMIN = Minimum operating voltage		
D133	TIE	Block Erase cycle time	_	4	8*	ms	VDD > 4.5V		
D133A	TPEW	Write cycle time	_	2	4*	ms			
D134	TRETP	Characteristic Retention	100	_	_	year	Provided no other specifications are violated		

<sup>\*</sup> These parameters are characterized but not tested.

Note 1: Refer to Section 13.7 "Using the Data EEPROM" for a more detailed discussion on data EEPROM endurance.

<sup>†</sup> Data in "Typ" column is at 5.0 V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

TABLE 17-2: COMPARATOR SPECIFICATIONS

	Operating Conditions: 2.0V $<$ VDD $<$ 5.5V, $-40^{\circ}$ C $<$ TA $<$ $+125^{\circ}$ C, unless otherwise stated.										
Param No.	Characteristics	Sym	Min	Тур	Max	Units	Comments				
D300	Input Offset Voltage	VIOFF	_	±5.0	±10	mV					
D301	Input Common Mode Voltage	VICM	0	_	VDD - 1.5*	V					
D302	Common Mode Rejection Ratio	CMRR	55*	_	_	db					
D303	Response Time <sup>(1)</sup>	TRESP	_	300	400*	ns	VDD = 3.0V to 5.5V -40° to +85°C				
			_	400	600*	ns	VDD = 3.0V to 5.5V -85° to +125°C				
			_	400	600*	ns	VDD = 2.0V to 3.0V -40° to +85°C				
D304	Comparator Mode Change to Output Valid	TMC2OV	_	300	10*	μS					

<sup>\*</sup> These parameters are characterized but not tested.

Note 1: Response time measured with one comparator input at (VDD - 1.5)/2 while the other input transitions from Vss to VDD.

**TABLE 17-3: VOLTAGE REFERENCE SPECIFICATIONS** 

	Operating Conditions: 2.0V < VDD < 5.5V, -40°C < TA < +125°C, unless otherwise stated.										
Spec No.	Characteristics	Sym	Min	Тур	Max	Units	Comments				
D310	Resolution	VRES		_	VDD/24 VDD/32	LSb LSb	Low Range (VRR = 1) High Range (VRR = 0)				
D311	Absolute Accuracy	VRAA		_	1/4 <sup>(2)</sup> * 1/2 <sup>(2)</sup> *	LSb LSb	Low Range (VRR = 1) High Range (VRR = 0)				
D312	Unit Resistor Value (R)	VRur	_	2k*	_	Ω					
D313	Settling Time <sup>(1)</sup>	TSET	_	_	10*	μS					

<sup>\*</sup> These parameters are characterized but not tested.

Note 1: Settling time measured while VRR = 1 and VR<3:0> transitions from 0000 to 1111.

<sup>2:</sup> When VDD is between 2.0V and 3.0V the VREF output voltage levels on RA2 described by the equation:[VDD/2 ± (3-VDD)/2] may cause the Absolute Accuracy (VRAA) of the VREF output signal on RA2 to be greater than the stated max.

#### 17.5 Timing Parameter Symbology

The timing parameter symbols have been created with one of the following formats:

- 1. TppS2ppS
- 2. TppS

mc


T				
F	Frequency	Т	Time	
Lowercas	e subscripts (pp) and their meanings:			
рр				
ck	CLKOUT	osc	OSC1	
io	I/O port	t0	T0CKI	

Uppercase letters and their meanings:

**MCLR** 

	opportunity to the control of the co									
S										
F	Fall	Р	Period							
Н	High	R	Rise							
1	Invalid (Hi-impedance)	V	Valid							
L	Low	Z	Hi-Impedance							

#### FIGURE 17-3: LOAD CONDITIONS



#### 17.6 Timing Diagrams and Specifications

FIGURE 17-4: EXTERNAL CLOCK TIMING




TABLE 17-4: EXTERNAL CLOCK TIMING REQUIREMENTS

Parameter No.	Sym	Characteristic	Min	Тур†	Max	Units	Conditions		
	Fosc	External CLKIN Frequency <sup>(1)</sup>	DC	_	4	MHz	XT and RC Osc mode, VDD = 5.0 V		
			DC	_	20	MHz	HS, EC Osc mode		
			DC	_	200	kHz	LP Osc mode		
		Oscillator Frequency <sup>(1)</sup>	_	_	4	MHz	RC Osc mode, VDD = 5.0V		
			0.1	_	4	MHz	XT Osc mode		
			1 —		20 200	MHz kHz	HS Osc mode LP Osc mode		
			_	4	_	MHz	INTOSC mode (fast)		
			_	37	_	kHz	INTOSC mode (slow)		
1	Tosc	External CLKIN Period <sup>(1)</sup>	250	_	_	ns	XT and RC Osc mode		
			50	_	_	ns	HS, EC Osc mode		
			5	_	— μs		LP Osc mode		
		Oscillator Period <sup>(1)</sup>	250	_	_	ns	RC Osc mode		
			250		10,000	ns	XT Osc mode		
			50		1,000	ns	HS Osc mode		
			5	_	_	μs	LP Osc mode		
				250		ns	INTOSC mode (fast)		
			_	27	_	μs	INTOSC mode (slow)		
2	Tcy	Instruction Cycle Time	200	TCY	DC	ns	Tcy = 4/Fosc		
3	TosL, TosH	External CLKIN (OSC1) High External CLKIN Low	100*	_	_	ns	XT oscillator, Tosc L/H duty cycle		
4	RC	External Biased RC Frequency	10 kHz*	_	4 MHz	_	VDD = 5.0V		

<sup>\*</sup> These parameters are characterized but not tested.

**Note:** Instruction cycle period (Tcy) equals four times the input oscillator time-based period. All specified values are based on characterization data for that particular oscillator type under standard operating conditions with the device executing code. Exceeding these specified limits may result in an unstable oscillator operation and/or higher than expected current consumption. All devices are tested to operate at "Min" values with an external clock applied to the OSC1 pin. When an external clock input is used, the "Max" cycle time limit is "DC" (no clock) for all devices.

<sup>†</sup> Data in "Typ" column is at 5.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

TABLE 17-5: PRECISION INTERNAL OSCILLATOR PARAMETERS

Parameter No.	Sym	Characteristic	Min	Тур	Max	Units	Conditions
F10	Fiosc	Oscillator Center frequency		4	_	MHz	
F13	Δlosc	Oscillator Stability (jitter)	_	_	±1	%	VDD = 3.5 V, 25°C
		, and the same of	_	_	±2	%	$2.0 \text{ V} \le \text{VDD} \le 5.5 \text{V}$ $0^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$
			_	_	±5	%	$2.0 \text{ V} \le \text{VDD} \le 5.5 \text{V}$ - $40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C} \text{ (IND)}$ - $40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C} \text{ (EXT)}$
F14	Tioscst	Oscillator Wake-up from Sleep start-up time	_	6	TBD	μs	$VDD = 2.0V, -40^{\circ}C \text{ to } +85^{\circ}C$
			_	4	TBD	μs	$VDD = 3.0V, -40^{\circ}C \text{ to } +85^{\circ}C$
			_	3	TBD	μs	$VDD = 5.0V, -40^{\circ}C \text{ to } +85^{\circ}C$







TABLE 17-6: CLKOUT AND I/O TIMING REQUIREMENTS

Parameter No.	Sym	Characteristic		Min	Тур†	Max	Units
10	TosH2ckL	OSC1↑ to CLKOUT↓	PIC16F62X	_	75	200*	ns
10A			PIC16LF62X	_	_	400*	ns
11	TosH2ckH	OSC1↑ to CLKOUT↑	PIC16F62X	_	75	200*	ns
11A			PIC16LF62X	_	_	400*	ns
12	TckR	CLKOUT rise time	PIC16F62X	_	35	100*	ns
12A			PIC16LF62X	_	_	200*	ns
13	TckF	CLKOUT fall time	PIC16F62X	_	35	100*	ns
13A			PIC16LF62X	_		200*	ns
14	TckL2ioV	CLKOUT ↓ to Port out valid		_	_	20*	ns
15	TioV2ckH	Port in valid before CLKOUT ↑	PIC16F62X	Tosc+200 ns*		_	ns
			PIC16LF62X	Tosc+400 ns*		_	ns
16	TckH2ioI	Port in hold after CLKOUT ↑	0		_	ns	
17	TosH2ioV	OSC1 <sup>↑</sup> (Q1 cycle) to	PIC16F62X	_	50	150*	ns
		Port out valid	PIC16LF62X	_		300*	ns
18	TosH2iol	OSC1↑ (Q2 cycle) to Port input inva (I/O in hold time)	100* 200*	_	_	ns	

<sup>\*</sup> These parameters are characterized but not tested.

FIGURE 17-6: RESET, WATCHDOG TIMER, OSCILLATOR START-UP TIMER AND POWER-UP TIMER TIMING



<sup>†</sup> Data in "Typ" column is at 5.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

#### FIGURE 17-7: BROWN-OUT DETECT TIMING




TABLE 17-7: RESET, WATCHDOG TIMER, OSCILLATOR START-UP TIMER AND POWER-UP TIMER REQUIREMENTS

Parameter No.	Sym	Characteristic	Min	Тур†	Max	Units	Conditions
30	TmcL	MCLR Pulse Width (low)	2000 TBD	— TBD	— TBD	ns ms	VDD = 5V, -40°C to +85°C Extended temperature
31	Twdt	Watchdog Timer Time out Period (No Prescaler)	7* TBD	18 TBD	33* TBD	ms ms	VDD = 5V, -40°C to +85°C Extended temperature
32	Tost	Oscillation Start-up Timer Period	_	1024Tosc	_	_	Tosc = OSC1 period
33	Tpwrt	Power-up Timer Period	28* TBD	72 TBD	132* TBD	ms ms	VDD = 5V, -40°C to +85°C Extended temperature
34	TIOZ	I/O Hi-impedance from MCLR Low or Watchdog Timer Reset	_		2.0*	μs	
35	TBOR	Brown-out Reset pulse width	100*	_	_	μs	VDD ≤ VBOR (D005)

<sup>\*</sup> These parameters are characterized but not tested.

#### FIGURE 17-8: TIMERO AND TIMER1 EXTERNAL CLOCK TIMINGS



© 2004 Microchip Technology Inc. Preliminary DS40044B-page 143

<sup>†</sup> Data in "Typ" column is at 5.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.


TABLE 17-8: TIMERO AND TIMER1 EXTERNAL CLOCK REQUIREMENTS

Param No.	Sym	Characteristic			Min	Тур†	Max	Units	Conditions
40	Tt0H	T0CKI High Pu	lse Width	No Prescaler	0.5Tcy + 20*	_	_	ns	
				With Prescaler	10*	_	_	ns	
41	TtOL	Γ0CKI Low Pulse Width		No Prescaler	0.5Tcy + 20*	_	_	ns	
			With Prescale			_	_	ns	
42	Tt0P	TOCKI Period			Greater of: TCY + 40* N	_	_	ns	N = prescale value (2, 4,, 256)
45	Tt1H	T1CKI High	Synchronous,	No Prescaler	0.5Tcy + 20*	_	_	ns	
		Time	Synchronous,	PIC16F62X	15*		_	ns	
			with Prescaler		25*	_	_	ns	
			Asynchronous		30*	_		ns	
				PIC16LF62X	50*	_	1	ns	
46	Tt1L	T1CKI Low	Synchronous,	No Prescaler	0.5Tcy + 20*	_	1	ns	
		Time	Synchronous,	PIC16F62X	15*	_		ns	
			with Prescaler		25*		_	ns	
			Asynchronous		30*		_	ns	
				PIC16LF62X	50*	—		ns	
47	Tt1P	T1CKI input period	Synchronous	PIC16F62X	Greater of: TCY + 40* N	_	_	ns	N = prescale value (1, 2, 4, 8)
				PIC16LF62X	Greater of: Tcy + 40* N	_	_	_	
			Asynchronous		60*			ns	
				PIC16LF62X	100*			ns	
	Ft1	Timer1 oscillator input frequency range (oscillator enabled by setting bit T1OSCEN)			_	32.7 <sup>(1)</sup>	_	kHz	
48		Delay from extended increment	ernal clock edge	e to timer	2Tosc	_	7Tosc	_	

<sup>\*</sup> These parameters are characterized but not tested.

**Note 1:** This oscillator is intended to work only with 32.768 kHz watch crystals and their manufactured tolerances. Higher value crystal frequencies may not be compatible with this crystal driver.

FIGURE 17-9: CAPTURE/COMPARE/PWM TIMINGS




<sup>†</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

TABLE 17-9: CAPTURE/COMPARE/PWM REQUIREMENTS

Param No.	Sym		Characteristic	Min	Тур†	Max	Units	Conditions	
50	TccL	CCP	No Prescaler		0.5Tcy + 20*	_	—	ns	
		input low time		PIC16F62X	10*	_	_	ns	
			With Prescaler	PIC16LF62X	20*	_	_	ns	
51			No Prescaler		0.5Tcy + 20*	_	_	ns	
	input high time		PIC16F62X	10*	_	_	ns		
			With Prescaler	PIC16LF62X	20*	_	_	ns	
52	TccP	CCP input period			3Tcy + 40* N	_	_	ns	N = prescale value (1,4 or 16)
53	TccR	CCP output rise	time	PIC16F62X		10	25*	ns	
				PIC16LF62X		25	45*	ns	
54	TccF	CCP output fall t	ime	PIC16F62X		10	25*	ns	
				PIC16LF62X		25	45*	ns	

These parameters are characterized but not tested.

FIGURE 17-10: TIMERO CLOCK TIMING



**TABLE 17-10: TIMERO CLOCK REQUIREMENTS** 

Parameter No.	Sym	Characteristic		Min	Тур†	Max	Units	Conditions		
40	Tt0H	T0CKI High Pulse Width	No Prescaler	0.5 Tcy + 20*	_		ns			
			With Prescaler	10*	_	_	ns			
41	Tt0L	T0CKI Low Pulse Width	No Prescaler	0.5 Tcy + 20*	_	_	ns			
			With Prescaler	10*	_	_	ns			
42	Tt0P	T0CKI Period		Tcy + 40* N	_		ns	N = prescale value (1, 2, 4,, 256)		

<sup>\*</sup> These parameters are characterized but not tested.

© 2004 Microchip Technology Inc. Preliminary DS40044B-page 145

<sup>†</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

<sup>†</sup> Data in "Typ" column is at 5.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

NOTES:

#### 18.0 DC AND AC CHARACTERISTICS GRAPHS AND TABLES


Not Available at this time.

NOTES:

#### 19.0 PACKAGING INFORMATION

#### 19.1 Package Marking Information

#### 18-LEAD PDIP (.300")



#### 18-LEAD SOIC (.300")



#### 20-LEAD SSOP



#### 28-LEAD QFN



Note:

#### **EXAMPLE**



#### **EXAMPLE**



#### **EXAMPLE**



#### **EXAMPLE**




Legend: XX...X Customer specific information\*

YY Year code (last 2 digits of calendar year)
WW Week code (week of January 1 is week '01')
NNN Alphanumeric traceability code

In the event the full Microchip part number cannot be marked on one line, it will be carried over to the next line thus limiting the number of available characters for customer specific information.

Standard PICmicro device marking consists of Microchip part number, year code, week code, and traceability code. For PICmicro device marking beyond this, certain price adders apply. Please check with your Microchip Sales Office. For QTP devices, any special marking adders are included in QTP price.

#### 18-Lead Plastic Dual In-line (P) - 300 mil (PDIP)



	Units		INCHES*		MILLIMETERS			
Dimension	Limits	MIN	NOM	MAX	MIN	NOM	MAX	
Number of Pins	n		18			18		
Pitch	р		.100			2.54		
Top to Seating Plane	Α	.140	.155	.170	3.56	3.94	4.32	
Molded Package Thickness	A2	.115	.130	.145	2.92	3.30	3.68	
Base to Seating Plane	A1	.015			0.38			
Shoulder to Shoulder Width	Е	.300	.313	.325	7.62	7.94	8.26	
Molded Package Width	E1	.240	.250	.260	6.10	6.35	6.60	
Overall Length	D	.890	.898	.905	22.61	22.80	22.99	
Tip to Seating Plane	L	.125	.130	.135	3.18	3.30	3.43	
Lead Thickness	С	.008	.012	.015	0.20	0.29	0.38	
Upper Lead Width	B1	.045	.058	.070	1.14	1.46	1.78	
Lower Lead Width	В	.014	.018	.022	0.36	0.46	0.56	
Overall Row Spacing §	eВ	.310	.370	.430	7.87	9.40	10.92	
Mold Draft Angle Top	α	5	10	15	5	10	15	
Mold Draft Angle Bottom	β	5	10	15	5	10	15	


Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" (0.254mm) per side.

JEDEC Equivalent: MS-001

Drawing No. C04-007

<sup>\*</sup> Controlling Parameter § Significant Characteristic

#### 18-Lead Plastic Small Outline (SO) - Wide, 300 mil (SOIC)




		INCHES*		MILLIMETERS			
Dimension	MIN	NOM	MAX	MIN	NOM	MAX	
Number of Pins	n		18			18	
Pitch	р		.050			1.27	
Overall Height	Α	.093	.099	.104	2.36	2.50	2.64
Molded Package Thickness	A2	.088	.091	.094	2.24	2.31	2.39
Standoff §	A1	.004	.008	.012	0.10	0.20	0.30
Overall Width	Е	.394	.407	.420	10.01	10.34	10.67
Molded Package Width	E1	.291	.295	.299	7.39	7.49	7.59
Overall Length	D	.446	.454	.462	11.33	11.53	11.73
Chamfer Distance	h	.010	.020	.029	0.25	0.50	0.74
Foot Length	L	.016	.033	.050	0.41	0.84	1.27
Foot Angle	ф	0	4	8	0	4	8
Lead Thickness	С	.009	.011	.012	0.23	0.27	0.30
Lead Width	В	.014	.017	.020	0.36	0.42	0.51
Mold Draft Angle Top	α	0	12	15	0	12	15
Mold Draft Angle Bottom	β	0	12	15	0	12	15

Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" (0.254mm) per side.

JEDEC Equivalent: MS-013 Drawing No. C04-051

<sup>\*</sup> Controlling Parameter § Significant Characteristic

#### 20-Lead Plastic Shrink Small Outline (SS) - 209 mil, 5.30 mm (SSOP)




	Units		INCHES*		N	MILLIMETERS		
Dimension	Limits	MIN	NOM	MAX	MIN	NOM	MAX	
Number of Pins	n		20			20		
Pitch	р		.026			0.65		
Overall Height	Α	.068	.073	.078	1.73	1.85	1.98	
Molded Package Thickness	A2	.064	.068	.072	1.63	1.73	1.83	
Standoff §	A1	.002	.006	.010	0.05	0.15	0.25	
Overall Width	Е	.299	.309	.322	7.59	7.85	8.18	
Molded Package Width	E1	.201	.207	.212	5.11	5.25	5.38	
Overall Length	D	.278	.284	.289	7.06	7.20	7.34	
Foot Length	L	.022	.030	.037	0.56	0.75	0.94	
Lead Thickness	С	.004	.007	.010	0.10	0.18	0.25	
Foot Angle	φ	0	4	8	0.00	101.60	203.20	
Lead Width	В	.010	.013	.015	0.25	0.32	0.38	
Mold Draft Angle Top	α	0	5	10	0	5	10	
Mold Draft Angle Bottom	β	0	5	10	0	5	10	

Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" (0.254mm) per side.

JEDEC Equivalent: MO-150 Drawing No. C04-072

<sup>\*</sup> Controlling Parameter § Significant Characteristic

#### 28-Lead Plastic Quad Flat No Lead Package (ML) 6x6 mm Body (QFN)



	Units		INCHES		М	ILLIMETERS*		
Dimension L	imits	MIN	NOM	MAX	MIN	NOM	MAX	
Number of Pins	n		28			28		
Pitch	р		.026 BSC			0.65 BSC		
Overall Height	Α		.033	.039		0.85	1.00	
Molded Package Thickness	A2		.026	.031		0.65	0.80	
Standoff	A1	.000	.0004	.002	0.00	0.01	0.05	
Base Thickness	А3		.008 REF.		0.20 REF.			
Overall Width	Е		.236 BSC		6.00 BSC			
Molded Package Width	E1		.226 BSC			5.75 BSC		
Exposed Pad Width	E2	.140	.146	.152	3.55	3.70	3.85	
Overall Length	D		.236 BSC		6.00 BSC			
Molded Package Length	D1		.226 BSC			5.75 BSC		
Exposed Pad Length	D2	.140	.146	.152	3.55	3.70	3.85	
Lead Width	В	.009	.011	.014	0.23	0.28	0.35	
Lead Length	L	.020	.024	.030	0.50	0.60	0.75	
Tie Bar Width	R	.005	.007	.010	0.13	0.17	0.23	
Tie Bar Length	Q	.012	.016	.026	0.30	0.40	0.65	
Chamfer	СН	.009	.017	.024	0.24	0.42	0.60	
Mold Draft Angle Top	α			12°			12°	

<sup>\*</sup>Controlling Parameter

Notes:
Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" (0.254mm) per side.
JEDEC equivalent: M0-220

Drawing No. C04-114

**Preliminary** © 2004 Microchip Technology Inc. DS40044B-page 153

NOTES:

# APPENDIX A: DATA SHEET REVISION HISTORY

#### **Revision A**

This is a new data sheet.

#### **Revision B**

Revised 28-Pin QFN Pin Diagram
Revised Figure 5-4 Block Diagram
Revised Register 7-1 TMR1ON
Revised Example 13-4 Data EEPROM Refresh
Routine
Revised Instruction Set SUBWF, Example 1
Revised DC Characteristics 17-2 and 17-3
Revised Tables 17-4 and 17-6
Corrected Table and Figure numbering in Section 17.0

APPENDIX B: DEVICE DIFFERENCES

The differences between the PIC16F627A/628A/648A devices listed in this data sheet are shown in Table B-1.

#### TABLE B-1: DEVICE DIFFERENCES

		Memory		
Device	Flash Program	RAM Data	EEPROM Data	
PIC16F627A	1024 x 14	224 x 8	128 x 8	
PIC16F628A	2048 x 14	224 x 8	128 x 8	
PIC16F648A	4096 x 14	256 x 8	256 x 8	

#### APPENDIX C: DEVICE MIGRATIONS

This section describes the functional and electrical specification differences when migrating between functionally similar devices. (such as from a PIC16F627 to a PIC16F627A).

#### C.1 PIC16F627/628 to a PIC16F627A/628A

- 1. ER mode is now RC mode.
- Code Protection for the Program Memory has changed from Code Protect sections of memory to Code Protect of the whole memory. The Configuration bits CP0 and CP1 in the PIC16F627/628 do not exist in the PIC16F627A/ 628A. They have been replaced with one Configuration bit<13> CP.
- "Brown-out Detect (BOD)" terminology has changed to "Brown-out Reset (BOR)" to better represent the function of the Brown-out circuitry.
- Enabling Brown-out Reset (BOR) does not automatically enable the Power-up Timer (PWRT) the way it did in the PIC16F627/628.
- 5. INTRC is now called INTOSC.
- Timer1 Oscillator is now designed for 32.768 kHz operation. In the PIC16F627/628 the Timer1 Oscillator was designed to run up to 200 kHz.
- The Dual Speed Oscillator mode only works in the INTOSC Oscillator mode. In the PIC16F627/ 628 the Dual Speed Oscillator mode worked in both the INTRC and ER Oscillator modes.

# APPENDIX D: MIGRATING FROM OTHER PICmicro DEVICES

This discusses some of the issues in migrating from other PICmicro devices to the PIC16F627A/628A/648A family of devices.

#### D.1 PIC16C62X/CE62X to PIC16F627A/628A/ 648A Migration

See Microchip web site for availability (www.microchip.com).

## D.2 PIC16C622A to PIC16F627A/628A/648A Migration

See Microchip web site for availability (www.microchip.com).

Note: This device has been designed to perform to the parameters of its data sheet. It has been tested to an electrical specification designed to determine its conformance with these parameters. Due to process differences in the manufacture of this device, this device may have different performance characteristics than its earlier version. These differences may cause this device to perform differently in your application than the earlier version of this device.

# APPENDIX E: DEVELOPMENT TOOL VERSION REQUIREMENTS

This lists the minimum requirements (software/firmware) of the specified development tool to support the devices listed in this data sheet.

MPLAB® IDE: TBD
MPLAB® SIMULATOR: TBD

MPLAB® ICE 3000:

PIC16F627A/628A/648A Processor Module:

Part Number - TBD

PIC16F627A/628A/648A Device Adapter:

Socket Part Number

 18-pin PDIP
 TBD

 18-pin SOIC
 TBD

 20-pin SSOP
 TBD

 28-pin QFN
 TBD

MPLAB® ICD: TBD

PRO MATE® II: TBD

PICSTART® Plus: TBD

MPASM™ Assembler: TBD

MPLAB® C18 C Compiler: TBD

Note: Please read all associated README.TXT

files that are supplied with the development tools. These "read me" files will discuss product support and any known

limitations.

NOTES:

#### **ON-LINE SUPPORT**

Microchip provides on-line support on the Microchip World Wide Web site.

The web site is used by Microchip as a means to make files and information easily available to customers. To view the site, the user must have access to the Internet and a web browser, such as Netscape<sup>®</sup> or Microsoft<sup>®</sup> Internet Explorer. Files are also available for FTP download from our FTP site.

#### Connecting to the Microchip Internet Web Site

The Microchip web site is available at the following URL:

#### www.microchip.com

The file transfer site is available by using an FTP service to connect to:

#### ftp://ftp.microchip.com

The web site and file transfer site provide a variety of services. Users may download files for the latest Development Tools, Data Sheets, Application Notes, User's Guides, Articles and Sample Programs. A variety of Microchip specific business information is also available, including listings of Microchip sales offices, distributors and factory representatives. Other data available for consideration is:

- Latest Microchip Press Releases
- Technical Support Section with Frequently Asked Questions
- Design Tips
- · Device Errata
- Job Postings
- · Microchip Consultant Program Member Listing
- Links to other useful web sites related to Microchip Products
- Conferences for products, Development Systems, technical information and more
- · Listing of seminars and events

## SYSTEMS INFORMATION AND UPGRADE HOT LINE

The Systems Information and Upgrade Line provides system users a listing of the latest versions of all of Microchip's development systems software products. Plus, this line provides information on how customers can receive the most current upgrade kits. The Hot Line Numbers are:

1-800-755-2345 for U.S. and most of Canada, and 1-480-792-7302 for the rest of the world.

#### **READER RESPONSE**

It is our intention to provide you with the best documentation possible to ensure successful use of your Microchip product. If you wish to provide your comments on organization, clarity, subject matter, and ways in which our documentation can better serve you, please FAX your comments to the Technical Publications Manager at (480) 792-4150.

Please list the following information, and use this outline to provide us with your comments about this document.

RE:	Reader Response	Total Pages Sent
Froi	m: Name  Company  Address  City / State / ZIP / Country  Telephone: ()	
Арр	olication (optional):	,
Wou	uld you like a reply?YN	
Dev	vice: PIC16F627A/628A/648A Literature Num	ber: DS40044B
Que	estions:	
1.	What are the best features of this document?	
2.	How does this document meet your hardware an	nd software development needs?
3.	Do you find the organization of this document ea	sy to follow? If not, why?
4.	What additions to the document do you think wo	uld enhance the structure and subject?
5.	What deletions from the document could be made	le without affecting the overall usefulness?
6.	Is there any incorrect or misleading information (	what and where)?
7.	How would you improve this document?	

INDEX		CCP1X:CCP1Y Bits	55
		CCP2CON Register	
A		CCP2M3:CCP2M0 Bits	55
A/D		CCP2X:CCP2Y Bits	55
Special Event Trigger (CCP)	57	Clocking Scheme/Instruction Cycle	
Absolute Maximum Ratings		CLRF Instruction	115
ADDLW Instruction		CLRW Instruction	116
ADDWF Instruction	113	CLRWDT Instruction	116
ANDLW Instruction	113	Code Examples	
ANDWF Instruction		Data EEPROM Refresh Routine	92
Architectural Overview	9	Code Protection	108
Assembler		COMF Instruction	116
MPASM Assembler	125	Comparator	
		Block Diagrams	
В		I/O Operating Modes	62
Baud Rate Error	71	Modified Comparator Output	64
Baud Rate Formula	71	Comparator Module	61
BCF Instruction	114	Configuration	62
Block Diagrams		Interrupts	65
Comparator		Operation	63
I/O Operating Modes	62	Reference	
Modified Comparator Output		Compare (CCP Module)	56
I/O Ports		Block Diagram	56
RB0/INT Pin	37	CCP Pin Configuration	57
RB1/RX/DT Pin		CCPR1H:CCPR1L Registers	56
RB2/TX/CK Pin		Software Interrupt	57
RB3/CCP1 Pin		Special Event Trigger	57
RB4/PGM Pin		Timer1 Mode Selection	57
RB5 Pin		Configuration Bits	93
RB6/T1OSO/T1CKI Pin		Crystal Operation	95
RB7/T1OSI Pin	42		
RC Oscillator Mode	96	D	
USART Receive	79	Data EEPROM Memory	89
USART Transmit	77	EECON1 Register	89
BRGH bit	71	EECON2 Register	89
Brown-Out Detect (BOD)	98	Operation During Code Protection	92
BSF Instruction		Reading	91
BTFSC Instruction	114	Spurious Write Protection	91
BTFSS Instruction	115	Using	92
		Write Verify	91
C		Writing to	91
C Compilers		Data Memory Organization	15
MPLAB C17	126	DECF Instruction	116
MPLAB C18	126	DECFSZ Instruction	117
MPLAB C30	126	Demonstration Boards	
CALL Instruction	115	PICDEM 1	128
Capture (CCP Module)	56	PICDEM 17	129
Block Diagram	56	PICDEM 18R	129
CCP Pin Configuration		PICDEM 2 Plus	128
CCPR1H:CCPR1L Registers		PICDEM 3	128
Changing Between Capture Prescalers		PICDEM 4	128
Prescaler	56	PICDEM LIN	129
Software Interrupt	56	PICDEM USB	129
Timer1 Mode Selection	56	PICDEM.net Internet/Ethernet	128
Capture/Compare/PWM (CCP)	55	Development Support	125
Capture Mode. See Capture		Development Tool Version Requirements	157
CCP1		Device Differences	
CCPR1H Register	55	Device Migrations	
CCPR1L Register		Dual-speed Oscillator Modes	97
CCP2	55		
Compare Mode. See Compare			
PWM Mode. See PWM			
Timer Resources	55		
CCP1CON Register			
CCP1M3·CCP1M0 Rite	55		

E	RRF 1	22
EECON1 register90	SLEEP1	22
EECON2 register 90	SUBLW 1	22
Errata	SUBWF1	23
Evaluation and Programming Tools	SWAPF1	23
External Crystal Oscillator Circuit	TRIS 1	23
External orystal oscillator offcult	XORLW1	24
G	XORWF 1	24
General-Purpose Register File15	Instruction Set Summary1	11
GOTO Instruction	INT Interrupt1	05
OTO Instruction	INTCON Register	24
I	Interrupt Sources	
I/O Ports31	Capture Complete (CCP)	
Bi-Directional	Compare Complete (CCP)	57
Block Diagrams	TMR2 to PR2 Match (PWM)	58
RB0/INT Pin37	Interrupts1	04
RB1/RX/DT Pin	Interrupts, Enable Bits	
RB2/TX/CK Pin38	CCP1 Enable (CCP1IE Bit)	56
RB3/CCP1 Pin	Interrupts, Flag Bits	
RB4/PGM Pin39	CCP1 Flag (CCP1IF Bit)	
RB5 Pin40	IORLW Instruction 1	
RB6/T1OSO/T1CKI Pin41	IORWF Instruction 1	.19
RB7/T1OSI Pin42	М	
PORTA31	<del></del>	
PORTB36	Memory Organization	
Programming Considerations44	Data EEPROM Memory 89, 91,	
Successive Operations44	Migrating from other PICmicro Devices 1	
TRISA31	MOVF Instruction1	
TRISB36	MOVLW Instruction 1	
ID Locations108	MOVWF Instruction 1	
INCF Instruction118	MPLAB ASM30 Assembler, Linker, Librarian 1	
INCFSZ Instruction118	MPLAB ICD 2 In-Circuit Debugger 1	
In-Circuit Serial Programming109	MPLAB ICE 2000 High-Performance Universal In-Circuit E	
Indirect Addressing, INDF and FSR Registers28	ulator1	
Instruction Flow/Pipelining13	MPLAB ICE 4000 High-Performance Universal In-Circuit E	
Instruction Set	ulator	
ADDLW113	MPLAB Integrated Development Environment Software 1	
ADDWF113	MPLAB PM3 Device Programmer	
ANDLW113	MPLINK Object Linker/MPLIB Object Librarian 1	26
ANDWF113	N	
BCF114		
BSF114	NOP Instruction 1	20
BTFSC114	0	
BTFSS115	_	200
CALL115	OPTION Instruction	20
CLRF115		
CLRW116	Oscillator Configurations Oscillator Start-up Timer (OST)	
CLRWDT116	Oscillator Start-up Tillier (OST)	90
COMF116	P	
DECF116	Package Marking Information1	110
DECFSZ117	Packaging Information	
GOTO117	PCL and PCLATH	
INCF	Stack	
INCFSZ118	PCON Register	
IORLW119	PICkit 1 Flash Starter Kit	
IORWF119	PICSTART Plus Development Programmer	
MOVF119	PIE1 Register	
MOVLW119	Pin Functions	
MOVWF120	RC6/TX/CK69–	-86
NOP	RC7/RX/DT	
OPTION	PIR1 Register	
RETFIE120	Port RB Interrupt	
RETLIN121	PORTA	
RETURN121	PORTB	
RLF121	. 32	-

Power Control/Status Register (PCON)		Timer0 Module	45
Power-Down Mode (SLEEP)	107	Timer1	
Power-On Reset (POR)	98	Asynchronous Counter Mode	50
Power-up Timer (PWRT)	98	Capacitor Selection	51
PR2 Register	52, 58	External Clock Input	49
PRO MATE II Universal Device Programmer	127	External Clock Input Timing	50
Program Memory Organization		Oscillator	51
PWM (CCP Module)	58	Prescaler	49, 51
Block Diagram		Resetting Timer1	51
Simplified PWM	58	Resetting Timer1 Registers	
CCPR1H:CCPR1L Registers	58	Special Event Trigger (CCP)	57
Duty Cycle	59	Synchronized Counter Mode	49
Example Frequencies/Resolutions	59	Timer Mode	49
Period	58	TMR1H	50
Set-Up for PWM Operation	59	TMR1L	50
TMR2 to PR2 Match	58	Timer2	
•		Block Diagram	52
Q		Postscaler	52
Q-Clock	59	PR2 register	52
Quick-Turnaround-Production (QTP) Devices	7	Prescaler	52, 59
<b>-</b>		Timer2 Module	52
R		TMR2 output	52
RC Oscillator	96	TMR2 to PR2 Match Interrupt	
RC Oscillator Mode		Timing Diagrams	
Block Diagram	96	Timer0	143
Registers		Timer1	143
Maps		USART	
PIC16F627A	16, 17	Asynchronous Receiver	80
PIC16F628A	16, 17	USART Asynchronous Master Transmission	
Reset	97	USART Asynchronous Reception	
RETFIE Instruction	120	USART RX Pin Sampling	
RETLW Instruction	121	USART Synchronous Reception	
RETURN Instruction	121	USART Synchronous Transmission	
Revision History		Timing Diagrams and Specifications	
RLF Instruction	121	TMR0 Interrupt	
RRF Instruction	122	TMR1CS bit	
		TMR10N bit	48
S		TMR2ON bit	53
Serial Communication Interface (SCI) Module, See	USART	TOUTPS0 bit	53
Serialized Quick-Turnaround-Production (SQTP) D		TOUTPS1 bit	53
SLEEP Instruction	122	TOUTPS2 bit	53
Software Simulator (MPLAB SIM)	126	TOUTPS3 bit	53
Software Simulator (MPLAB SIM30)		TRIS Instruction	
Special Event Trigger. See Compare		TRISA	31
Special Features of the CPU	93	TRISB	36
Special Function Registers			
Status Register		U	
SUBLW Instruction	122	Universal Synchronous Asynchronous Receiver Trans	smitter
SUBWF Instruction		(USART)	
SWAPF Instruction	123	Asynchronous Receiver	
		Setting Up Reception	82
T		Asynchronous Receiver Mode	
T1CKPS0 bit	48	Address Detect	82
T1CKPS1 bit		Block Diagram	
T1OSCEN bit		USART	
T1SYNC bit		Asynchronous Mode	76
T2CKPS0 bit		Asynchronous Receiver	
T2CKPS1 bit		Asynchronous Reception	
Timer0		Asynchronous Transmission	
Block Diagrams		Asynchronous Transmitter	
Timer0/WDT	46	Baud Rate Generator (BRG)	
External Clock Input		Block Diagrams	1
Interrupt		Transmit	77
Prescaler		USART Receive	
Switching Prescaler Assignment		BRGH bit	
			1

72, 73, 74
83
85
83
86
87
86
67
67
106
3
124
124 12 <i>4</i>

#### PRODUCT IDENTIFICATION SYSTEM

To order or obtain information, e.g., on pricing or delivery, refer to the factory or the listed sales office.

PART NO. Device	-X /XX XXX       Temperature Package Pattern Range	Examples:  a) PIC16F627A - E/P 301 = Extended Temp., PDIP package, 20 MHz, normal VDD limits, QTP pattern #301.
Device	PIC16F627A/628A/648A:Standard VDD range 3.0V to 5.5V PIC16F627A/628A/648ATVDD range 3.0V to 5.5V (Tape and Reel) PIC16LF627A/628A/648A:VDD range 2.0V to 5.5V PIC16LF627A/628A/648AT:VDD range 2.0V to 5.5V (Tape and Reel)	<ul> <li>b) PIC16LF627A - I/SO = Industrial Temp., SOIC package, 20 MHz, extended VDD limits.</li> </ul>
Temperature Range	I = -40°C to +85°C E = -40°C to +125°C	
Package	P = PDIP SO = SOIC (Gull Wing, 300 mil body) SS = SSOP (209 mil) ML = QFN (28 Lead)	
Pattern	3-Digit Pattern Code for QTP (blank otherwise).	

<sup>\*</sup> JW Devices are UV erasable and can be programmed to any device configuration. JW Devices meet the electrical requirement of each oscillator type.

#### **Sales and Support**

#### **Data Sheets**

Products supported by a preliminary Data Sheet may have an errata sheet describing minor operational differences and recommended workarounds. To determine if an errata sheet exists for a particular device, please contact one of the following:

- 1. Your local Microchip sales office
- 2. The Microchip Corporate Literature Center U.S. FAX: (480) 792-7277
- 3. The Microchip Worldwide Site (www.microchip.com)

Please specify which device, revision of silicon and Data Sheet (include Literature #) you are using.

#### **New Customer Notification System**

Register on our web site (www.microchip.com/cn) to receive the most current information on our products.

© 2004 Microchip Technology Inc. Preliminary DS40044B-page 165



#### WORLDWIDE SALES AND SERVICE

#### **AMERICAS**

**Corporate Office** 

2355 West Chandler Blvd. Chandler, AZ 85224-6199 Tel: 480-792-7200

Fax: 480-792-7277 Technical Support: 480-792-7627 Web Address: http://www.microchip.com

Atlanta

3780 Mansell Road, Suite 130 Alpharetta, GA 30022 Tel: 770-640-0034 Fax: 770-640-0307

**Boston** 

2 Lan Drive, Suite 120 Westford, MA 01886 Tel: 978-692-3848 Fax: 978-692-3821

Chicago

333 Pierce Road, Suite 180 Itasca, IL 60143 Tel: 630-285-0071 Fax: 630-285-0075

**Dallas** 

4570 Westgrove Drive, Suite 160 Addison, TX 75001 Tel: 972-818-7423 Fax: 972-818-2924

Detroit

Tri-Atria Office Building 32255 Northwestern Highway, Suite 190 Farmington Hills, MI 48334

Tel: 248-538-2250 Fax: 248-538-2260 **Kokomo** 

2767 S. Albright Road Kokomo, IN 46902 Tel: 765-864-8360 Fax: 765-864-8387

Los Angeles

18201 Von Karman, Suite 1090 Irvine, CA 92612 Tel: 949-263-1888 Fax: 949-263-1338

San Jose

1300 Terra Bella Avenue Mountain View, CA 94043 Tel: 650-215-1444 Fax: 650-961-0286

**Toronto** 

6285 Northam Drive, Suite 108 Mississauga, Ontario L4V 1X5, Canada

Tel: 905-673-0699 Fax: 905-673-6509

#### ASIA/PACIFIC

Australia

Suite 22, 41 Rawson Street Epping 2121, NSW Australia

Tel: 61-2-9868-6733 Fax: 61-2-9868-6755 China - Beijing

Unit 706B Wan Tai Bei Hai Bldg. No. 6 Chaoyangmen Bei Str. Beijing, 100027, China Tel: 86-10-85282100 Fax: 86-10-85282104

China - Chengdu

Rm. 2401-2402, 24th Floor, Ming Xing Financial Tower No. 88 TIDU Street Chengdu 610016, China Tel: 86-28-86766200 Fax: 86-28-86766599

China - Fuzhou

Unit 28F, World Trade Plaza No. 71 Wusi Road Fuzhou 350001, China Tel: 86-591-7503506 Fax: 86-591-7503521

China - Hong Kong SAR

Unit 901-6, Tower 2, Metroplaza 223 Hing Fong Road Kwai Fong, N.T., Hong Kong Tel: 852-2401-1200 Fax: 852-2401-3431

China - Shanghai

Room 701, Bldg. B Far East International Plaza No. 317 Xian Xia Road Shanghai, 200051 Tel: 86-21-6275-5700 Fax: 86-21-6275-5060

China - Shenzhen

Rm. 1812, 18/F, Building A, United Plaza No. 5022 Binhe Road, Futian District

Shenzhen 518033, China Tel: 86-755-82901380 Fax: 86-755-8295-1393

China - Shunde

Room 401, Hongjian Building, No. 2 Fengxiangnan Road, Ronggui Town, Shunde District, Foshan City, Guangdong 528303, China Tel: 86-757-28395507 Fax: 86-757-28395571

China - Qingdao

Rm. B505A, Fullhope Plaza, No. 12 Hong Kong Central Rd. Qingdao 266071, China

Tel: 86-532-5027355 Fax: 86-532-5027205

India

Divyasree Chambers 1 Floor, Wing A (A3/A4) No. 11, O'Shaugnessey Road Bangalore, 560 025, India Tel: 91-80-2290061 Fax: 91-80-2290062

Japan

Benex S-1 6F 3-18-20, Shinyokohama Kohoku-Ku, Yokohama-shi Kanagawa, 222-0033, Japan Tel: 81-45-471-6166 Fax: 81-45-471-6122 Korea

168-1, Youngbo Bldg. 3 Floor Samsung-Dong, Kangnam-Ku Seoul, Korea 135-882 Tel: 82-2-554-7200 Fax: 82-2-558-5932 or

82-2-558-5934

**Singapore** 200 Middle Road #07-02 Prime Centre Singapore, 188980

Tel: 65-6334-8870 Fax: 65-6334-8850

Taiwan

Kaohsiung Branch 30F - 1 No. 8 Min Chuan 2nd Road Kaohsiung 806, Taiwan Tel: 886-7-536-4818 Fax: 886-7-536-4803

Taiwan

Taiwan Branch 11F-3, No. 207 Tung Hua North Road Taipei, 105, Taiwan

Tel: 886-2-2717-7175 Fax: 886-2-2545-0139

#### **EUROPE**

Austria

Durisolstrasse 2 A-4600 Wels Austria Tel: 43-7242-2244-399

Tel: 43-7242-2244-399 Fax: 43-7242-2244-393

Denmark

Regus Business Centre Lautrup hoj 1-3 Ballerup DK-2750 Denmark Tel: 45-4420-9895 Fax: 45-4420-9910

France

Parc d'Activite du Moulin de Massy 43 Rue du Saule Trapu Batiment A - ler Etage 91300 Massy, France Tel: 33-1-69-53-63-20 Fax: 33-1-69-30-90-79

Germany

Steinheilstrasse 10 D-85737 Ismaning, Germany Tel: 49-89-627-144-0 Fax: 49-89-627-144-44

Italy

Via Quasimodo, 12 20025 Legnano (MI) Milan, Italy Tel: 39-0331-742611 Fax: 39-0331-466781

Netherlands

P. A. De Biesbosch 14 NL-5152 SC Drunen, Netherlands Tel: 31-416-690399

Fax: 31-416-690340 United Kingdom

505 Eskdale Road Winnersh Triangle Wokingham Berkshire, England RO

Berkshire, England RG41 5TU Tel: 44-118-921-5869 Fax: 44-118-921-5820

01/26/04